


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒

<b>APPLICATION FOR PERMIT TO DRILL</b>						<b>1. WELL NAME and NUMBER</b> IWM SWD 3-30 B4							
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						<b>3. FIELD OR WILDCAT</b> ALTAMONT							
<b>4. TYPE OF WELL</b> Water Disposal Well Coalbed Methane Well: NO						<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b>							
<b>6. NAME OF OPERATOR</b> INTEGRATED WATER MANAGEMENT LLC						<b>7. OPERATOR PHONE</b> 435 722-3555							
<b>8. ADDRESS OF OPERATOR</b> PO Box 816, Roosevelt, UT, 84066						<b>9. OPERATOR E-MAIL</b> rballou@stratanet.com							
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> 3691			<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>							
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b> Integrated Water Management						<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b> 435-454-4646							
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b> PO Box 430, Altamont, UT 84001						<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b> rballou@stratanet.com							
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>			<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			<b>19. SLANT</b> VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>							
<b>20. LOCATION OF WELL</b>		<b>FOOTAGES</b>		<b>QTR-QTR</b>		<b>SECTION</b>		<b>TOWNSHIP</b>		<b>RANGE</b>		<b>MERIDIAN</b>	
<b>LOCATION AT SURFACE</b>		300 FSL 800 FEL		SESE		30		2.0 S		4.0 W		U	
<b>Top of Uppermost Producing Zone</b>		300 FSL 800 FEL		SESE		30		2.0 S		4.0 W		U	
<b>At Total Depth</b>		300 FSL 800 FEL		SESE		30		2.0 S		4.0 W		U	
<b>21. COUNTY</b> DUCHESNE			<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 300			<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 90							
			<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 1632			<b>26. PROPOSED DEPTH</b> MD: 5500 TVD: 5500							
<b>27. ELEVATION - GROUND LEVEL</b> 1632			<b>28. BOND NUMBER</b> RLB0013838			<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> Integrated Facility							
<b>Hole, Casing, and Cement Information</b>													
<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Length</b>	<b>Weight</b>	<b>Grade &amp; Thread</b>	<b>Max Mud Wt.</b>	<b>Cement</b>		<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>		
<b>SURF</b>	12.25	9.625	0 - 500	32.3	J-55 ST&C	9.0	Class G		230	1.15	15.8		
<b>I1</b>	8.75	7	0 - 5500	23.0	J-55 LT&C	9.0	Premium Lite High Strength		320	1.69	13.1		
<b>ATTACHMENTS</b>													
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>													
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN							
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input checked="" type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER							
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP							
<b>NAME</b> Robert Ballou					<b>TITLE</b> President					<b>PHONE</b> 435 722-3555			
<b>SIGNATURE</b>					<b>DATE</b> 05/04/2011					<b>EMAIL</b> rballou@stratanet.com			
<b>API NUMBER ASSIGNED</b> 43013507530000					<b>APPROVAL</b>  Permit Manager								

## INTEGRATED WATER MANAGEMENT

IWM SWD 3-30 B4

SE/SE SECTION 30, 2S 4W DUCHESNE CO., UT

Surface owner: Integrated Water Management

PO Box 430 Altamont, UT 84001

435-454-4646

DRILLING PROGRAM1 GEOLOGIC SURFACE FORMATION:

Duchesne River Formation of Oligocene Age.

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS OR FMS.

Duchesne River Fm 0-1500'

Uintah Fm 1500-2500'

Green River 2500-5500'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS

Fresh water may be encountered in the Duchesne river Fm, but would not be expected below about 350', no economic oil or gas anticipated. All production in area > 8000'. Well is being drilled to encounter sands suitable for injecting as SWD well.

4. PROPOSED CASING /CEMENTING PROGRAM**Casing Design****IWM SWD 3-30****B4**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface Casing 9-5/8"	0	500'	32.3#	J55	STC	2,950	2020	211000
Prod Casing 7"	0	5500	23#	J55	LTC	4,810	3270	366,000



- Assumptions:
- 1. Surface casing max anticipated surface press (MASP)= Frac gradient-Gas gradient
  - 2. Prod casing MASP (Production mode)=pore pressure-gas gradient
  - 3. All collapse calculations assume fully evacuated casing w/gas gradients
  - 4. All tension calculations assume air weight

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints

**Cementing  
Design IWM  
SWD 3-30 B4**

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft³/sk)
			Ft³			
Surface Casing	500'	Class G W/2% CaCl	230	30%	15.8	1.15
Prod Casing Lead	3500	Prem Lite II W/10% gel + 3% KCL	320	30%	13.1	1.69
Prod Casing Tail	2000	50/50 Poz W/2% gel + 3% KCL	360	30%	14.2	1.26

- 1. Actual volume pumped will be 15% over the caliper log
- 2. Compressive strength of lead cement: 1800 PSI @ 24hrs, 2250 psi @ 72 hrs
- 3. Compressive strength of tail cement 2500 psi @ 24 hrs

Hole Sizes: a 12 1/4" hole will be drilled for the 9-5/8" surface casing. A 8 3/4" hole will be drilled for the 7" production casing.

The 9-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operations the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface , then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be checked on a daily basis.

Refer to Exhibit C for a diagram of BOP equipment that will be utilized on this well.

**6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

Well will be drilled with water/gel. No high pressures are anticipated in the drilling of this well to depth.

**7. AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be Kelly Cock, bit float, and a TIW valve with drill pipe threads.

**8. TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a triple combination Dual Induction/Density-Neutron with GR and Caliper log from TD to 3500'. A Cement Bond Log will be run from PBTD to cement top. No DST or coring will be done.

**9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No Hydrogen sulfide has been encountered or is known to exist from previous drilling in the area to this depth. Maximum anticipated borehole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


**10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operation will commence in the second quarter of 2011 and take approximately seven (7) days from spud to rig release.

**INTEGRATED WATER MANAGEMENT**

WELL LOCATION

IWMSWD 3-30B4

LOCATED IN THE SE¼ OF THE SE¼ OF  
SECTION 30, T2S, R4W, U.S.B.&M.  
DUCHESNE COUNTY, UTAH**LEGEND AND NOTES**

◆ CORNER MONUMENTS FOUND AND USED  
BY THIS SURVEY

THE GENERAL LAND OFFICE (G.L.O.) PLAT WAS  
USED FOR REFERENCE AND CALCULATIONS AS  
WAS THE U.S.G.S. MAP


THIS SURVEY WAS PERFORMED USING GLOBAL  
POSITIONING SYSTEM PROCEDURES AND EQUIPMENT

THE BASIS OF BEARINGS IS GEODETIC NORTH DERIVED  
FROM G.P.S. OBSERVATIONS AT THE SECTION  
CORNER LOCATED AT LAT. 40°15'22.90258"N AND  
LONG. 110°23'21.19760"W USING THE UTAH  
STATE G.P.S. VIRTUAL REFERENCE STATION CONTROL  
NETWORK MAINTAINED AND OPERATED BY THE  
AUTOMATED GEOGRAPHIC REFERENCE CENTER


BASIS OF ELEVATIONS: NAVD 88 DATUM USING  
THE UTAH REFERENCE NETWORK CONTROL SYSTEM

**SURVEYOR'S CERTIFICATE**

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM THE FIELD  
NOTES AND ELECTRONIC DATA COLLECTOR FILES OF AN ACTUAL  
SURVEY PERFORMED BY ME, OR UNDER MY PERSONAL SUPERVISION,  
DURING WHICH THE SHOWN MONUMENTS WERE FOUND OR REESTABLISHED.



JERRY D. ALLRED, REGISTERED LAND SURVEYOR,  
CERTIFICATE NO. 148951 (UTAH)



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS


1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352

3 MAY 2011

11-100-016

**RECEIVED: Jun. 07, 2011**






## LEGEND:


- ⊕ PROPOSED WELL LOCATION
- OTHER WELLS AS LOCATED FROM SUPPLIED MAP

11-100-016



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352



## INTERGRADED WATER MANAGEMENT

IWMSWD 3-30B4  
SECTION 30, T2S, R4W, U.S.B.&M.  
300' FSL 800' FEL

## TOPOGRAPHIC MAP "C"




SCALE: 1"=2000'  
29 APR 2010



# INTEGRATED WATER MANAGEMENT

LOCATION LAYOUT FOR  
IWMSWD 3-30B4  
SECTION 30, T2S, R4W, U.S.B.&M.  
300' FSL, 800' FEL

FIGURE #1



	<b>JERRY D. ALLRED &amp; ASSOCIATES</b> SURVEYING CONSULTANTS
	1235 NORTH 700 EAST--P.O. BOX 975 DUCHESNE, UTAH 84021 (435) 738-5352

3 MAY 2011

11-100-016

RECEIVED: Jun. 07, 2011

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 5

## DESIGNATION OF AGENT OR OPERATOR

The undersigned is, on record, the holder of oil and gas lease

LEASE NAME: Integrated Water Management

LEASE NUMBER: \_\_\_\_\_

and hereby designates

NAME: Robert BallouADDRESS: 849 Canyon View Drive # 416-3city Roosevelt state UT zip 84066

as his (check one) agent ☒ / operator ☐, with full authority to act in his behalf in complying with the terms of the lease and regulations applicable thereto and on whom the Division Director or Authorized Agent may serve written or oral instructions in securing compliance with the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah with respect to:

(Describe acreage to which this designation is applicable. Identify each oil and gas well by API number and name. Attach additional pages as needed.)


SE/SE Section 30 2S 4W Duchesne, Co. Utah; IWM SWD 3-30 B4

It is understood that this designation of agent/operator does not relieve the lessee of responsibility for compliance with the terms of the lease and the Oil and Gas Conservation General Rules and Procedural Rules of the Board of Oil, Gas and Mining of the State of Utah. It is also understood that this designation of agent or operator does not constitute an assignment of any interest in the lease.

In case of default on the part of the designated agent/operator, the lessee will make full and prompt compliance with all rules, lease terms or orders of the Board of Oil, Gas and Mining of the State of Utah or its authorized representative.

The lessee agrees to promptly notify the Division Director or Authorized Agent of any change in this designation.

Effective Date of Designation: 05/04/2011

BY: (Name) Robert Ballou  
(Signature)   
(Title) President  
(Phone) (435) 722-3555

OF: (Company) Integrated Water Management  
(Address) PO Box 430  
city Altamont  
state UT zip 84001

(5/2000)

Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066  
Office 435-722-3555 Fax 435-722-3556 Cell 435-724-2500  
rballou@stratanet.com

May 4, 2011

Re: APD Materials for proposed SWD well IWM SWD 3-30B4

Attention Brad Hill:

Brad:

Enclosed is the APD form 3 along with support material as outlined and discussed. I scanned the materials as discussed and included them as part of the e filing.

Included in this package is a 10 point drilling plan and a surface use plan with supporting documentation.


Prior to submitting this package, on April 8th 2011, two hard copies of an associated SWD permit was sent to the DOGM offices for processing. As discussed it is understood that a final permit and operations established cannot be done until the well is drilled and tested. As discussed, if after review notices could be sent for publication and review it would make possible that upon completion of the drilling and testing of the well we could start operations.

Please do not hesitate to call with any questions or comments.



Bob Ballou  
enc.

**2-M SYSTEM**  
Blowout Prevention Equipment Systems



**EXHIBIT C**





April 28, 2011

Mr. Brad Hill  
State of Utah  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

Re: Letter of No Objection to Hardline Exception  
Integrated Water Management Saltwater Disposal Well #3-30B4  
SE/4SE/4 of Section 30, Township 2 South, Range 4 West  
Duchesne County, Utah

Mr. Hill,

El Paso, as offset operator, has no objection to Integrated Water Management drilling a saltwater disposal well, the IWM SWD 3-30B4, to be located 800' from the east line and 300' from the south line of Section 30, Township 2 South, Range 4 West, Duchesne County, Utah, at the proposed injection interval of 4,000' – 5,500' and with a maximum injection pressure as deemed acceptable to the Division of Oil, Gas and Mining.

If you have any questions, please call me at 303-291-6422.

Very truly yours,

El Paso E&P Company, L.P.

A handwritten signature in blue ink, reading "Catherine L. Hammock". The signature is fluid and cursive.

Catherine L. Hammock  
Sr. Staff Landman – Altamont Business Area

El Paso E&P Company, L.P.  
1099 18<sup>th</sup> Street, Suite 1900 Denver, Colorado 80202  
tel 303.291.6400 fax 303.291.6487

Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066  
Office 435-722-3555 Fax 435-722-3556 Cell 435-724-2500  
rballou@stratanet.com

May 4, 2011

Re: APD Materials for proposed SWD well IWM SWD 3-30B4

Attention Brad Hill:


Brad:

Enclosed is the APD form 3 along with support material as outlined and discussed. I scanned the materials as discussed and included them as part of the e filing.

Included in this package is a 10 point drilling plan and a surface use plan with supporting documentation.

Prior to submitting this package, on April 8th 2011, two hard copies of an associated SWD permit was sent to the DOGM offices for processing. As discussed it is understood that a final permit and operations established cannot be done until the well is drilled and tested. As discussed, if after review notices could be sent for publication and review it would make possible that upon completion of the drilling and testing of the well we could start operations.

Please do not hesitate to call with any questions or comments.



Bob Ballou  
enc.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>		5. MINERAL LEASE NO:	6. SURFACE: Fee
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER <u>SWD</u> SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Integrated Water Management		9. WELL NAME and NUMBER: IWM SWD 3-30 B4	
3. ADDRESS OF OPERATOR: PO Box 430 CITY Altamont STATE UT ZIP 84001		PHONE NUMBER: (435) 454-4646	10. FIELD AND POOL, OR WILDCAT:
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: 800' FEL 300' FSL  AT PROPOSED PRODUCING ZONE: 4000'-5500' (Injection Interval)		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:  SESE 30 2S 4W	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE:  8 miles north and one mile east of Duchesne, UT		12. COUNTY: Duchesne	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET)  300'	16. NUMBER OF ACRES IN LEASE:	17. NUMBER OF ACRES ASSIGNED TO THIS WELL:	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET)  1632', Christman Blann 1-31 B4	19. PROPOSED DEPTH:  5,500	20. BOND DESCRIPTION:	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.):  Gr 6128'	22. APPROXIMATE DATE WORK WILL START:	23. ESTIMATED DURATION:	

24. **PROPOSED CASING AND CEMENTING PROGRAM**


SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12 1/4"	9 5/8" J55 32.3#	500	Class G 230 sks
8 3/4"	7" J55 23#	5,500	Prem Lite, 50/50 poz

25. **ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- ☒ WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  
☐ EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER

- ☒ COMPLETE DRILLING PLAN  
☐ FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Robert Ballou TITLE PG- Consulting Geologist  
SIGNATURE  DATE 4/28/2011

(This space for State use only)

API NUMBER ASSIGNED: \_\_\_\_\_

APPROVAL: \_\_\_\_\_

(11/2001)

(See Instructions on Reverse Side)

SURFACE USE PLAN  
IWM SWD 3-30 B4

1. Existing Roads:

The well will be accessed from state highway 87. All access roads to the well location are paved county roads.

2. Location of Existing Wells:

The nearest well is the El Paso Operating Company's Christman Blann 1-31 B4, located approximately 1700' S of the proposed well location. Note: a variance letter from El Paso has been included in the APD materials.

3. Location of Existing and/or proposed Facilities:

There are no existing facilities on the proposed well pad. All proposed facilities will be contained within the existing facilities and the SWD fluid pumped to the well head, (tri-plex pump and filter facility). The well head will be the only visible portion of the SWD well. (see attached Location Layout).

Location and Type of Water Supply:

Water will be taken from facility fresh water tank from permitted fresh water well on premises.

4. Source of Construction Materials:

It is not anticipated that any construction materials will be needed for the drilling phase of this project. Gravel, shale or road base materials needed to upgrade access roads will be obtained from local vendors.

5. Methods for Handling Waste Disposal

Drill cuttings will be buried in the reserve pit

Sewage waste will be contained in portable chemical toilets serviced by a commercial sanitary service.

Garbage and trash will be contained in a trash basket and hauled to a sanitary landfill.

Drilling fluids will be contained in the reserve pit and mud tanks.



Unusable drilling fluids and water will be disposed of in an approved manner upon the completion of the well.

The reserve pit will be lined with 12 mil plastic nylon reinforced liner installed over sufficient bedding material to cover any exposed rocks.

The pit will be fenced on three sides with 39" net wire, topped with a minimum of one stand of barbed wire. All wire will be stretched prior to attachment to the corner posts. The fourth side will be fenced when drilling activities are completed to allow drying:

6. Ancillary Facilities:

All living quarters and office facilities will be confined to the drilling location. This will include mobile housing for rig crew, supervisors etc.

7. Site Layout

Refer to "Location Layout" diagram for location of mud tanks, reserve pits, pipe racks, living facilities.

8. Plans for Restoration of the

Surface:

- i. Immediately upon well completion the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash and junk not required for production. The reserve pit will be reclaimed to before drilling specs.

Within 90 days of the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc, removed. The liner will be perforated and torn prior to backfilling.

9. Lessee's or Operator's Representative and Certification:

Robert L. Ballou PG Consulting Geologist

PO Box 430, Altamont, UT 84001

IWM office: 435-454-4646

R.L. Ballou's Office: 435-722-3555 Fax: 435-722-3556

R.L. Ballou's Cell: 435-724-2500

rballou@stratanet.com

I hereby certify that I have inspected the proposed drill site and access road; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Integrated Water Management, and its contractors and subcontractors in conformity with the plan and the terms and conditions under which it is approved.


# INTEGRATED WATER MANAGEMENT

LOCATION LAYOUT FOR  
IWMSWD 3-30B4  
SECTION 30, T2S, R4W, U.S.B.&M.  
300' FSL, 800' FEL

FIGURE #2

1"=30'  
X-SECTION  
SCALE  
1"=60'

NOTE: ALL CUT/FILL  
SLOPES ARE 1½:1  
UNLESS OTHERWISE  
NOTED



## APPROXIMATE YARDAGES



TOTAL CUT (INCLUDING PIT) = 6153 CU. YDS.

PIT CUT = 2115 CU. YDS.

TOPSOIL STRIPPING: (6") = 1089 CU. YDS.

REMAINING LOCATION CUT = 2949 CU. YDS

TOTAL FILL = 2200 CU. YDS.



JERRY D. ALLRED & ASSOCIATES  
SURVEYING CONSULTANTS


1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESTER, UTAH 84021  
(435) 738-5352

4 MAY 2011

11-100-016

RECEIVED: Jun. 07, 2011






## LEGEND:

PROPOSED WELL LOCATION

11-100-016

**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHEсне, UTAH 84021  
(435) 738-5352



## INTEGRATED WATER MANAGEMENT

IWMSWD 3-30B4

SECTION 30, T2S, R4W, U.S.B.&M.


300' FSL 800' FEL

## TOPOGRAPHIC MAP "A"





SCALE: 1"=10,000'

29 APR 2011






## LEGEND:


-  PROPOSED WELL LOCATION
-  PROPOSED ACCESS ROAD
-  EXISTING GRAVEL ROAD
-  EXISTING PAVED ROAD

11-100-016



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCHESNE, UTAH 84021  
(435) 738-5352




## INTEGRATED WATER MANAGEMENT

IWMSWD 3-30B4  
SECTION 30, T2S, R4W, U.S.B.&M.  
300' FSL 800' FEL



## TOPOGRAPHIC MAP "B"

SCALE: 1"=2000'  
29 APR 2010






**LEGEND:**


-  PROPOSED WELL LOCATION  
 OTHER WELLS AS LOCATED FROM SUPPLIED MAP

11-100-016



**JERRY D. ALLRED & ASSOCIATES**  
SURVEYING CONSULTANTS

1235 NORTH 700 EAST--P.O. BOX 975  
DUCESNE, UTAH 84021  
(435) 738-5352




## INTEGRATED WATER MANAGEMENT

IWMSWD 3-30B4  
SECTION 30, T2S, R4W, U.S.B.&M.  
300' FSL 800' FEL



TOPOGRAPHIC MAP "C"

SCALE: 1"=2000'  
29 APR 2010





**API Number: 4301350753**  
**Well Name: IWM SWD 3-30 B4**  
**Township T0.2 . Range R0.4 . Section 30**  
**Meridian: UBM**  
**Operator: INTEGRATED WATER MANAGEMENT LLC**  
**Map Prepared:**  
**Map Produced by Diana Mason**



Well Name	INTEGRATED WATER MANAGEMENT LLC IWM SWD 3-30 B			
String	Surf	I1		
Casing Size(in)	9.625	7.000		
Setting Depth (TVD)	500	5500		
Previous Shoe Setting Depth (TVD)	0	500		
Max Mud Weight (ppg)	9.0	9.0		
BOPE Proposed (psi)	0	2000		
Casing Internal Yield (psi)	2270	4360		
Operators Max Anticipated Pressure (psi)	2365	8.3		

Calculations	Surf String	9.625	"	
Max BHP (psi)	.052*Setting Depth*MW=	234		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	174	NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	124	NO	Reasonable depth
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	124	NO	
Required Casing/BOPE Test Pressure=		500	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi    *Assumes 1psi/ft frac gradient	

Calculations	I1 String	7.000	"	
Max BHP (psi)	.052*Setting Depth*MW=	2574		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	1914	YES	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1364	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	1474	NO	Reasonable
Required Casing/BOPE Test Pressure=		2000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		500	psi    *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi    *Assumes 1psi/ft frac gradient	


Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	

API Well Number: 43013507530000

*Max Pressure Allowed @ Previous Casing Shoe=	<input type="text"/>	psi *Assumes 1psi/ft frac gradient
---	----------------------	------------------------------------

# 43013507530000 IWM SWD 3-30 B4

## Casing Schematic





Well name:	<b>43013507530000 IWM SWD 3-30 B4</b>		
Operator:	<b>INTEGRATED WATER MANAGEMENT LLC</b>		
String type:	Surface	Project ID:	43-013-50753
Location:	DUCHESNE COUNTY		

**Design parameters:****Collapse**

Mud weight: 9.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 81 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: 83 ft

**Burst**

Max anticipated surface pressure: 440 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 500 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 434 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 5,500 ft  
Next mud weight: 9.000 ppg  
Next setting BHP: 2,571 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 500 ft  
Injection pressure: 500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	500	9.625	32.30	H-40	ST&C	500	500	8.876	4134

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	234	1370	5.862	500	2270	4.54	16.1	254	15.73 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801-538-5357  
FAX: 801-359-3940

Date: May 26, 2011  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 500 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**RECEIVED: Jun. 07, 2011**

Well name:	<b>43013507530000 IWM SWD 3-30 B4</b>	
Operator:	<b>INTEGRATED WATER MANAGEMENT LLC</b>	
String type:	Production	Project ID: 43-013-50753
Location:	DUCHESNE COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 151 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 1,624 ft

**Burst**

Max anticipated surface pressure: 1,361 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 2,571 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Non-directional string.**

Tension is based on air weight.  
Neutral point: 4,756 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	5500	7	23.00	J-55	LT&C	5500	5500	6.25	28858

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	2571	3270	1.272	2571	4360	1.70	126.5	313	2.47 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: May 26, 2011  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 5500 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes.  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**RECEIVED: Jun. 07, 2011**

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

<b>Operator</b>	INTEGRATED WATER MANAGEMENT LLC				
<b>Well Name</b>	IWM SWD 3-30 B4				
<b>API Number</b>	43013507530000	<b>APD No</b>	3691	<b>Field/Unit</b>	ALTAMONT
<b>Location: 1/4,1/4</b>	SESE	<b>Sec</b>	30	<b>Tw</b>	2.0S
	<b>Rng</b>	4.0W	300	<b>FSL</b>	800 FEL
<b>GPS Coord (UTM)</b>	553408	4457948	<b>Surface Owner</b>	Integrated Water Management	

**Participants**

Floyd Bartlett (DOGM), Robert Ballou and Nathan Robinson (Integrated Water Management, LLC.)

**Regional/Local Setting & Topography**

The proposed IWMSWD 3-30B4 salt water injection well is on Blue Bench approximately 7.7 miles north of Duchesne, Duchesne County, Utah. Paved County roads lead to the site except for approximately 0.1 mile of private road which will be upgraded. Blue Bench, which begins about 1 mile north of Duchesne, is an expansive bench bordered by the breaks into the Strawberry River on the west and the Duchesne River to the east. Except for a few rolling to moderately steep hills, the topography is quite flat with a gentle slope to the south. On the edges of the bench, steep draws or side hills form leading to the drainages below. Some dwellings and limited commercial sites are scattered on the bench with most concentrated along Utah Highway 87 which runs from Duchesne to Altamont. No streams, springs or seeps are known to exist in the general area. It is expected that water for developed sites is obtained from individual water wells.

**Surface Use Plan****Current Surface Use**

Existing Well Pad

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0.1	<b>Width</b> 225 <b>Length</b> 307	Onsite	UNTA

**Ancillary Facilities** N

**Waste Management Plan Adequate?****Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

The site is barren of vegetation, having been removed with the present use.

**Soil Type and Characteristics**

Deep sandy loam.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required?** N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? N    Paleo Potential Observed? N    Cultural Survey Run? N    Cultural Resources? N

**Reserve Pit****Site-Specific Factors****Site Ranking**

<b>Distance to Groundwater (feet)</b>	100 to 200	5	
<b>Distance to Surface Water (feet)</b>	>1000	0	
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0	
<b>Distance to Other Wells (feet)</b>	>1320	0	
<b>Native Soil Type</b>	Mod permeability	10	
<b>Fluid Type</b>	Fresh Water	5	
<b>Drill Cuttings</b>	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
<b>Affected Populations</b>	10 to 30	10 to 30	
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	<b>Final Score</b>	26	1 Sensitivity Level

**Characteristics / Requirements**

The reserve pit is planned on the north east corner of the location in an area of cut. Dimensions are 75' x 107' x 12 feet deep. A 15 foot wide outer bench is planned. Excavations completed in the general area indicate that the total depth will be in sand with little gravel. Sensitivity Level 1. A liner with a minimum thickness of 12-mils is required. A sub-liner or cushion may not be needed.

Closed Loop Mud Required? N    Liner Required? Y    Liner Thickness 12    Pit Underlayment Required?

**Other Observations / Comments**

Floyd Bartlett  
Evaluator

5/16/2011  
Date / Time

# Application for Permit to Drill Statement of Basis

6/7/2011

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
3691	43013507530000	LOCKED	WD	P	No
<b>Operator</b>	INTEGRATED WATER MANAGEMENT LLC		<b>Surface Owner-APD</b>	Integrated Water Management	
<b>Well Name</b>	IWM SWD 3-30 B4		<b>Unit</b>		
<b>Field</b>	ALTAMONT		<b>Type of Work</b>	DRILL	
<b>Location</b>	SESE 30 2S 4W U 300 FSL 800 FEL		<b>GPS Coord (UTM)</b>	553401E 4457948N	

**Geologic Statement of Basis**

Integrated proposes to set 500 feet of surface casing which will be cemented to surface. The surface hole will be drilled utilizing fresh water mud. The estimated depth to the base of moderately saline ground water is 2,700 feet. A search of Division of Water Rights records indicates that there are 18 water wells within a 10,000 foot radius of the center of Section 30. These wells range in depth from 150-540 feet. Average depth is approximately 400 feet. The wells are listed as being used for irrigation, stock watering, oil exploration, industrial and domestic. These water wells probably produce from the Duchesne River Formation which is a highly used aquifer in this area. This well is being drilled with the intention of permitting it as a water disposal well. The production string of casing will also be cemented to surface. The proposed drilling, casing and cement program should adequately protect usable ground water in this area.

Brad Hill  
APD Evaluator

5/16/2011  
Date / Time

**Surface Statement of Basis**

The proposed IWMSWD 3-30B4 salt water injection well is on Blue Bench approximately 7.7 miles north of Duchesne, Duchesne County, Utah. Paved County roads lead to the site except for approximately 0.1 mile of private road which will be upgraded. Blue Bench, which begins about 1 mile north of Duchesne, is an expansive bench bordered by the breaks into the Strawberry River on the west and the Duchesne River to the east. Except for a few rolling to moderately steep hills, the topography is quite flat with a gentle slope to the south. On the edges of the bench, steep draws or side hills form leading to the drainages below. Some dwellings and limited commercial sites are scattered on the bench with most concentrated along Utah Highway 87 which runs from Duchesne to Altamont. No streams, springs or seeps are known to exist in the general area. It is expected that water for developed sites is obtained from individual water wells.

The selected location is within the interior of a facility managed to separate and evaporate oil field produced water. The pad begins at the south toe of the secondary containment catchment for a water evaporation pond. It extends south to near the existing access road for the facility. To the west a short distance is a series of large separation and storage tanks. Cut along the north side of the pad is 4.9 feet. To the south where the access road will enter, a 4.6 feet fill is shown. In this corner, the location may be gradually sloped to reduce the ramping that will be necessary to access the pad. A large pile of soil currently is located adjacent to the Reserve Pit area. Excavation from the pit will be added to this pile extending it to the north. Some hardening of the site under the rig structure may be needed because of the nature of the sandy soils. The well has been located in this site to facilitate its use with the associated tanks and evaporation ponds which are operated by the same company.

Floyd Bartlett  
Onsite Evaluator

5/16/2011  
Date / Time

**Conditions of Approval / Application for Permit to Drill**

<b>Category</b>	<b>Condition</b>
-----------------	------------------



---

# **Application for Permit to Drill Statement of Basis**

6/7/2011

**Utah Division of Oil, Gas and Mining**

Page 2

---

Pits

A synthetic liner with a minimum thickness of 12 mils with a felt subliner if needed shall be properly installed and maintained in the reserve pit.

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/4/2011**API NO. ASSIGNED:** 43013507530000**WELL NAME:** IWM SWD 3-30 B4**OPERATOR:** INTEGRATED WATER MANAGEMENT LLC (N3685)**PHONE NUMBER:** 435 722-3555**CONTACT:** Robert Ballou**PROPOSED LOCATION:** SESE 30 020S 040W**Permit Tech Review:** ☒**SURFACE:** 0300 FSL 0800 FEL**Engineering Review:** ☒**BOTTOM:** 0300 FSL 0800 FEL**Geology Review:** ☒**COUNTY:** DUCHESNE**LATITUDE:** 40.27220**LONGITUDE:** -110.37192**UTM SURF EASTINGS:** 553401.00**NORTHINGS:** 4457948.00**FIELD NAME:** ALTAMONT**LEASE TYPE:** 4 - Fee**LEASE NUMBER:** 3691**PROPOSED PRODUCING FORMATION(S):** GREEN RIVER**SURFACE OWNER:** 4 - Fee**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**☒ **PLAT**☒ **Bond:** STATE - RLB0013838☐ **Potash**☐ **Oil Shale 190-5**☐ **Oil Shale 190-3**☐ **Oil Shale 190-13**☒ **Water Permit:** Integrated Facility☐ **RDCC Review:**☒ **Fee Surface Agreement**☐ **Intent to Commingle****Commingle Approved****LOCATION AND SITING:**☐ **R649-2-3.****Unit:**☐ **R649-3-2. General**☒ **R649-3-3. Exception**☒ **Drilling Unit****Board Cause No:** R649-3-3**Effective Date:****Siting:**☐ **R649-3-11. Directional Drill****Comments:** Presite Completed**Stipulations:**  
1 - Exception Location - bhill  
5 - Statement of Basis - bhill  
8 - Cement to Surface -- 2 strings - ddoucet**RECEIVED:** Jun. 07, 2011



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** IWM SWD 3-30 B4

**API Well Number:** 43013507530000

**Lease Number:** 3691

**Surface Owner:** FEE (PRIVATE)

**Approval Date:** 6/7/2011

**Issued to:**

INTEGRATED WATER MANAGEMENT LLC, PO Box 816, Roosevelt, UT 84066

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-3. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**Exception Location:**

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volumes for the 9 5/8" and 7" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface as indicated in the submitted drilling plan.

**Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program  
– contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

**Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-231-8956 - after office hours

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read 'John Rogers', is written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 1

APPLICATION FOR INJECTION WELL

Name of Operator Integrated Water Management	Utah Account Number N	Well Name and Number IWM SWD 3-30 B4
Address of Operator PO Box 430 CITY Altamont STATE UT ZIP 84001	Phone Number (435) 454-4646	API Number
Location of Well Footage : 800' FEL, 300' FSL County : Duchesne QQ, Section, Township, Range: SESE 30 2S 4W State : UTAH		Field or Unit Name Lease Designation and Number

Is this application for expansion of an existing project? Yes ☐ No ☒

Will the proposed well be used for:	Enhanced Recovery?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
	Disposal?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Storage?	Yes <input type="checkbox"/>	No <input type="checkbox"/>

Is this application for a new well to be drilled? Yes ☒ No ☐

If this application is for an existing well, has a casing test been performed? Yes ☐ No ☐  
Date of test: \_\_\_\_\_

Proposed injection interval: from 4,000 to 5,500

Proposed maximum injection: rate 5,000 bpd pressure 800 psig

Proposed injection zone contains oil ☒, gas ☐, and / or fresh water ☐ within 1/2 mile of the well.

List of attachments: Attached are write up with exhibits

ATTACH ADDITIONAL INFORMATION AS REQUIRED BY CURRENT  
UTAH OIL AND GAS CONSERVATION GENERAL RULES

I hereby certify that this report is true and complete to the best of my knowledge.

Name (Please Print) Robert Ballou

Title PG- Consultant

Signature

Date 4/7/2011

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING  
WATER DISPOSAL,  
STORAGE AND ENHANCED RECOVERY WELLS  
SECTION V - RULE R615-5-2**

1. **Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**

Integrated Water Management, a Utah Corporation is the operator of an existing SWD facility located 8 miles north and 1 mile east of Duchesne, Utah. IWM is bonded by the DOGM to conduct operations in its existing evaporation pits associated with its SWD operations. This application is submitted as support for IWM to drill and operate a commercial SWD well to be used in conjunction with current operations. Applicant proposes to dispose of such produced water by injection underground into the lower portion of the Duchesne River-Uintah formations underlying the proposed disposal well.

Applicant proposes to drill a SWD well to be designated the **IWM SWD 3-30 B4** and located 300 feet from the south line and 800 feet from the east line of section 30 2S, 4W, Duchesne, County, Utah. Location of the proposed drill site and other wells drilled within a 1/2 mile of the proposed location and surface owners are noted on exhibits A and B.

2. **The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**

- 2.1 **A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.

- 2.2 **Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

Triple combination (Electric log, Density/Neutron) logs will be run and will be provided to the DOGM.

- 2.3 **A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A cement bond log (CBL) will be run and provided to the DOGM.

**RECEIVED**

**APR 11 2011**

**DIV. OF OIL, GAS & MINING**

- 2.4 Copies of logs already on file with the Division should be referenced, but need not be re-filed.**

All copies of logs in area of review are on file with the Utah Division of Oil, Gas and Mining.

- 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The proposed casing program is 9-5/8", 40#, J-55 surface casing run to 500' GL, (cemented to surface), and 7" 23-29 # J-55 casing run from surface to approximately 5000-5500' (cemented to surface).

- 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be production water that has been cleaned and gravity fed to IWM's disposal pit #3. The estimated average rate of injection will be 2000 BPD, and the estimated maximum rate of injection will be 5000 BPD.

- 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

Production water analysis will vary depending on the company and associated location that the production is coming from. Included are representative analysis of produced water from 3 IWM customer wells. See **Exhibit C-A, C-B, C-C**. Included as **Exhibit C1** are water analysis reports from two SWD wells in the immediate vicinity, (both drilled as SWD wells and not as recompletions from a producing oil and gas well, to a SWD well). These wells are;

To the east of the proposed IWM SWD 3-30 B4, **The Russell SWDW 2-32B4**.

To the west of the proposed IWM SWD 3-30 B4, **the LDS Church 2-27 B5**).

These water analysis reports are from actual swab tests of specific intervals and show that formation water from produced water and in the proposed injection interval, the Duchesne River-Uintah formations, are unfit for domestic livestock, irrigation or other general uses.

It is proposed that in the IWM SWD 3-30 B2, IWM will take two samples of formation water by production swab tests, one from the subsurface interval from 4000 to 4875 feet and the other test will be taken below 4875 feet over an interval to be selected. We will notify the DOGM prior to taking such samples and conducting such tests in order that the DOGM may witness the tests and take independent samples if desired.

**RECEIVED**  
**APR 11 2011**  
**DIV. OF OIL, GAS & MINING**

**The proposed average and maximum injection pressures.**

Judging from the data collected from the similar wells in the immediate area The proposed average injection pressure will be approximately 400 psig and the maximum injection pressure will not exceed 800 psig.

**2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.**

The minimum fracture gradient for the IWM SWD 3-30 B4 calculates at 0.733 psig/ft. However a gradient step rate test will be run on the well to determine the maximum injection pressure. Historically this has not been an issue in the SWD wells located within a township of the IWM SWD 3-30 B4 as they all have operated at pressures of less than 800#, some much less.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief

**2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent**

**In the Russell SWDW 2-32B4** the gross injection zones are 2464'-3726', (2464'-2470', 2548'-2558', 2630'-2638', 2884'-2890', 3054'-3062', 3720'-3726', two holes per foot). Records from 1/86 to 9/10 show that this well disposed of 6,836,018 BW with a maximum tubing pressure of 830 # and an average tubing pressure of about 600#. Note: this figure does not include the unreported water that was put away from 1975-1986.

**In the LDS 2-27 B5** the gross injection zones are 2088-2860, ( 2088'-2098', 2129'-2136', 2312'-2317', 2370'-2374', 2377'-2383', 2407'-2413', 2416'-2419', 2515'-2522', 2559'-2561', 2817'-2819', 2840'-2860' one hole per foot); Records from 1/86 to 9/10 show that this well disposed of 33,654,635 BW with a maximum tubing pressure of 550 # . Note: this figure does not include the unreported water that was put away from 1975-1986. All perforations in the Duchesne River-Uintah formations.

**Note:** The original scope of the project was to pattern the IWM SWD 3-30 B4 after the 2-32B4 and the 2-27 B5. However, after meeting with the DOGM it was agreed that due to possible environmental concerns a deeper injection interval horizon patterned after wells that injected into deeper horizons would satisfy DOGM concerns. The closest offset being the Rhodes 1-36 B5 a converted SWD well. Other close by wells that appear

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



to be similar to the proposed IWM SWD 3-30 B4 are the Tew 1-9 B5 a converted SWD well with a perforation interval of 3700-5800' and 5900-6400'. Also the Erich 2-11 B5 that has injected into 4 injection intervals: 3749-3985', 4027-4496, 4576-5573', 5607-5810'.

In the Rhodes 1-36 B5 the gross injection zone intervals are: 4114' to 5055' the original plan was to perforate from 5070'-4583' (phase I) and if needed phase II would be from 4452'-4052' with the injection packer set 4520' for phase I. Records show that phase I and phase II were perf'd and injected into. All perforations in the lower Uinta Fm. Since the well was put into service in January of 1999 it has taken 13,813,822 bbls (to 9/10) for an average per day total of 4168 BW/d.

The reservoir is composed primarily of clastic fluviatile, lacustrine, and transitional sediments and is composed of sandstones, siltstones and shales. Carbonates are also encountered increasing with depth with numerous sandstones containing waters of varying degrees of salinity, porosity and permeability.

The completion reports and logs of these three wells are included in exhibit D, D1, D2.

- 2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.**

Well bore diagrams of the Katherine 3-29 B4 and Christman Blann 1-31 B4 are included as **Exhibit E**. Both wells are producing wells with no reported casing issues.

- 2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.**

See **Exhibit F**.

- 2.12 Any other Information that the Board or Division may determine is necessary to adequately review the application.**

**RECEIVED**

**APR 11 2011**

**DIV. OF OIL, GAS & MINING**


The proposed injection zone is in the - Uintah Formation, upper Tgr fm. The IWM SWD 3-30 B4 well was patterned after the 1-36 B5 in closest in proximity to the IWM SWD 3-30 B2. The proposed injection zone will be determined by the porous intervals encountered in the drilling of the well but if

consistent with other nearby SWD wells (1-36 B5 as noted but also the Tew 1-9 B5, and the Erich 2-11 B5), the zones are expected to be from 4000' to 5500'. The confining stratum directly above the injection zone is the Duchesne River formation and below the injection zones is the Green River Formation.

Integrated Water Management will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

**RECEIVED**  
**APR 11 2011**

**DIV. OF OIL, GAS & MINING**




**Integrated Water Management  
IWM SWD 3-30 B4  
Section 30 2S, 4W  
Surface Owners within 1/2 mile  
radius  
Exhibit A**

**RECEIVED**

**APR 11 2001**

**DIV. OF OIL, GAS & MINING**



RECEIVED

APR 11 2011



DIV. OF OIL, GAS &amp; MINING

1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

**Water Analysis Report**

Field : **Newfield** Sample Date : **4/18/2010**  
 County : **FENCELINE 2-23-8-16** Formation :  
 Lab ID : **Depth :** **Analysed Date: 1/5/2011**  
 Comments :

CATIONS	mg/l	Measured	Calculated	ANIONS	mg/l
Potassium	42.8	Total Dissolve Solid	17205.00	Sulfate	10.0
Sodium	6,776.3	Total Hardness	29.93	Chloride	10,000.0
Calcium	8.2	PH	8.27	Carbonate	0.0
Magnesium	2.3	Total H2S aq	0.00	Bicarbonate	878.4
Iron	1.2	Manganese	1.38	Bromide	0.0
Barium	13.0	PO4 Residual	0.00	Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	-	Hydroxide	0.0
<b>SUM +</b>	<b>6,843.8</b>	APB Vials Turned	-	<b>SUM -</b>	<b>10,888.4</b>

Initial(BH) Final(WH)

**Saturation Index values**

Calcite (CaCO<sub>3</sub>)  
-0.36 -0.48

Barite (BaSO<sub>4</sub>)  
0.12 0.54

Halite (NaCl)  
-3.01 -2.96

Gypsum  
-4.34 -4.35

Hemihydrate  
-4.90 -5.11

Anhydrite  
-4.32 -4.59

Celestite  
0.00 0.00

Iron Sulfide  
0.00 0.00

Zinc Sulfide  
0.00 0.00





Calcium fluoride  
0.00 0.00

Iron Carbonate  
0.74 0.46

**Inhibitor needed (mg/L)**

Calcite **NTMP**  
0.00 0.00

Barite **BHPMP**  
0.00 0.00



Lab Manager: Andrea Craig  
Analysis by:

Exhibit C-A



RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING



1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

**Water Analysis Report**

Field : **Barrett** Sample Date : **8/16/2010**  
 County : **Prickly Pear Fed #12-24-12-14** Formation :  
 Location : **Prickly Pear Fed #12-24-12-14** Rock Type :  
 Lab ID : **Depth : Analyzed Date: 2/16/2011**

**Comments :**

CATIONS	mg/l	Measured	Calculated	ANIONS	mg/l
Potassium	356.5	Total Dissolve Solid	48046.00	Sulfate	1,040.0
Sodium	15,909.1	Total Hardness	6226.52	Chloride	27,900.0
Calcium	1,913.0	PH	6.79	Carbonate	0.0
Magnesium	352.2	Total H2S aq	0.00	Bicarbonate	1,220.0
Iron	83.4	Manganese	0.12	Bromide	0.0
Barium	4.0	PO4 Residual	0.00	Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	0.00	Hydroxide	0.0
<b>SUM +</b>	<b>18,618.2</b>	APB Vials Turned	0.00	<b>SUM -</b>	<b>30,160.0</b>

Initial(BH) Final(WH)

**Saturation Index values**Calcite (CaCO<sub>3</sub>)

2.01 0.86

Barite (BaSO<sub>4</sub>)

0.70 1.82

Halite (NaCl)

-2.08 -2.15

Gypsum

-0.20 -0.42

Hemihydrate

0.85 -1.21

Anhydrite

1.28 -0.75

Celestite

0.00 0.00

Iron Sulfide

0.00 0.00

Zinc Sulfide

0.00 0.00

Calcium fluoride

0.00 0.00

Iron Carbonate

1.81 1.12





**Inhibitor needed (mg/L)**

Calcite NTMP

105.51 0.00

Barite BHPMP

8.91 0.65



Lab Manager: Andrea Craig  
 Analysis by:

Exhibit C-B

# Production Water Report and Scaling Tendencies

Creg Wilkins

12/17/2003

Version : 947

Analysis by : <b>Creg Wilkins</b>
Field :
County : <b>Uintah</b>
Lab ID# : <b>El Paso Production</b>
Sample Date : <b>13-Apr-09</b>
Location : <b>2-9B4</b>
Formation :
Depth :
Rock Type:
Porosity:
Permeability:

INPUT Sample Temp °F :	<b>60.0</b>	INPUT TDS @180 °C, mg/L	<b>54,491</b>
INPUT Downhole Temp °F :	<b>125.0</b>	Calc TDS (less CO <sub>2</sub> ), mg/L	<b>54,491</b>
INPUT Sample Press :	<b>6.0</b>	INPUT Resistivity @ 68°F	<b>0.150</b>
INPUT sample pH, su	<b>10.00</b>	Calculated Resistivity @ 68°F	<b>0.150</b>
Input mole % CO <sub>2</sub>	<b>0.04</b>	Input Conductivity, µmhos/cm	<b>66,667</b>
pH resulting from CO <sub>2</sub>	<b>10.02</b>	Calc Cond@25 °C, µmhos/cm	<b>66,667</b>
Calc Carbon Dioxide (Aq), mg/L	<b>0.2</b>	INPUT Density @ STP, g/mL	<b>1.039</b>
Carbon Dioxide, CO <sub>2</sub> mg/L	<b>0.0</b>	Calc Density @STP, g/mL	<b>1.039</b>
Total Sulfide, mg/L	<b>6.0</b>	MicroBiological - # of bottles turned	
Dissolved Oxygen, ppm		SRBs :	( 1 )
Dissolved Oxygen, ppb	<b>0.0</b>	Aerobic Bacteria :	( 1 )

K <sup>+</sup>	<b>172.0</b>
Na <sup>+</sup>	<b>20,990.9</b>
Na <sup>+</sup> by Diff	<b>+ 0.00</b>
Ca <sup>++</sup>	<b>60.0</b>
Mg <sup>++</sup>	<b>378.2</b>
Fe <sup>++</sup>	<b>3.8</b>
Ba <sup>++</sup>	<b>125.0</b>
Sr <sup>++</sup>	<b>0.0</b>
Br <sup>-</sup>	<b>0.0</b>
SO <sub>4</sub> <sup>=</sup>	<b>1,600.0</b>
Cl <sup>-</sup>	<b>30,000.0</b>
CO <sub>2</sub> <sup>=</sup>	<b>1,560.0</b>
HCO <sub>3</sub> <sup>-</sup>	<b>1,342.0</b>
OH <sup>-</sup>	<b>0.0</b>
Organic Acid	<b>0.0</b>

Note: Organic Acids as Acetate

Titration - if values are placed in mls or digits - results will transfer to Water Report

Parameter	mls	Digits	Sample Size	Normality	Results
CO <sub>2</sub>	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>3.636</b>	
H <sub>2</sub> S	<b>0</b>	<b>0.0</b>	<b>10</b>	<b>0.3998</b>	
T reading	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>8.0</b>	
P reading	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>1.6</b>	
Ca <sup>++</sup>	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
THardness	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
Cl <sup>-</sup>	<b>0</b>	<b>0.0</b>	<b>1</b>	<b>2.256</b>	

RECEIVED  
APR 11 2011  
DIV OF OIL, GAS & MINING

Comments: Mn .45

Exhibit Cc



PARTIAL

75 086

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE JAN. 16 1975  
Sample Received on  
Analysis Authorization

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒  
WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

RECEIVED  
APR 11 2001

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

DIV. OF OIL, GAS & MINING

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL No.

2-27B5 SEC 27, T2S, R5W (USM) DUCHECNE Co.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2088 TO 2383 LEVEL

SUPPLY OWNED BY: \_\_\_\_\_

PRESENT USE OF SUPPLY: \_\_\_\_\_

PROPOSED USE OF SUPPLY: \_\_\_\_\_

SAMPLE COLLECTED BY: CLEW FEIGHT, OIL & GAS DIV. DATE: \_\_\_\_\_

REPORT RESULTS TO: R. WINSLOW RNL PHONE: \_\_\_\_\_

Address: BLDG 72

DO NOT WRITE BELOW DOUBLE LINE

RESULTS OF ANALYSIS

Turbidity	J.T.U.	Iron (total) as Fe	mg/l
✓ Conductivity <u>23,300</u>	micromhos/cm	Iron in filtered sample as Fe	mg/l
✓ pH <u>7.00</u>		Lead as Pb	mg/l
✓ Total Dissolved Solids <u>17,560</u>	<u>17,560</u> mg/l	Magnesium as Mg	mg/l
✓ Alkalinity (total) as CaCO <sub>3</sub> <u>4428</u>	mg/l	Manganese as Mn	mg/l
Aluminum as Al	mg/l	Mercury as Hg	mg/l
Arsenic as As	mg/l	Nitrate as N	mg/l
Barium as Ba	mg/l	Nitrite as N	mg/l
✓ Bicarbonate as HCO <sub>3</sub>	mg/l	Phosphate as PO <sub>4</sub>	mg/l
Boron as B	mg/l	Phenols as Phenol	mg/l
Cadmium as Cd	mg/l	Potassium as K	mg/l
Calcium as Ca	mg/l	Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>	mg/l	Silica as SiO <sub>2</sub>	mg/l
✓ Chloride as Cl	<u>8000</u> mg/l	Silver as Ag	mg/l
Chromium (hexavalent) as Cr	mg/l	✓ Sodium as Na	<u>7000</u> mg/l
Copper as Cu	mg/l	✓ Sulfate as SO <sub>4</sub>	<u>500</u> mg/l
Cyanide as CN	mg/l	Surfactant as MBAS	mg/l
Fluoride as F	mg/l	Zinc as Zn	mg/l
✓ Hardness (total) as CaCO <sub>3</sub> <u>17</u>	mg/l	Total Alpha	pci/l
Hydroxide as OH	mg/l	Total beta	pci/l
Ammonia N as NH <sub>3</sub>			i/l
			mg/l

Exhibit C1



# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

(801) 722-2254

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

LABORATORY NUMBER W-2129  
SAMPLE TAKEN \_\_\_\_\_  
SAMPLE RECEIVED 4-18-75  
RESULTS REPORTED 4-18-75

## SAMPLE DESCRIPTION

COMPANY Husky Oil Co. LEASE Russell FIELD NO. \_\_\_\_\_  
FIELD Altamont COUNTY Duchesne STATE Utah WELL NO. 2-32B4  
SAMPLE TAKEN FROM \_\_\_\_\_  
PRODUCING FORMATION Duchesne River - Uinta TOP 2548-2558 <sup>3726'</sup>  
REMARKS \_\_\_\_\_

SAMPLE TAKEN BY Warren Johnston

## CHEMICAL AND PHYSICAL PROPERTIES


SPECIFIC GRAVITY @60/60° F. 1.0146 pH 8.28 RES. 0.30 OHM METERS @ 77°F

TOTAL HARDNESS 1155.47 mg/L as CaCO<sub>3</sub> TOTAL ALKALINITY 360.0 mg/L as CaCO<sub>3</sub>


CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca ++	273.0	13.65		
MAGNESIUM - Mg ++	114.0	9.34		
SODIUM - Na +	8450.0	367.39		
BARIUM (INCL. STRONTIUM) - Ba ++	10.6	0.15		
TOTAL IRON - Fe ++ AND Fe +++	2.55	0.09	390.62	
BICARBONATE - HCO <sub>3</sub> --	360.0	5.90		
CARBONATE - CO <sub>3</sub> --	0	0		
SULFATE - SO <sub>4</sub> --	1500.0	31.25		
CHLORIDE - CL -	11695.3	329.45	366.69	
TOTAL DISSOLVED SOLIDS	20120.			

## MILLEQUIVALENTS PER LITER

LOGARITHMIC



STANDARD



ANALYST \_\_\_\_\_

CHECKED \_\_\_\_\_

Exhibit C1





# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

(801) 722-2254

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

LABORATORY NUMBER W-2123  
SAMPLE TAKEN 4-17-75  
SAMPLE RECEIVED 4-17-75  
RESULTS REPORTED 4-17-75

## SAMPLE DESCRIPTION

COMPANY Husky Oil LEASE Russell FIELD NO. 2-32B4  
FIELD Altamont COUNTY Duchesne STATE Utah  
SAMPLE TAKEN FROM Duchesne River - Uinta TOP 2464-2470  
PRODUCING FORMATION 2464-2470  
REMARKS

SAMPLE TAKEN BY

## CHEMICAL AND PHYSICAL PROPERTIES


SPECIFIC GRAVITY @60/60° F. 1.0138 pH 8.91 RES. 0.50 OHM METERS @ 77°F

TOTAL HARDNESS 254.35 mg/L as CaCO<sub>3</sub> TOTAL ALKALINITY 352.0 mg/L as CaCO<sub>3</sub>


CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca ++	51.15	2.56		
MAGNESIUM - Mg ++	30.30	2.48		
SODIUM - Na +	4890.0	212.61		
BARIUM (INCL. STRONTIUM) - Ba ++	2.9	0.04		
TOTAL IRON - Fe ++ AND Fe +++	1.07	0.04	217.73	
BICARBONATE - HCO <sub>3</sub> --	260.0	4.26		
CARBONATE - CO <sub>3</sub> --	92.0	3.07		
SULFATE - SO <sub>4</sub> --	2600.0	54.17		
CHLORIDE - CL -	9596.2	270.32	331.82	
TOTAL DISSOLVED SOLIDS	17440.			

MILLEQUIVALENTS PER LITER

LOGARITHMIC



STANDARD



Al

Cl

Exhibit C1

A

PARTIAL

75 085

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE  
Sample Received on  
Analysis Authorization

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒  
WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL NO.

2-2785 Sec 27, T2S, R5W (USM) DUCHESNE CO.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2817 TO 2860 LEVEL.

SUPPLY OWNED BY: \_\_\_\_\_

RECEIVED

PRESENT USE OF SUPPLY: \_\_\_\_\_

APR 11 2001

PROPOSED USE OF SUPPLY: \_\_\_\_\_

DIV. OF OIL, GAS & MINING

SAMPLE COLLECTED BY: CLEON FREIGHT, OIL & GAS DIV. DATE: \_\_\_\_\_

REPORT RESULTS TO: R. HINSHAW RMT PHONE: \_\_\_\_\_

Address: BLDG 72

DO NOT WRITE BELOW DOUBLE LINE

RESULTS OF ANALYSIS



Turbidity	J.T.U.	Iron (total) as Fe	mg/l
Conductivity	micromhos/cm	Iron in filtered sample as Fe	mg/l
pH	7.70	Lead as Pb	mg/l
Total Dissolved Solids	18,340	Magnesium as Mg	mg/l
Alkalinity (total) as CaCO <sub>3</sub>	2,790	Manganese as Mn	mg/l
Aluminum as Al		Mercury as Hg	mg/l
Arsenic as As		Nitrate as N	mg/l
Barium as Ba		Nitrite as N	mg/l
Bicarbonate as HCO <sub>3</sub>	3,500	Phosphate as PO <sub>4</sub>	mg/l
Boron as B		Phenols as Phenol	mg/l
Cadmium as Cd		Potassium as K	mg/l
Calcium as Ca		Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>		Silica as SiO <sub>2</sub>	mg/l
Chloride as Cl	2,715	Silver as Ag	mg/l
Chromium (hexavalent) as Cr		Sodium as Na	705 mg/l
Copper as Cu		Sulfate as SO <sub>4</sub>	220 mg/l
Cyanide as CN		Surfactant as MBAS	mg/l
Fluoride as F		Zinc as Zn	0.04 mg/l
Hardness (total) as CaCO <sub>3</sub>	10	Total Alpha	pci/l
Hydroxide as OH		Total beta	pci/l
Ammonia N as NH <sub>3</sub>			nci/l
			mg/l

Exhibit C<sub>1</sub>

SPONTANEOUS-POTENTIAL MILLIVOLTS	CONDUCTIVITY MILLIMHOES M <span style="float: right;">1000 CMHRS M<sup>2</sup> M</span>
$\frac{10}{100} =$	DEEP INDUCTION LOG YES _____ NO _____
	<b>RESISTIVITY</b> OHMS M <sup>2</sup> M
	<b>DEEP INDUCTION LOG</b> YES _____ NO _____
	<b>AVERAGED LATEROLOG - II</b> YES _____ NO _____

RECEIVED  
APR 11 2001  
DIV. OF OIL, GAS & MINING


# Exhibit D



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING




TOP OF DISPOSAL  
ZONE 2090'




RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

DETAIL LOG			
SPONTANEOUS POTENTIAL MILLIVOLTS	DEPTH FEET	RESISTIVITY OHMS IN. M.	
		DEEP INDUCTION LOG	LATEROLOG - 8
10	1400	10	100
	1410	10	100
	1420	10	100
	1430	10	100
	1440	10	100
	1450	10	100
	1460	10	100
	1470	10	100
	1480	10	100
	1490	10	100
	1500	10	100



Form OGCC-3

RECEIVED

APR 11 2011

14

2

STATE OF UTAH

SUBMIT IN DUPLICATE\*

DIVISION OF OIL, GAS & MINING  
(See other instructions on reverse side)

OIL &amp; GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other <u>SWD Well</u>										5. LEASE DESIGNATION AND SERIAL NO. <b>Patented</b>	
b. TYPE OF COMPLETION: NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____										6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR <b>Shell Oil Company</b>										7. UNIT AGREEMENT NAME	
3. ADDRESS OF OPERATOR <b>1700 Broadway, Denver, Colorado 80202</b>										8. FARM OR LEASE NAME <b>L.D.S. Church</b>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface <b>551' FSL and 2556' FEL, Section 27</b> At top prod. interval reported below At total depth										9. WELL NO. <b>2-27B5 SWD</b>	
14. PERMIT NO. <b>43-013-30340</b> DATE ISSUED <b>9/26/74</b>										10. FIELD AND POOL, OR WILDCAT <b>Altamont</b>	
15. DATE SPUDDED <b>11/3/74</b> 16. DATE T.D. REACHED <b>11/12/74</b> 17. DATE COMPL. (Ready to prod.) <b>1/4/75</b>										11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA <b>SW/4 SE/4 Section 27-T2S-R5W, USB&amp;M</b>	
18. ELEVATIONS (DF, REB, RT, GR, ETC.)* <b>5887KB, 5860 GL</b>										12. COUNTY OR PARISH <b>Duchesne</b>	
19. ELEV. CASINGHEAD <b>5862</b>										13. STATE <b>Utah</b>	
20. TOTAL DEPTH, MD & TVD <b>4205</b> 21. PLUG, BACK T.D., MD & TVD <b>4075 (FC)</b> 22. IF MULTIPLE COMPL., HOW MANY* <b>-</b>										23. INTERVALS DRILLED BY <b>→</b>	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* <b>2088-2860 (gross interval) Duchesne River-Uinta</b>										25. WAS DIRECTIONAL SURVEY MADE <b>No</b>	
26. TYPE ELECTRIC AND OTHER LOGS RUN <b>BHCS, PDC, CBL</b>										27. WAS WELL CORED <b>No</b>	
28. CASING RECORD (Report all strings set in well)											
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED	
9-5/8"		40#		305'		12-1/4"		300 sx		0	
7"		23#, 26#, 29#		4,205'		8-3/4"		1080 cu ft		0	
29. LINER RECORD											
SIZE		TOP (MD)		BOTTOM (MD)		SACKS CEMENT*		SCREEN (MD)			
30. TUBING RECORD											
SIZE		DEPTH SET (MD)		PACKER SET (MD)							
2-7/8"		2014'		2000'							
31. PERFORATION RECORD (Interval, size and number)											
2088-2098, 2129-2136, 2312-2317, 2370-2374, 2377-2383, 2407-2413, 2416-2419, 2515-2522, 2559-2561, 2817-2819, 2840-2860 (1 hole/ft w/Jumbo jets, 72 holes total)											
32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.											
DEPTH INTERVAL (MD)						AMOUNT AND KIND OF MATERIAL USED					
2817-2860						2200 gal 15% HCl					
2312-2561						2300 gal 15% HCl					
2088-2136						1700 gal 15% HCl					
33. PRODUCTION											
DATE FIRST PRODUCTION IN <b>1/4/75</b>				PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) <b>Injecting into SWD well</b>				WELL STATUS (Producing or shut-in) <b>Injecting</b>			
DATE OF TEST <b>1/26/75</b>		HOURS TESTED <b>24</b>		CHOKE SIZE <b>-</b>		PROD'N. FOR TEST PERIOD <b>→</b>		OIL—BBL. <b>-</b>		GAS—MCF. <b>-</b>	
								WATER—BBL. <b>3390</b>		GAS-OIL RATIO <b>-</b>	
CASING PRESSURE <b>250</b>		CALCULATED 24-HOUR RATE <b>→</b>		OIL—BBL. <b>-</b>		GAS—MCF. <b>-</b>		WATER—BBL. <b>3390</b>		OIL GRAVITY-API (CORR.) <b>-</b>	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) <b>-</b>										TEST WITNESSED BY <b>-</b>	
35. LIST OF ATTACHMENTS <b>Well History Report</b>											
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records											
SIGNED <u>T.S. Mize</u> TITLE <u>Division Operations Engr.</u> DATE <u>1/29/75</u>											



**BOAT INDUCTION - EATLILKLOU  
WITH LINEAR CORRELATION LOG**

OLD HERE      The well name, location and borehole reference data were furnished by the customer.

[illegible]


All interpretations are opinions based on inferences from electrical or other measurements and we cannot, and do not guarantee the accuracy or correctness of any interpretations, and we shall not, except in the case of gross or willful negligence on our part, be liable or responsible for any loss, costs, damages or expenses incurred or sustained by anyone resulting from any interpretation made by any of our officers, agents or employees. These interpretations are also subject to Clause 7 of our General Terms and Conditions as set out in our current Price Schedule.

# Exhibit D1

RECEIVED

APR 11 2011

## DIV. OF OIL, GAS & MINING



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

2600

2700

2800

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING


2900

3000

RECEIVED

APR 11 2011


DIV. OF OIL, GAS & MINING



3100

3200

3300




RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING





3400


3500



RECEIVED

APR 11 2011


DIV. OF OIL, GAS & MINING



3600

3700

3800



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING

3800

3900

FR

4000

SP

LLB

ILM

ILD

Cut before  
Survey

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☐ Other SWD Well

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other \_\_\_\_\_

2. NAME OF OPERATOR

Husky Oil Company of Delaware

3. ADDRESS OF OPERATOR

P. O. Box 380, Cody, Wyoming 82414

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface S $\frac{1}{2}$  NE (1919' FNL, 1317' FEL) Sec. 32, T2S, R4W  
At top prod. interval reported below

At total depth

14. PERMIT NO.

DATE ISSUED

5. LEASE DESIGNATION AND SERIAL NO.

FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Russell

9. WELL NO.

SWDW 2-32 B4

10. FIELD AND POOL, OR WILDCAT

Altamont

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Section 32  
T2S, R4W12. COUNTY OR PARISH  
Duchesne13. STATE  
Utah

15. DATE SPUDDED

3-21-75

16. DATE T.D. REACHED

3-28-75

17. DATE COMPL. (Ready to prod.)

4-17-75

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\*

6145.8 KB, 6134 GL

19. ELEV. CASINGHEAD

6136

20. TOTAL DEPTH, MD &amp; TVD

4000

21. PLUG, BACK T.D., MD &amp; TVD

3936

22. IF MULTIPLE COMPL., HOW MANY\*

23. INTERVALS DRILLED BY

ROTARY TOOLS

CABLE TOOLS

Total

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\*

2464-3720 (gross interval) Duchesne River - Uinta

25. WAS DIRECTIONAL SURVEY MADE

no

26. TYPE ELECTRIC AND OTHER LOGS RUN

GHC-GR, DIL, CBL

27. WAS WELL CORED

no

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
9-5/8"	40#	380'	12-1/4"	175 sacks	0
5-1/2"	15.5#	3982'	8-1/2"	1305 sacks	0

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	2412'	2391'

31. PERFORATION RECORD (Interval, size and number)

2464-2470, 2548-2558,  
2630-2638, 2884-2890,  
3054-3062, 3720-3726  
(2 holes/ft.)

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
	none

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
		injecting into SWD well				shut in	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
4-17-75			→				
INJECTING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
500 psig		→			3000 (est.)		

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Well history report, Cement Bond logs

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED R. L. HansenTITLE Senior EngineerDATE 4-24-75

(See Instructions and Spaces for Additional Data on Reverse Side)

Full Case  
Schlumberger

DUAL INDUCTION - SFL

CSU

COMPANY: LINMAR ENERGY CORPORATION

WELL: BROTHERSOIN 2-35B5

FIELD: ALTAMONT  
COUNTY: DUCHESNE  
STATE: UTAH  
NATION: USA  
LOCATION: SE / NE

SEC: 35 TWP: 2S RGE: 5M

PERMANENT DATUM: GL  
ELEV. OF PERM. DATUM: 5817.0 F  
LOG MEASURED FROM: KB  
20.0 F ABOVE PERM. DATUM  
DRLG. MEASURED FROM: KB  
ELEVATIONS-  
KB: 5837.0 F  
DF: 5836.0 F  
GL: 5817.0 F

DATE: 14 APR 84  
RUN NO: 132

DEPTH-DRILLER: 10020.0 F  
DEPTH-LOGGER: 9997.0 F  
BTM. LOG INTERVAL: 9988.0 F  
TOP LOG INTERVAL: 2511.0 F

CASING-DRILLER: 2508 F  
CASING-LOGGER: 2511 F  
CASING: 9.625

BIT SIZE: 8.75

OTHER SERVICES-  
FDC  
CNL  
CYBERLOOK

PROGRAM  
TAPE NO:  
26.2  
SERVICE  
ORDER NO:  
267137

RUN 1

TYPE FLUID IN HOLE: GEL-YP  
DENSITY: 10.2 LB/G  
VISCOSITY: 39.0 S  
PH: 10.5  
FLUID LOSS: 16.0 C3  
SOURCE OF SAMPLE: MUD TANK  
RM: .660 DHMM AT 70.0 DEGF  
RMF: .440 DHMM AT 70.0 DEGF  
RMC: .990 DHMM AT 70.0 DEGF  
SOURCE RMF/RMC: MEAS/CALC  
RM AT BHT: .260 DHMM AT 188. DEGF  
RMF AT BHT: .173 DHMM AT 188. DEGF  
RMC AT BHT: .390 DHMM AT 188. DEGF  
TIME CIRC. STOPPED: 0900 4/14  
TIME LOGGER ON BTM.: 1445 4 /14  
MAX. REC. TEMP: 188.0 DEGF  
LOGGING UNIT NO: 8305  
LOGGING UNIT LOC: VERNAL  
RECORDED BY: T. TEIPNER K. FOX  
WITNESSED BY: JIM GARCIA

REMARKS:

-Exhibit D2

RECEIVED


APR 11 2011

DIV. OF OIL, GAS & MINING




GR (GAPI)		ILD (OHMM)		TENS(LB )	
0.0	150.00	0.0	100.00	0.0	10000.
SP (MY 10)		SFLA(OHMM)		CILD(MMHD)	
-100.0	0.0	0.0	100.00	400.00	


FILE 3 14-APR-84 17:36  
LR




RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING




RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING



# SWD CONVERSION PROCEDURE

Revision #1

June 12, 1997

RHOADES-MOON #1-36B5

Section 36-T2S-R5W

Altamont Field

Duchesne County, Utah

## WELL DATA

Location: 1178' FEL, 1178' FNL  
Elevation: 6077' GL; 6105' KB  
Total Depth: 12,100' PBTd: 9390' (RBP)  
Casing: 13-3/8" 48# H-40 @ 315' KB cmt'd to surf w/ 300 sks  
9-5/8" 40# J-55(103 jts) and N-80 (38 jts) @ 5799' KB cmt'd w/ 600sks  
7" 26# S-95 (64 jts) & N-80 (186 jts) @ 10,198' KB cmt'd w/ 380 sks  
DV collar @ 8148' cmt'd w/ 590 sks.  
5" 18# N-80 from 9,872' to 12,092' cmt'd w/ 210 sks  
Tubing: 2-7/8" N-80 EUE 8 rd @ 8905' open ended.

## TUBULAR DATA

Description	ID	Drift	Capacity (BPF)	Burst (PSI)	Collapse (PSI)
9-5/8" 40# J-55	8.835"	8.679"	.0773	3950	2570
9-5/8" 40# N-80	8.835"	8.679"	.0773	5750	3090
7" 26# S-95	6.276"	6.151"	.0382	8600	5870
7" 26# N-80	6.276"	6.151"	.0382	7240	5410
5" 18# N-80	4.276"	4.151"	.0177	10140	10490

## WELL HISTORY

- 6/74 Initial completion. Perforate from 10,669' to 11,691', 2 SPF, 164 holes. Acidize w/ 20,000 gals 15% HCl. Prod 50 BOPD, 250 MCFPD, 125 BWPD.
- 4/76 Added perforations 10,214' to 11,548'. 374 holes. Acidize with 20,000 gals 7-1/2% HCl.  
Prior Production: 15 BOPD, 60 MCFPD, 5 BWPD  
Post Production: 75 BOPD, 225 MCFPD, 35 BWPD
- 2/81 Acidized w/ 10,000 gals 15% HCl  
Prior Production: 15 BOPD, 60 MCFPD, 5 BWPD  
Post Production: 25 BOPD, 75 MCFPD, 20 BWPD

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

RECEIVED

APR 11 2011

Form OGCC-3

STATE OF UTAH

SUBMIT IN DUPLICATE\*

DIV. OF OIL, GAS &amp; MINING

(See other instructions on reverse side)

OIL &amp; GAS CONSERVATION COMMISSION


## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL:		OIL WELL <input checked="" type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input type="checkbox"/>	Other _____
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>
			DIFF. RESVR. <input type="checkbox"/>	Other _____	
2. NAME OF OPERATOR HUSKY OIL COMPANY OF DELAWARE					
3. ADDRESS OF OPERATOR P. O. Box 380, Cody, Wyoming 82414					
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface 1178' FEL, 1178' FNL Sec 36, T2S, R5W At top prod. interval reported below Same At total depth Same					
14. PERMIT NO.			DATE ISSUED		
5. LEASE DESIGNATION AND SERIAL NO. FEE		6. IF INDIAN, ALLOTTEE OR TRIBE NAME			
7. UNIT AGREEMENT NAME					
8. FARM OR LEASE NAME Rhoades					
9. WELL NO. 1-36					
10. FIELD AND POOL, OR WILDCAT Altamont					
11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA 36 T2S-R5W					
12. COUNTY OR PARISH Duchesne			13. STATE Utah		
15. DATE SPUDDED 3-16-74	16. DATE T.D. REACHED 5-22-74	17. DATE COMPL. (Ready to prod.) 7-4-74	18. ELEVATIONS (DF, REB, RT, GR, ETC.)* 6077 Gr. Ungraded	19. ELEV. CASINGHEAD 6077	
20. TOTAL DEPTH, MD & TVD 12095	21. PLUG, BACK T.D., MD & TVD 11990	22. IF MULTIPLE COMPL., HOW MANY*	23. INTERVALS DRILLED BY →	ROTARY TOOLS	CABLE TOOLS
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 11686-691 11652-657 11454-459 11120-125 10782-789 Wasatch 11662-673 11616-621 11175-179 10854-870 10756-765 10669-679					25. WAS DIRECTIONAL SURVEY MADE NO
26. TYPE ELECTRIC AND OTHER LOGS RUN DUL. IND. LL-GR. BHCS-GR. FDC-CNL-GR.					27. WAS WELL CORRED NO
28. CASING RECORD (Report all strings set in well)					
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	
13-3/8	48#	315 K.B.	17-1/2"	300 sks class G 3% CaCl <sub>2</sub>	
9-5/8	40#	5612 K.B.	12-1/4"	400 sks lite 200sks class G	
7	26#	10200 K.B.	8-1/2"	180 sks lite 200sks class G	
29. LINER RECORD			30. TUBING RECORD		
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	
5"	9872	12092	210 sks		
				SIZE	DEPTH SET (MD)
				2-7/8	9772
				1-1/2	5026.56
31. PERFORATION RECORD (Interval, size and number)			32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.		
11686-691	11454-459	10756-765			
11662-673	11175-179	10669-679			
11652-657	11120-125	2 jet shots per ft.			
11616-621	10854-870				
	10782-789				
			DEPTH INTERVAL (MD)		
			AMOUNT AND KIND OF MATERIAL USED		
			All Perfs		
			20,000 Gal 15% HCL		
			6,000# Unibeads		
			600# Buttons		
			264 Balls		
33. PRODUCTION					
DATE FIRST PRODUCTION 6-12-74		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Flowing			WELL STATUS (Producing or shut-in) Producing
DATE OF TEST 7-4-74	HOURS TESTED 24	CHOKE SIZE 16/64	PROD'N. FOR TEST PERIOD →	OIL—BBL. 106	GAS—MCF. 379
WATER—BBL. 43	GAS-OIL RATIO 3575 SCF/BBL				
FLOW. TUBING PRESS. 300 PSIG	CASING PRESSURE	CALCULATED 24-HOUR RATE →	OIL—BBL. 37	GAS—MCF. 260	WATER—BBL. 127
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Vented (connection to gas plant)					TEST WITNESSED BY Glynn Mayson
35. LIST OF ATTACHMENTS					
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records					
SIGNED <u>Joe C. Hugo</u>		TITLE <u>PRODUCTION ENGINEER</u>		DATE <u>7-8-74</u>	

\*(See Instructions and Spaces for Additional Data on Reverse Side)

# 04-06 El Paso Katherine 3- B4

## Casing Schematic



## CHRISTMAN BLANN 1-31B4

Sec 31; 2S; 4W

## Average Production:

19 25 BOPD  
 150 125 BWP D  
 85 MCFD

Downhole Pump:  
 Jet

Surface Equipment:  
 J100 belt drive

Comments:  
 SWD line to L. Russel 2-32B4

2 7/8" Scab Liner  
 9399-10,350'  
 Cemented w/45 sx

1.90 Heat String to 1870'

7 5/8" 40 # K-55 @ 4519'

2 7/8" Tubing EUE 8rd N80

Packer: 7" Lokset @ 9254  
 (Bottom part of a previous Lokset  
 was left @ 9265' Mar '80)

TOL: 4 1/2" @ 9738'

9920' Tight spot in 4 1/2"

7" Shoe: 10,052' 23+26 # 1/-80

Perfs: 10,409-11,545' Aug '73  
 58 holes

Perfs: 10,805-11,953' May '73  
 16 holes

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

31-Aug-94

4 1/2" Shoe: 12,024' 13.5# P-110

Cmt 41621 st 50/50 132

PRTD  
15KH'

TD w/ 14.6 ppg 11.11.

Exhibit E1

**Exhibit F**

Operator/Landowner Section 29	Duchesne Co. Serial #	Address	Date Sent	Comments
Brent Farnsworth	2146	PO Box 153 Duchesne, UT 84021		Only Neighbor in vicinity, IWM purchased 9 additional nine acres from Brent and he constructed the fence around our facility.
Section 30 & 31				
William A. Robinson	2147-2-1	243 E. Escondido Blvd # 518 Escondido CA 92025		
J. Christman	2151	146 Avenida Coto San Clemente, CA 92672		
Jerry A. Craysper and Joann Craysper	2148-2	840 E. House Mtn. Drive Cottonwood, AZ 86326		
Heidi Kennelly	2148-2-1	PO Box 2074 Mesquite, NV 89024		
Jose Luis Tomayo	2150	4200 Dennis Dr. SLC, UT 84120		
Antonio Gander Jr. Trustee, Victoria Bell Gander Trustee, SJ Christman Trustees	2157	14808 E. Sabine Dr. La Mirada, CA 90638		
Ronnie W. Case, Cristine Case	2152	PO Box 70161 SLC, UT 84170		
Duchesne /Wasatch Blue Bench Landfill	2158	Duchesne Co. Landfill C/O Manager P.O. Box 228 Duchesne, UT 84021		
Section 32				
Lois Bleazard Trustee	96792	PO Box 510033 Mountain Home, UT 84051		
Duchesne /Wasatch Blue Bench Landfill	2158	Duchesne Co. Landfill C/O Manager P.O. Box 228 Duchesne, UT 84021		
El Paso Exploration and Production		El Paso Exploration and Production Attention: Jordan Nelson Senior Production Engineer 1099 18th Street, Suite 1900 Denver, CO 80202		Operator in Sections 29, 30,31, 32 2S 4W

**RECEIVED****APR 11 2011****DIV. OF OIL, GAS & MINING**




BEFORE THE DOGM in and for the STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF IWM SEEKING  
FOR ADMINISTRATIVE APPROVAL,  
PURSUANT TO RULE C-11, AUTHORIZING THE DRILLING  
OF AN INJECTION WELL AND THE UNDERGROUND DISPOSAL OF  
WATER PRODUCED AS A BY PRODUCT OF OIL AND GAS  
PRODUCTION

CERTIFICATE of MAILING

State of Utah  
County of Duchesne

Robert L. Ballou, Agent for applicant, Integrated Water Management, deposes and affirms that on April 8th 2011 he caused to be deposited in the US mail, copies of the application as directed by the DOGM for the above entitled matter to the list referred to as Exhibit "F", and that the addresses given in that exhibit are correct to the best of the affiant's information and belief; such exhibit includes all lease holders, offset operators and surface owners within a 1/2 mile radius of the proposed SWD described in the application.




Robert L. Ballou PG -Consultant

RECEIVED


APR 11 2011

DIV. OF OIL, GAS & MINING

Subscribed and sworn to before me this 8<sup>th</sup> day of April 2011.



My commission expires: 10.18.13



Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066  
Office 435-722-3555 Fax 435-722-3556 Cell 435-724-2500  
rballou@stratanet.com  
March 24, 2011

Re: SWD Well project for Integrated Water Management.

To all mineral and surface owners:

By way of introduction, my name is Bob Ballou and as a professional registered geologist, I have been retained by Integrated Water Management (IWM) to assist them in permitting, business development and operations for their SWD facility in Duchesne Co., Utah. IWM has permitted a SWD well to be drilled and utilized in conjunction with its current operation of processing and storing produced oilfield water in SWD evaporation pits.

As part of the permitting process to drill a new SWD well it is a DOGM requirement that all offset operators (El Paso), and all entities with ownership of mineral interests and surface interests within a 1/2 mile radius of the proposed well bore be notified.

The IWM facility is located about 8 miles north of Duchesne just east of Hwy 87 and north of the Duchesne Co. Landfill. The location of the facility is in the SE/SE of section 30 2S 4W. Currently the facility consists of 2 small lined containment ponds and 3 lined evaporation ponds with a calculated total fluid capacity of approximately 900,000 bbls.

Integrated Water Management LLC was formed as a service entity and operator in Duchesne County, Utah to provide oilfield service in the form of a produced water disposal facility serving producing operators primarily in Duchesne Co., Utah.

**Background:**

After securing a conditional use permit and the proper business licenses from Duchesne County, and after a permitting and construction phase in the summer and fall of 2010, which included purchasing and cleaning up the Grant Bleazard disposal facility (an environmental eyesore that had been idle for over 20 years), a fully bonded and DOGM approved Integrated Water Management (IWM) commenced operations in December.

Operations have exceeded expectations and the volume of fluids has increased to several thousand barrels a day from a number of different operators including El Paso, Bill Barrett Resources, Gasco, Newfield Production, Berry Petroleum and others.

**RECEIVED**

**APR 11 2011**

**DIV. OF OIL, GAS & MINING**

For a number of reasons the decision was made to initiate the permitting process for drilling a new SWD well on IWM's property. The footprint for the actual SWD well will be very small and aside from the well head and pump house no additional equipment will be installed at the IWM facility, as IWM will utilize their current unloading and in place tank farms for normal operations.

In short the addition of a SWD well at IWM's current location will provide a means wherein IWM can increase the capacity to their pits without depending solely on evaporation. SWD wells have been successfully utilized by various operators in this portion of the basin since the first wells were drilled in the early 70's. Geologically the sands are well suited to receive the injected fluids with the fluid injected well below frac gradient pressures.

Currently there are eight SWD wells within 6 miles of the IWM proposed SWD well location and collectively they have disposed of tens of millions of bbls of produced water with no reported ill effects.

A complete copy of the permit is located at the DOGM offices in Salt Lake City, Utah and can be reviewed by request. Additionally should any question arise concerning the nature or scope of the project please do not hesitate to contact me.

Thank you,



Robert Ballou

Ballou Geologic Consulting

cc. IWM, DOGM, Duchesne Co.

enc.

**RECEIVED**

**APR 11 2011**

**DIV. OF OIL, GAS & MINING**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 1

APPLICATION FOR INJECTION WELL

Name of Operator Integrated Water Management	Utah Account Number N	Well Name and Number IWM SWD 3-30 B4
Address of Operator PO Box 430      CITY Altamont      STATE UT      ZIP 84001	Phone Number (435) 454-4646	API Number
Location of Well Footage : 800' FEL, 300' FSL      County : Duchesne QQ, Section, Township, Range: SESE 30 2S 4W      State : UTAH		Field or Unit Name Lease Designation and Number

Is this application for expansion of an existing project?      Yes ☐      No ☒

Will the proposed well be used for:	Enhanced Recovery?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
	Disposal?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Storage?	Yes <input type="checkbox"/>	No <input type="checkbox"/>

Is this application for a new well to be drilled?      Yes ☒      No ☐

If this application is for an existing well, has a casing test been performed?      Yes ☐      No ☐  
Date of test: \_\_\_\_\_

Proposed injection interval:      from 4,000      to 5,500

Proposed maximum injection:      rate 5,000      bpd      pressure 800      psig

Proposed injection zone contains oil ☒, gas ☐, and / or fresh water ☐ within 1/2 mile of the well.

List of attachments: Attached are write up with exhibits

ATTACH ADDITIONAL INFORMATION AS REQUIRED BY CURRENT  
UTAH OIL AND GAS CONSERVATION GENERAL RULES

I hereby certify that this report is true and complete to the best of my knowledge.

Name (Please Print) Robert Ballou

Title PG- Consultant

Signature 

Date 4/7/2011

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING


FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO:	6. SURFACE: Fee
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER <u>SWD</u> SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Integrated Water Management				9. WELL NAME and NUMBER: IWM SWD 3-30 B4	
3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>			PHONE NUMBER: (435) 454-4646		
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: 800' FEL, 300' FSL  AT PROPOSED PRODUCING ZONE: Proposed Injection Interval: 4000'-5500'				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE:  8 miles North and 1 mile East of Duchesne, Utah				12. COUNTY: Duchesne	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET)  300'		16. NUMBER OF ACRES IN LEASE:		17. NUMBER OF ACRES ASSIGNED TO THIS WELL:	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1632', Christman Blann 1-31 B4		19. PROPOSED DEPTH:  5,500		20. BOND DESCRIPTION:	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.):  Gr 6128'		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION:	

24. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT	
12 1/4"	9 5/8" J55 40#	500		
8 3/4"	7" J55 23-29#	5,500		

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> COMPLETE DRILLING PLAN  <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <u>Robert Ballou</u>	TITLE <u>PG- Consultant</u>
SIGNATURE <u></u>	DATE <u>4/7/2011</u>

(This space for State use only)

API NUMBER ASSIGNED: \_\_\_\_\_

APPROVAL: \_\_\_\_\_

**RECEIVED**

**APR 11 2011**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 1

APPLICATION FOR INJECTION WELL

Name of Operator Integrated Water Management	Utah Account Number N	Well Name and Number IWM SWD 3-30 B4
Address of Operator PO Box 430 CITY Altamont STATE UT ZIP 84001	Phone Number (435) 454-4646	API Number
Location of Well Footage : 800' FEL, 300' FSL County : Duchesne	Field or Unit Name	
QQ, Section, Township, Range: SESE 30 2S 4W State : UTAH	Lease Designation and Number	

Is this application for expansion of an existing project? Yes ☐ No ☒

Will the proposed well be used for:	Enhanced Recovery?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
	Disposal?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Storage?	Yes <input type="checkbox"/>	No <input type="checkbox"/>

Is this application for a new well to be drilled? Yes ☒ No ☐

If this application is for an existing well, has a casing test been performed? Yes ☐ No ☐  
Date of test: \_\_\_\_\_

Proposed injection interval: from 4,000 to 5,500

Proposed maximum injection: rate 5,000 bpd pressure 800 psig

Proposed injection zone contains oil ☒, gas ☐, and / or fresh water ☐ within 1/2 mile of the well.

List of attachments: Attached are write up with exhibits

ATTACH ADDITIONAL INFORMATION AS REQUIRED BY CURRENT  
UTAH OIL AND GAS CONSERVATION GENERAL RULES

I hereby certify that this report is true and complete to the best of my knowledge.

Name (Please Print) Robert Ballou

Title PG- Consultant

Signature

Date 4/7/2011

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING  
WATER DISPOSAL,  
STORAGE AND ENHANCED RECOVERY WELLS  
SECTION V - RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**

Integrated Water Management, a Utah Corporation is the operator of an existing SWD facility located 8 miles north and 1 mile east of Duchesne, Utah. IWM is bonded by the DOGM to conduct operations in its existing evaporation pits associated with its SWD operations. This application is submitted as support for IWM to drill and operate a commercial SWD well to be used in conjunction with current operations. Applicant proposes to dispose of such produced water by injection underground into the lower portion of the Duchesne River-Uintah formations underlying the proposed disposal well.

Applicant proposes to drill a SWD well to be designated the **IWM SWD 3-30 B4** and located 300 feet from the south line and 800 feet from the east line of section 30 2S, 4W, Duchesne, County, Utah. Location of the proposed drill site and other wells drilled within a 1/2 mile of the proposed location and surface owners are noted on exhibits A and B.

- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**

- 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.

- 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

Triple combination (Electric log, Density/Neutron) logs will be run and will be provided to the DOGM.

- 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A cement bond log (CBL) will be run and provided to the DOGM.

**RECEIVED**  
**APR 11 2011**  
**DIR OF OIL, GAS & MINING**

- 2.4 Copies of logs already on file with the Division should be referenced, but need not be re-filed.**

All copies of logs in area of review are on file with the Utah Division of Oil, Gas and Mining.

- 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The proposed casing program is 9-5/8", 40#, J-55 surface casing run to 500' GL, (cemented to surface), and 7" 23-29 # J-55 casing run from surface to approximately 5000-5500' (cemented to surface).

- 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be production water that has been cleaned and gravity fed to IWM's disposal pit #3. The estimated average rate of injection will be 2000 BPD, and the estimated maximum rate of injection will be 5000 BPD.

- 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

Production water analysis will vary depending on the company and associated location that the production is coming from. Included are representative analysis of produced water from 3 IWM costumer wells. See **Exhibit C-A, C-B, C-C**. Included as **Exhibit C1** are water analysis reports from two SWD wells in the immediate vicinity, (both drilled as SWD wells and not as recompletions from a producing oil and gas well, to a SWD well). These wells are;

To the east of the proposed IWM SWD 3-30 B4, **The Russell SWDW 2-32B4**.

To the west of the proposed IWM SWD 3-30 B4, **the LDS Church 2-27 B5**).

These water analysis reports are from actual swab tests of specific intervals and show that formation water from produced water and in the proposed injection interval, the Duchesne River-Uintah formations, are unfit for domestic livestock, irrigation or other general uses.

It is proposed that in the IWM SWD 3-30 B2, IWM will take two samples of formation water by production swab tests, one from the subsurface interval from 4000 to 4875 feet and the other test will be taken below 4875 feet over an interval to be selected. We will notify the DOGM prior to taking such samples and conducting such tests in order that the DOGM may witness the tests and take independent samples if desired.

RECEIVED

APR 11 2011

UTAH DIVISION OF OIL, GAS & MINING

**The proposed average and maximum injection pressures.**

Judging from the data collected from the similar wells in the immediate area The proposed average injection pressure will be approximately 400 psig and the maximum injection pressure will not exceed 800 psig.

**2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.**

The minimum fracture gradient for the IWM SWD 3-30 B4 calculates at 0.733 psig/ft. However a gradient step rate test will be run on the well to determine the maximum injection pressure. Historically this has not been an issue in the SWD wells located within a township of the IWM SWD 3-30 B4 as they all have operated at pressures of less than 800#, some much less.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief

**2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent**

**In the Russell SWDW 2-32B4** the gross injection zones are 2464'-3726', (2464'-2470', 2548'-2558', 2630'-2638', 2884'-2890', 3054'-3062', 3720'-3726', two holes per foot). Records from 1/86 to 9/10 show that this well disposed of 6,836,018 BW with a maximum tubing pressure of 830 # and an average tubing pressure of about 600#. Note: this figure does not include the unreported water that was put away from 1975-1986.

**In the LDS 2-27 B5** the gross injection zones are 2088-2860, ( 2088'-2098', 2129'-2136', 2312'-2317', 2370'-2374', 2377'-2383', 2407'-2413', 2416'-2419', 2515'-2522', 2559'-2561', 2817'-2819', 2840'-2860' one hole per foot); Records from 1/86 to 9/10 show that this well disposed of 33,654,635 BW with a maximum tubing pressure of 550 # . Note: this figure does not include the unreported water that was put away from 1975-1986. All perforations in the Duchesne River-Uintah formations.

**Note: The original scope of the project was to pattern the IWM SWD 3-30 B4 after the 2-32B4 and the 2-27 B5. However, after meeting with the DOGM it was agreed that due to possible environmental concerns a deeper injection interval horizon patterned after wells that injected into deeper horizons would satisfy DOGM concerns. The closest offset being the Rhodes 1-36 B5 a converted SWD well. Other close by wells that appear**

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

to be similar to the proposed IWM SWD 3-30 B4 are the Tew 1-9 B5 a converted SWD well with a perforation interval of 3700-5800' and 5900-6400'. Also the Erich 2-11 B5 that has injected into 4 injection intervals: 3749-3985', 4027-4496, 4576-5573', 5607-5810'.

In the Rhodes 1-36 B5 the gross injection zone intervals are: 4114' to 5055' the original plan was to perforate from 5070'-4583' (phase I) and if needed phase II would be from 4452'-4052' with the injection packer set 4520' for phase I. Records show that phase I and phase II were perf'd and injected into. All perforations in the lower Uinta Fm. Since the well was put into service in January of 1999 it has taken 13,813,822 bbls (to 9/10) for an average per day total of 4168 BW/d.

The reservoir is composed primarily of clastic fluviatile, lacustrine, and transitional sediments and is composed of sandstones, siltstones and shales. Carbonates are also encountered increasing with depth with numerous sandstones containing waters of varying degrees of salinity, porosity and permeability.

The completion reports and logs of these three wells are included in exhibit D, D1, D2.

- 2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.**

Well bore diagrams of the Katherine 3-29 B4 and Christman Blann 1-31 B4 are included as **Exhibit E**. Both wells are producing wells with no reported casing issues.

- 2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.**

See **Exhibit F**.

- 2.12 Any other Information that the Board or Division may determine is necessary to adequately review the application.**

The proposed injection zone is in the - Uintah Formation, upper Tgr fm. The IWM SWD 3-30 B4 well was patterned after the 1-36 B5 in closest in proximity to the IWM SWD 3-30 B2. The proposed injection zone will be determined by the porous intervals encountered in the drilling of the well but if

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING


consistent with other nearby SWD wells (1-36 B5 as noted but also the Tew 1-9 B5, and the Erich 2-11 B5), the zones are expected to be from 4000' to 5500'. The confining stratum directly above the injection zone is the Duchesne River formation and below the injection zones is the Green River Formation.

Integrated Water Management will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

**RECEIVED**


**APR 11 2011**

**DIV. OF OIL, GAS & MINING**



# DIV. OF OIL, GAS & MINING





RECEIVED

APR 11 2011

DIV OF OIL, GAS & MINING

Proposed Location:  
IWM SWD 3-30 B4

Water Well 43-2422

Katherine 2-29 B4

Water Well 43-10499

Christman Blann 1-31 B4

Water Well 43-9196

1/2 Mile Radius

Integrated Water Management  
IWM SWD 3-30 B4  
Section 30 2S, 4W  
Location: 800' from E, 300' from S  
Exhibit B

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING



1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

**Water Analysis Report**

Field : **Newfield** Sample Date : **4/18/2010**  
 County :  Formation :   
 Location : **FENCELINE 2-23-8-16** Rock Type :   
 Lab ID :  Depth :  Analysed Date: **1/5/2011**  
 Comments :

CATIONS	mg/l		Measured	Calculated		ANIONS	mg/l
Potassium	42.8	Total Dissolve Solid	17205.00	0.00		Sulfate	10.0
Sodium	6,776.3	Total Hardness		29.93		Chloride	10,000.0
Calcium	8.2	PH	8.27	0.00		Carbonate	0.0
Magnesium	2.3	Total H2S aq	0.00	0.00		Bicarbonate	878.4
Iron	1.2	Manganese	1.38			Bromide	0.0
Barium	13.0	PO4 Residual	0.00			Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	-			Hydroxide	0.0
<b>SUM +</b>	<b>6,843.8</b>	APB Vials Turned	-			<b>SUM -</b>	<b>10,888.4</b>

Initial(BH) Final(WH)

**Saturation Index values**Calcite (CaCO<sub>3</sub>)

-0.36 -0.48

Barite (BaSO<sub>4</sub>)

0.12 0.54

Halite (NaCl)

-3.01 -2.96

Gypsum

-4.34 -4.35

Hemihydrate

-4.90 -5.11

Anhydrite

-4.32 -4.59

Celestite

0.00 0.00

Iron Sulfide

0.00 0.00

Zinc Sulfide

0.00 0.00

Calcium fluoride

0.00 0.00

Iron Carbonate

0.74 0.46





Inhibitor needed (mg/L)

Calcite NTMP

0.00 0.00

Barite BHPMP

0.00 0.00



Lab Manager: Andrea Craig

Analysis by:

Exhibit C-A

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

**NALCO**

1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

**Water Analysis Report**

<b>Field :</b>	<b>Barrett</b>	<b>Sample Date :</b>	<b>8/16/2010</b>
<b>County :</b>		<b>Formation :</b>	
<b>Location :</b>	Prickly Pear Fed #12-24-12-14	<b>Rock Type :</b>	
<b>Lab ID :</b>		<b>Depth :</b>	<b>Analysed Date: 2/16/2011</b>

**Comments :**

<b>CATIONS</b>	<b>mg/l</b>		<b>Measured</b>	<b>Calculated</b>		<b>ANIONS</b>	<b>mg/l</b>
Potassium	356.5	Total Dissolve Solid	48046.00	0.00		Sulfate	1,040.0
Sodium	15,909.1	Total Hardness		6226.52		Chloride	27,900.0
Calcium	1,913.0	PH	6.79	0.00		Carbonate	0.0
Magnesium	352.2	Total H2S aq	0.00	0.00		Bicarbonate	1,220.0
Iron	83.4	Manganese	0.12			Bromide	0.0
Barium	4.0	PO4 Residual	0.00			Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	0.00			Hydroxide	0.0
<b>SUM +</b>	<b>18,618.2</b>	APB Vials Turned	0.00			<b>SUM -</b>	<b>30,160.0</b>

Initial(BH) Final(WH)

**Saturation Index values**

<b>Calcite (CaCO<sub>3</sub>)</b>	
2.01	0.86

<b>Barite (BaSO<sub>4</sub>)</b>	
0.70	1.82

<b>Halite (NaCl)</b>	
-2.08	-2.15

<b>Gypsum</b>	
-0.20	-0.42

<b>Hemihydrate</b>	
0.85	-1.21

<b>Anhydrite</b>	
1.28	-0.75

<b>Celestite</b>	
0.00	0.00

<b>Iron Sulfide</b>	
0.00	0.00

<b>Zinc Sulfide</b>	
0.00	0.00

<b>Calcium fluoride</b>	
0.00	0.00

<b>Iron Carbonate</b>	
1.81	1.12

**Inhibitor needed (mg/L)**

<b>Calcite</b>	<b>NTMP</b>
105.51	0.00

<b>Barite</b>	<b>BHPMP</b>
8.91	0.65






 Lab Manager: Andrea Craig  
 Analysis by:

Exhibit C-B

# Production Water Report and Scaling Tendencies

Creg Wilkins

12/17/2003

Version : 947

Analysis by : <b>Creg Wilkins</b>
Field :
County : <b>Uintah</b>
Lab ID# : <b>El Paso Production</b>
Sample Date : <b>13-Apr-09</b>
Location : <b>2-9B4</b>
Formation :
Depth :
Rock Type:
Porosity:
Permeability:

INPUT Sample Temp °F :	<b>60.0</b>	INPUT TDS @180 °C, mg/L	<b>54,491</b>
INPUT Downhole Temp °F :	<b>125.0</b>	Calc TDS (less CO <sub>2</sub> ), mg/L	<b>54,491</b>
INPUT Sample Press :	<b>6.0</b>	INPUT Resistivity @ 68°F	<b>0.150</b>
INPUT sample pH, su	<b>10.00</b>	Calculated Resistivity @ 68°F	<b>0.150</b>
Input mole % CO <sub>2</sub>	<b>0.04</b>	Input Conductivity, µmhos/cm	<b>66,667</b>
pH resulting from CO <sub>2</sub>	<b>10.02</b>	Calc Cond@25 °C, µmhos/cm	<b>66,667</b>
Calc Carbon Dioxide (Aq), mg/L	<b>0.2</b>	INPUT Density @ STP, g/mL	<b>1.039</b>
Carbon Dioxide, CO <sub>2</sub> mg/L	<b>0.0</b>	Calc Density @STP, g/mL	<b>1.039</b>
Total Sulfide, mg/L	<b>6.0</b>	MicroBiological - # of bottles turned	
Dissolved Oxygen, ppm		SRBs :	( 1 )
Dissolved Oxygen, ppb	<b>0.0</b>	Aerobic Bacteria :	( 1 )

K <sup>+</sup>	<b>172.0</b>
Na <sup>+</sup>	<b>20,990.9</b>
Na <sup>+</sup> by Diff	<b>+ 0.00</b>
Ca <sup>++</sup>	<b>60.0</b>
Mg <sup>++</sup>	<b>378.2</b>
Fe <sup>++</sup>	<b>3.8</b>
Ba <sup>++</sup>	<b>125.0</b>
Sr <sup>++</sup>	<b>0.0</b>
Br <sup>-</sup>	<b>0.0</b>
SO <sub>4</sub> <sup>=</sup>	<b>1,600.0</b>
Cl <sup>-</sup>	<b>30,000.0</b>
CO <sub>3</sub> <sup>=</sup>	<b>1,560.0</b>
HCO <sub>3</sub> <sup>-</sup>	<b>1,342.0</b>
OH <sup>-</sup>	<b>0.0</b>
Organic Acid	<b>0.0</b>

Note: Organic Acids as Acetate

Titration - if values are placed in mls or digits - results will transfer to Water Report

Parameter	mls	Digits	Sample Size	Normality	Results
CO <sub>2</sub>	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>3.636</b>	
H <sub>2</sub> S	<b>0</b>	<b>0.0</b>	<b>10</b>	<b>0.3998</b>	
T reading	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>8.0</b>	
P reading	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>1.6</b>	
Ca <sup>++</sup>	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
THardness	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
Cl <sup>-</sup>	<b>0</b>	<b>0.0</b>	<b>1</b>	<b>2.256</b>	

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

Comments: Mn .45

Exhibit Cc

PARTIAL

75 086

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE JAN. 16 1979  
Sample Received on  
Analysis Authorization

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒  
WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

RECEIVED

APR 11 2011

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

DIV. OF OIL, GAS & MINING

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL No.

2-27B5 SEC 27, T2S, R5W (USM) DUCHEPNE CO.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2088 TO 2383 LEVEL

SUPPLY OWNED BY:

PRESENT USE OF SUPPLY:

PROPOSED USE OF SUPPLY:

SAMPLE COLLECTED BY: CLEW FEIGHT, OIL & GAS DIV. DATE:

REPORT RESULTS TO: R. WINSLOW RNM PHONE:

Address: BLDG 72

DO NOT WRITE BELOW DOUBLE LINE

# RESULTS OF ANALYSIS

Turbidity	J.T.U.	Iron (total) as Fe	mg/l
Conductivity 22,200	micromhos/cm	Iron in filtered sample as Fe	mg/l
pH 10.00		Lead as Pb	mg/l
Total Dissolved Solids 17,560	17,560	Magnesium as Mg	mg/l
Alkalinity (total) as CaCO <sub>3</sub> 44.28	mg/l	Manganese as Mn	mg/l
Aluminum as Al	mg/l	Mercury as Hg	mg/l
Arsenic as As	mg/l	Nitrate as N	mg/l
Barium as Ba	mg/l	Nitrite as N	mg/l
Bicarbonate as HCO <sub>3</sub>	mg/l	Phosphate as PO <sub>4</sub>	mg/l
Boron as B	mg/l	Phenols as Phenol	mg/l
Cadmium as Cd	mg/l	Potassium as K	mg/l
Calcium as Ca	mg/l	Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>	mg/l	Silica as SiO <sub>2</sub>	mg/l
Chloride as Cl	8,000	Silver as Ag	mg/l
Chromium (hexavalent) as Cr	mg/l	Sodium as Na	7000 mg/l
Copper as Cu	mg/l	Sulfate as SO <sub>4</sub>	500 mg/l
Cyanide as CN	mg/l	Surfactant as MBAS	mg/l
Fluoride as F	mg/l	Zinc as Zn	mg/l
Hardness (total) as CaCO <sub>3</sub> 176	mg/l	Total Alpha	pci/l
Hydroxide as OH	mg/l	Total beta	pci/l
Ammonia N as NH <sub>3</sub>			i/l
			mg/l

Exhibit C1



# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

(801) 722-2254

RECEIVED

APR 11 2011

LABORATORY NUMBER W-2129

SAMPLE TAKEN \_\_\_\_\_

SAMPLE RECEIVED 4-18-75

RESULTS REPORTED 4-18-75

DIV. OF OIL, GAS & MINING

## SAMPLE DESCRIPTION

COMPANY Husky Oil Co.

LEASE Russell

FIELD NO. \_\_\_\_\_

WELL NO. 2-32B4

FIELD Altamont COUNTY Duchesne STATE Utah

SAMPLE TAKEN FROM \_\_\_\_\_

PRODUCING FORMATION Duchesne River - Uinta TOP 2548-2558

REMARKS \_\_\_\_\_

SAMPLE TAKEN BY Warren Johnston

## CHEMICAL AND PHYSICAL PROPERTIES

SPECIFIC GRAVITY @60/60° F. 1.0146 pH 8.28 RES. 0.30 OHM METERS @ 77°F


TOTAL HARDNESS 1155.47 mg/L as CaCO<sub>3</sub>

TOTAL ALKALINITY 360.0 mg/L as CaCO<sub>3</sub>


CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca ++	273.0	13.65		
MAGNESIUM - Mg ++	114.0	9.34		
SODIUM - Na +	8450.0	367.39		
BARIUM (INCL. STRONTIUM) - Ba ++	10.6	0.15		
TOTAL IRON - Fe ++ AND Fe +++	2.55	0.09	390.62	
BICARBONATE - HCO <sub>3</sub> --	360.0	5.90		
CARBONATE - CO <sub>3</sub> --	0	0		
SULFATE - SO <sub>4</sub> --	1500.0	31.25		
CHLORIDE - CL -	11695.3	329.45	366.69	
TOTAL DISSOLVED SOLIDS	20120.			

## MILLEQUIVALENTS PER LITER

LOGARITHMIC



STANDARD



ANALYST \_\_\_\_\_

CHECKED \_\_\_\_\_

Exhibit C1



# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

LABORATORY NUMBER W-2123  
SAMPLE TAKEN 4-17-75  
SAMPLE RECEIVED 4-17-75  
RESULTS REPORTED 4-17-75

## SAMPLE DESCRIPTION

COMPANY Husky Oil LEASE Russell FIELD NO. 2-32B4  
FIELD Altamont COUNTY Duchesne STATE Utah  
SAMPLE TAKEN FROM Duchesne River - Uinta TOP 2464 - 2470  
PRODUCING FORMATION TOP  
REMARKS

SAMPLE TAKEN BY


## CHEMICAL AND PHYSICAL PROPERTIES

SPECIFIC GRAVITY @60/60° F. 1.0138 pH 8.91 RES. 0.50 OHM METERS @ 77°F

TOTAL HARDNESS 254.35 mg/L as CaCO<sub>3</sub> TOTAL ALKALINITY 352.0 mg/L as CaCO<sub>3</sub>

CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca ++	51.15	2.56		
MAGNESIUM - Mg ++	30.30	2.48		
SODIUM - Na +	4890.0	212.61		
BARIUM (INCL. STRONTIUM) - Ba ++	2.9	0.04		
TOTAL IRON - Fe ++ AND Fe +++	1.07	0.04	217.73	
BICARBONATE - HCO <sub>3</sub> --	260.0	4.26		
CARBONATE - CO <sub>3</sub> --	92.0	3.07		
SULFATE - SO <sub>4</sub> --	2600.0	54.17		
CHLORIDE - CL --	9596.2	270.32	331.82	
TOTAL DISSOLVED SOLIDS	17440.			

MILLEQUIVALENTS PER LITER



AI

CI

Exhibit C1



A

PARTIAL

75 085

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE  
Sample Received on APR 11 2011  
Analysis Authorization

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒  
WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

RECEIVED

APR 11 2011

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

DIV. OF OIL, GAS & MINING

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL NO.

2-2785 Sec 27, T2S, R5W (USM) DUCHENE Co.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2817 TO 2860 LEVEL.

SUPPLY OWNED BY: \_\_\_\_\_

PRESENT USE OF SUPPLY: \_\_\_\_\_

PROPOSED USE OF SUPPLY: \_\_\_\_\_

SAMPLE COLLECTED BY: CLEON FREIGHT, OIL & GAS DIV. DATE: \_\_\_\_\_

REPORT RESULTS TO: R. HINSHAW RHT PHONE: \_\_\_\_\_

Address: BLDG 72.

DO NOT WRITE BELOW DOUBLE LINE

RESULTS OF ANALYSIS

Turbidity	J.T.U.	Iron (total) as Fe	mg/l
Conductivity	micromhos/cm	Iron in filtered sample as Fe	mg/l
pH	7.70	Lead as Pb	mg/l
Total Dissolved Solids	18,340	Magnesium as Mg	mg/l
Alkalinity (total) as CaCO <sub>3</sub>	2790	Manganese as Mn	mg/l
Aluminum as Al		Mercury as Hg	mg/l
Arsenic as As		Nitrate as N	mg/l
Barium as Ba		Nitrite as N	mg/l
Bicarbonate as HCO <sub>3</sub>	3500	Phosphate as PO <sub>4</sub>	mg/l
Boron as B		Phenols as Phenol	mg/l
Cadmium as Cd		Potassium as K	mg/l
Calcium as Ca		Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>		Silica as SiO <sub>2</sub>	mg/l
Chloride as Cl	27.5	Silver as Ag	mg/l
Chromium (hexavalent) as Cr		Sodium as Na	7080 mg/l
Copper as Cu		Sulfate as SO <sub>4</sub>	220 mg/l
Cyanide as CN		Surfactant as MBAS	mg/l
Fluoride as F		Zinc as Zn	0.04 mg/l
Hardness (total) as CaCO <sub>3</sub>	10	Total Alpha	pci/l
Hydroxide as OH		Total beta	pci/l
Ammonia N as NH <sub>3</sub>			nci/l
			mg/l

Exhibit C<sub>1</sub>

**SPONTANEOUS-POTENTIAL**  
MILLIVOLTS

$\frac{10}{- \left| \frac{10}{100} \right| +}$

**CONDUCTIVITY**  
MILLIMHOLES M<sup>-1</sup> CM<sup>-1</sup> TEMPERATURE 25°C

DEEP INDUCTION LOG

yes 2.90


RESISTIVITY OHMS M <sup>2</sup> M	
DEEP INDUCTION LOG	
0	100
0	1000
AVERAGED LATEROLOG - 2	
0	100
0	1000

0000

0050


0100

# Exhibit D



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING


TOP OF DISPOSAL  
ZONE 2090'



RECEIVED


APR 11 2011

DIV. OF OIL, GAS & MINING



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING

DETAIL LOG		
SPONTANEOUS POTENTIAL MILLIVOLTS	DEPTH FEET	RESISTIVITY OHMS IN. FT.
		DEEP INDUCTION LOG
10		LATERAL LOG - 2



APR 11 2001

14 PF

## STATE OF UTAH

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

DIV OF OIL, GAS &amp; MINING


## OIL &amp; GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL:				OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other <u>SWD Well</u>				5. LEASE DESIGNATION AND SERIAL NO.			
b. TYPE OF COMPLETION:				NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____				Patented			
2. NAME OF OPERATOR								6. IF INDIAN, ALLOTTEE OR TRIBE NAME			
Shell Oil Company								7. UNIT AGREEMENT NAME			
3. ADDRESS OF OPERATOR								8. FARM OR LEASE NAME			
1700 Broadway, Denver, Colorado 80202								L.D.S. Church			
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*								9. WELL NO.			
At surface 551' FSL and 2556' FEL, Section 27								2-27B5 SWD			
At top prod. interval reported below								10. FIELD AND POOL, OR WILDCAT			
At total depth								Altamont			
14. PERMIT NO. 43-013-30340								12. COUNTY OR PARISH			
DATE ISSUED 9/26/74								13. STATE			
15. DATE SPUNDED 11/3/74								Duchesne Utah			
16. DATE T.D. REACHED 11/12/74		17. DATE COMPL. (Ready to prod.) 1/4/75		18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5887KB, 5860 GL		19. ELEV. CASINGHEAD 5862					
20. TOTAL DEPTH, MD & TVD 4205		21. PLUG, BACK T.D., MD & TVD 4075 (FC)		22. IF MULTIPLE COMPL., HOW MANY* -		23. INTERVALS DRILLED BY -		ROTARY TOOLS CABLE TOOLS			
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*								25. WAS DIRECTIONAL SURVEY MADE			
2088-2860 (gross interval) Duchesne River-Uinta								No			
26. TYPE ELECTRIC AND OTHER LOGS RUN								27. WAS WELL CORED			
BHCS, PDC, CBL								No			
28. CASING RECORD (Report all strings set in well)											
CASING SIZE		WEIGHT, LB./FT.		DEPTH SET (MD)		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED	
9-5/8"		40#		305'		12-1/4"		300 sx		0	
7"		23#, 26#, 29#		4,205'		8-3/4"		1080 cu ft		0	
29. LINER RECORD										30. TUBING RECORD	
SIZE		TOP (MD)		BOTTOM (MD)		SACKS CEMENT*		SCREEN (MD)		SIZE	
										2-7/8"	
										2014'	
										2000'	
31. PERFORATION RECORD (Interval, size and number)						32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.					
2088-2098, 2129-2136, 2312-2317, 2370-2374, 2377-2383, 2407-2413, 2416-2419, 2515-2522, 2559-2561, 2817-2819, 2840-2860						DEPTH INTERVAL (MD)					
(1 hole/ft w/Jumbo jets, 72 holes total)						AMOUNT AND KIND OF MATERIAL USED					
						2817-2860 2200 gal 15% HCl					
						2312-2561 2300 gal 15% HCl					
						2088-2136 1700 gal 15% HCl					
33. PRODUCTION											
DATE FIRST PRODUCTION 1/4/75		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)						WELL STATUS (Producing or shut-in)			
		Injecting into SWD well						Injecting			
DATE OF TEST 1/26/75		HOURS TESTED 24		CHOKE SIZE -		PROD'N. FOR TEST PERIOD -		OIL—BBL. -		GAS—MCF. -	
								WATER—BBL. 3390		GAS-OIL RATIO -	
FROM TEST PRESS. 250		CASING PRESSURE -		CALCULATED 24-HOUR RATE -		OIL—BBL. -		GAS—MCF. -		WATER—BBL. 3390	
										OIL GRAVITY-API (CORR.) -	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)										TEST WITNESSED BY	
35. LIST OF ATTACHMENTS											
Well History Report											
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records											
SIGNED <u>T.S. Mize</u> TITLE <u>Division Operations Engr.</u> DATE <u>1/29/75</u>											








2300

2400

2500

1st



RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING

2600

2700

2800

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

2900

3000

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

3100


3200

3300

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



3400

3500




RECEIVED

APR 11 2 11

DIV. OF OIL, GAS & MINES






3600

3700

3800



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING



3800

3900

FR

4000

SP

LLP

ELM

ELD

RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

Cal. Before  
Survey

STATE OF UTAH

SUBMIT IN DUPLICATE\*

(See other instructions on reverse side)

## OIL &amp; GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

5. LEASE DESIGNATION AND SERIAL NO.

FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Russell

9. WELL NO.

SWDW 2-32 B4

10. FIELD AND POOL, OR WILDCAT  
Altamont11. SEC., T., R., M., OR BLOCK AND SURVEY  
OR AREA

Section 32

T2S, R4W

12. COUNTY OR  
PARISH  
Duchesne

13. STATE

Utah

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☐ DRY ☐ Other SWD Well

b. TYPE OF COMPLETION:

NEW ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other \_\_\_\_\_

2. NAME OF OPERATOR

Husky Oil Company of Delaware

3. ADDRESS OF OPERATOR

P. O. Box 380, Cody, Wyoming 82414

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface S $\frac{1}{2}$  NE (1919' FNL, 1317' FEL) Sec. 32, T2S, R4W

At top prod. interval reported below

At total depth

14. PERMIT NO.

DATE ISSUED

15. DATE SPUDDED

3-21-75

16. DATE T.D. REACHED

3-28-75

17. DATE COMPL. (Ready to prod.)

4-17-75

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\*

6145.8 KB, 6134 GL

19. ELEV. CASINGHEAD

6136

20. TOTAL DEPTH, MD &amp; TVD

4000

21. PLUG, BACK T.D., MD &amp; TVD

3936

22. IF MULTIPLE COMPL.,  
HOW MANY\*23. INTERVALS  
DRILLED BY

ROTARY TOOLS

CABLE TOOLS

Total

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\*

2464-3720 (gross interval) Duchesne River - Uinta

25. WAS DIRECTIONAL  
SURVEY MADE

no

26. TYPE ELECTRIC AND OTHER LOGS RUN

GHC-GR, DIL, CBL

27. WAS WELL CORED

no

28. CASING RECORD (Report all strings set in well)

CASINO SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
9-5/8"	40#	380'	12-1/4"	175 sacks	0
5-1/2"	15.5#	3982'	8-1/2"	1305 sacks	0

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	2412'	2391'

31. PERFORATION RECORD (Interval, size and number)

2464-2470, 2548-2558,  
2630-2638, 2884-2890,  
3054-3062, 3720-3726  
(2 holes/ft.)

6 1/2" x 5/8"

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
	none

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
		injecting into SWD well				shut in	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
4-17-75			→				
FROM Casing Press.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
500 psig		→			3000 (est.)		
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)					TEST WITNESSED BY		

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Well history report, Cement Bond logs

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

R. Warren Johnston

TITLE

Senior Engineer

DATE

4-24-75

(See Instructions and Spaces for Additional Data on Reverse Side)

Schlumberger

CSU

DUAL INDUCTION - SFL

COMPANY: LINMAR ENERGY CORPORATION

WELL: BROTHERSON 2-35B5

FIELD: ALTAMONT  
COUNTY: DUCHESNE  
STATE: UTAH  
NATION: USA  
LOCATION: SE / NE

SEC: 35 TWP: 2S

RGE: 5M

PERMANENT DATUM: GL  
ELEV. OF PERM. DATUM: 5817.0 F  
LOG MEASURED FROM: KB  
20.0 F ABOVE PERM. DATUM  
DRLG. MEASURED FROM: KBELEVATIONS-  
KB: 5837.0 F  
DF: 5836.0 F  
GL: 5817.0 FDATE: 14 APR 84  
RUN NO: 152OTHER SERVICES-  
FDC  
CNL  
CYBERLOOKPROGRAM  
TAPE NO:  
26.2  
SERVICE  
ORDER NO:  
267137DEPTH-DRILLER: 10020.0 F  
DEPTH-LOGGER: 9997.0 F  
BTM. LOG INTERVAL: 9988.0 F  
TOP LOG INTERVAL: 2511.0 F  
CASING-DRILLER: 2508 F  
CASING-LOGGER: 2511 F  
CASING: 9.625  
BIT SIZE: 8.75

## RUN 1

TYPE FLUID IN HOLE:

DENSITY:

VISCOSITY:

PH:

FLUID LOSS:

SOURCE OF SAMPLE:

RM:

RMF:

RMC:

SOURCE RMF/RMC:

RM AT BHT:

RMF AT BHT:

RMC AT BHT:

TIME CIRC. STOPPED:

TIME LOGGER ON BTM.:

MAX. REC. TEMP:

LOGGING UNIT NO:

LOGGING UNIT LOC:

RECORDED BY:

WITNESSED BY:

GEL-YP

10.2 LB/G

39.0 S

10.5

16.0 C3

MUD TANK

.660 DHMM AT 70.0 DEGF

.440 DHMM AT 70.0 DEGF

.990 DHMM AT 70.0 DEGF

MEAS/CALC

.260 DHMM AT 188. DEGF

.173 DHMM AT 188. DEGF

.390 DHMM AT 188. DEGF

0900 4/14

1445 4 /14

188.0 DEGF

8305

VERNAL

T. TEIPNER K. FOX

JIM GARCIA

REMARKS:

-Exhibit D2


RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

GR (GAPI)		ILD (OHMM)		TENS(LB )	
0.0	150.00	0.0	100.00	0.0	10000.
SP (MY 10)		SFLA(OHMM)		CILD(MMHD)	
-100.0	0.0	0.0	100.00	400.00	


FILE 3 14-APR-84 17:36



RECEIVED

APR 11 2011


DIV. OF OIL, GAS & MINING



RECEIVED

APR 11 2011


DIV. OF OIL, GAS & MINING



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING




RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING





RECEIVED  
APR 11 2011  
DIV. OF OIL, GAS & MINING

# SWD CONVERSION PROCEDURE

Revision #1

June 12, 1997

RHOADES-MOON #1-36B5

Section 36-T2S-R5W  
Altamont Field  
Duchesne County, Utah

## WELL DATA

Location: 1178' FEL, 1178' FNL  
Elevation: 6077' GL; 6105' KB  
Total Depth: 12,100' PBTD: 9390' (RBP)  
Casing: 13-3/8" 48# H-40 @ 315' KB cmt'd to surf w/ 300 sks  
9-5/8" 40# J-55(103 jts) and N-80 (38 jts) @ 5799' KB cmt'd w/ 600sks  
7" 26# S-95 (64 jts) & N-80 (186 jts) @ 10,198' KB cmt'd w/ 380 sks  
DV collar @ 8148' cmt'd w/ 590 sks.  
5" 18# N-80 from 9,872' to 12,092' cmt'd w/ 210 sks  
Tubing: 2-7/8" N-80 EUE 8 rd @ 8905' open ended.

## TUBULAR DATA

Description	ID	Drift	Capacity (BPF)	Burst (PSI)	Collapse (PSI)
9-5/8" 40# J-55	8.835"	8.679"	.0773	3950	2570
9-5/8" 40# N-80	8.835"	8.679"	.0773	5750	3090
7" 26# S-95	6.276"	6.151"	.0382	8600	5870
7" 26# N-80	6.276"	6.151"	.0382	7240	5410
5" 18# N-80	4.276"	4.151"	.0177	10140	10490

## WELL HISTORY

- 6/74 Initial completion. Perforate from 10,669' to 11,691', 2 SPF, 164 holes. Acidize w/ 20,000 gals 15% HCl. Prod 50 BOPD, 250 MCFPD, 125 BWPD.
- 4/76 Added perforations 10,214' to 11,548'. 374 holes. Acidize with 20,000 gals 7-1/2% HCl.  
Prior Production: 15 BOPD, 60 MCFPD, 5 BWPD  
Post Production: 75 BOPD, 225 MCFPD, 35 BWPD
- 2/81 Acidized w/ 10,000 gals 15% HCl  
Prior Production: 15 BOPD, 60 MCFPD, 5 BWPD  
Post Production: 25 BOPD, 75 MCFPD, 20 BWPD

RECEIVED

APR 11 2001

DIV. OF OIL, GAS & MINING

STATE OF UTAH

## OIL &amp; GAS CONSERVATION COMMISSION

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other _____				5. LEASE DESIGNATION AND SERIAL NO. <b>FEE</b>	
b. TYPE OF COMPLETION: NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other _____				6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR <b>HUSKY OIL COMPANY OF DELAWARE</b>				7. UNIT AGREEMENT NAME	
3. ADDRESS OF OPERATOR <b>P. O. Box 380, Cody, Wyoming 82414</b>				8. FARM OR LEASE NAME <b>Rhoades</b>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface <b>1178' FEL, 1178' FNL Sec 36, T2S, R5W</b> At top prod. interval reported below <b>Same</b> At total depth <b>Same</b>				9. WELL NO. <b>1-36</b>	
14. PERMIT NO. _____ DATE ISSUED _____				10. FIELD AND POOL, OR WILDCAT <b>Altamont</b>	
15. DATE SPUDDED <b>3-16-74</b> 16. DATE T.D. REACHED <b>5-22-74</b> 17. DATE COMPL. (Ready to prod.) <b>7-4-74</b>				11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA <b>36 T2S-R5W</b>	
18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* <b>6077 Gr. Ungraded</b>				12. COUNTY OR PARISH <b>Duchesne</b>	
19. ELEV. CASINGHEAD <b>6077</b>				13. STATE <b>Utah</b>	
20. TOTAL DEPTH, MD & TVD <b>12095</b> 21. PLUG, BACK T.D., MD & TVD <b>11990</b>				23. INTERVALS DRILLED BY _____ ROTARY TOOLS _____ CABLE TOOLS _____	
22. IF MULTIPLE COMPL., HOW MANY* _____				24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* <b>11686-691 11652-657 11454-459 11120-125 10782-789 Wasatch</b> <b>11662-673 11616-621 11175-179 10854-870 10756-765 10669-679</b>	
25. WAS DIRECTIONAL SURVEY MADE <b>NO</b>				26. TYPE ELECTRIC AND OTHER LOGS RUN <b>DUL. IND. LL-GR. BHCS-GR. FDC-CNL-GR.</b>	
27. WAS WELL CORED <b>NO</b>				28. CASING RECORD (Report all strings set in well)	
CASING SIZE		WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD
13-3/8		48#	315 K.B.	17-1/2"	300 sks class G 3% CaCl <sub>2</sub>
9-5/8		40#	5612 K.B.	12-1/4"	400 sks lite 200sks class G
7		26#	10200 K.B.	8-1/2"	180 sks lite 200sks class G
29. LINER RECORD		30. TUBING RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE
5"	9872	12092	210 sks		2-7/8
					1-1/2
					5026.56
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.	
11686-691 11454-459 10756-765				DEPTH INTERVAL (MD)	
11662-673 11175-179 10669-679				AMOUNT AND KIND OF MATERIAL USED	
11652-657 11120-125 2 jet shots per ft.				All Perfs	
11616-621 10854-870				20,000 Gal 15% HCL	
10782-789				6,000# Unibeads	
				600# Buttons	
				264 Balls	
33. PRODUCTION					
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)			WELL STATUS (Producing or shut-in)
6-12-74		Flowing			Producing
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.
7-4-74	24	16/64	→	106	379
WATER—BBL.	GAS-OIL RATIO				
43	3575 SCF/BBL				
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.
300 PSIG		→	37	260	127
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)					TEST WITNESSED BY
Vented (connection to gas plant)					Glynn Mayson
35. LIST OF ATTACHMENTS					

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Joe C. Hugo

TITLE

PRODUCTION ENGINEER


DATE

7-8-74

\*(See Instructions and Spaces for Additional Data on Reverse Side)

# 04-06 El Paso Katherine 3- B4

## Casing Schematic



## CHRISTMAN BLANN 1-31B4

Sec 31; 2S; 4W

## Average Production:

19 25 BOPD  
 150 125 BOPD  
 85 MCFD

Downhole Pump:  
 Jet

Surface Equipment:  
 J100 belt drive

Comments:  
 SWD line to L. Russel 2-32B4

2 7/8" Scab Liner  
 9399-10,350'  
 Cemented w/45 sx

1.90 Heat String to 1870'

9 5/8" 40 # K-55 @ 4519'

2 7/8" Tubing EUE 8rd N80

Packer: 7" Lokset @ 9254  
 (Bottom part of a previous Lokset  
 was left @ 9265' Mar '80)

TOL: 4 1/2" @ 9738'

9920' Tight spot in 4 1/2"

7" Shoe: 10,052' 23+26 # 1/-80

Perfs: 10,409-11,545' Aug '73

58 holes

Perfs: 10,805-11,953' May '73

16 holes

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING

4 1/2" Shoe: 12,024' 13.5 # P-110

Cmt L/621 st 50/50 132

PRTD  
IFKH

31-Aug-94

TD w/ 14.6 ppq .11.11.

Exhibit E1


BEFORE THE DOGM in and for the STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF IWM SEEKING  
FOR ADMINISTRATIVE APPROVAL,  
PURSUANT TO RULE C-11, AUTHORIZING THE DRILLING  
OF AN INJECTION WELL AND THE UNDERGROUND DISPOSAL OF  
WATER PRODUCED AS A BY PRODUCT OF OIL AND GAS  
PRODUCTION

CERTIFICATE of MAILING


State of Utah  
County of Duchesne

Robert L. Ballou, Agent for applicant, Integrated Water Management, deposes and affirms that on April 8th 2011 he caused to be deposited in the US mail, copies of the application as directed by the DOGM for the above entitled matter to the list referred to as Exhibit "F", and that the addresses given in that exhibit are correct to the best of the affiant's information and belief; such exhibit includes all lease holders, offset operators and surface owners within a 1/2 mile radius of the proposed SWD described in the application.




Robert L. Ballou PG -Consultant

Subscribed and sworn to before me this 8<sup>th</sup> day of April 2011.



My commission expires: 10.18.13



RECEIVED

APR 11 2011

DIV. OF OIL, GAS & MINING

Operator/Landowner Section 29	Duchesne Co. Serial #	Address	Date Sent	Comments
Brent Farnsworth	2146	PO Box 153 Duchesne, UT 84021		Only Neighbor in vicinity, IWM purchased 9 additional nine acres from Brent and he constructed the fence around our facility.
<b>Section 30 &amp; 31</b>				
William A. Robinson	2147-2-1	243 E. Escondido Blvd # 518 Escondido CA 92025		
J. Christman	2151	146 Avenida Coto San Clemente, CA 92672		
Jerry A. Craysper and Joann Craysper	2148-2	840 E. House Mtn. Drive Cottonwood, AZ 86326		
Heidi Kennelly	2148-2-1	PO Box 2074 Mesquite, NV 89024		
Jose Luis Tomayo	2150	4200 Dennis Dr. SLC, UT 84120		
Antonio Gander Jr. Trustee, Victoria Bell Gander Trustee, SJ Christman Trustees	2157	14808 E. Sabine Dr. La Mirada, CA 90638		
Ronnie W. Case, Cristine Case	2152	PO Box 70161 SLC, UT 84170		
Duchesne /Wasatch Blue Bench Landfill	2158	Duchesne Co. Landfill C/O Manager P.O. Box 228 Duchesne, UT 84021		
<b>Section 32</b>				
Lois Bleazard Trustee	96792	PO Box 510033 Mountain Home, UT 84051		
Duchesne /Wasatch Blue Bench Landfill	2158	Duchesne Co. Landfill C/O Manager P.O. Box 228 Duchesne, UT 84021		
El Paso Exploration and Production		El Paso Exploration and Production Attention: Jordan Nelson Senior Production Engineer 1099 18th Street, Suite 1900 Denver, CO 80202		Operator in Sections 29, 30,31, 32 2S 4W

RECEIVED

APR 11 2011

DIV. OF OIL, GAS &amp; MINING



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

<p><b>SUNDRY NOTICES AND REPORTS ON WELLS</b></p> <p><small>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</small></p>		<p>5. LEASE REGISTRATION AND SERIAL NUMBER:</p>
<p>1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>SWD</u></p>		<p>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</p>
<p>2. NAME OF OPERATOR: <u>Integrated Water Management</u></p>		<p>7. UNIT or CA AGREEMENT NAME:</p>
<p>3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u></p>		<p>8. WELL NAME and NUMBER: <u>IWM SWD 3-30 B4</u></p>
<p>4. LOCATION OF WELL: FOOTAGES AT SURFACE: <u>300' FSL 800' FEL</u></p>		<p>9. API NUMBER: <u>4301350753</u></p>
<p>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SESE 30 2S 4W</u></p>		<p>10. FIELD AND POOL, OR WILDCAT:</p>
<p>COUNTY: <u>Duchesne</u></p>		<p>STATE: <u>UTAH</u></p>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/17/2011</u>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Spud @ 17:30 on June 17, 2011, drill surface hole and set 500' of 36# M-50, cement to surface, cut casing and installed well head. Currently drilling with 8-3/4" PDC, to reach TD of 5500'

NAME (PLEASE PRINT) <u>Robert Ballou</u>	TITLE <u>Geologist/Agent</u>
SIGNATURE <u>Robert Ballou</u>	DATE <u>6/21/2011</u>

(This space for State use only)

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>SWD</u>		5. LEASE DESIGNATION AND SERIAL NUMBER
2. NAME OF OPERATOR: <u>Integrated Water Management</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR: <u>PO Box 430</u> CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>		7. UNIT or CA AGREEMENT NAME
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>800 feet from east line 300 feet from south line</u>		8. WELL NAME and NUMBER: <u>IWM SWD 3-30 B4</u>
PHONE NUMBER: <u>(435) 454-4646</u>		9. API NUMBER: <u>4301350753</u>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SESE 2 S 4 W</u>		10. FIELD AND POOL, OR WILDCAT:

COUNTY: DuchesneSTATE: UTAH

### CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input checked="" type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDE TRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

IWM intends to perforate gross zones from 4963' to 5130', a total of 180' of gross interval.

The perforations will be 4 shots per foot. This action is in preparation for establishing operations up as a SWD well. All perforations in the Tu fm.

COPY SENT TO OPERATOR

Date: JUL 11 2011Initials: KS

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Date: 07-07-2011By: [Signature]NAME (PLEASE PRINT) Robert Ballou

SIGNATURE

TITLE Geologist/AgentDATE 7/6/2011

(This space for State use only)

RECEIVED

JUL 06 2011

DIV. OF OIL, GAS &amp; MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: Integrated Water Management Operator Account Number: N 3685  
Address: PO Box 430  
city Altamont  
state UT zip 84066 Phone Number: (435) 454-4646

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301350753	IWM SWD 3-30B4		SESE	30	2S	4W	Duchesne
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	18109	6/18/2011		7/20/11		
Comments: <u>GRRV</u>							<b>CONFIDENTIAL</b>

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

**RECEIVED**

JUL 11 2011

DIV. OF OIL, GAS & MINING

Robert Ballou

Name (Please Print)


Signature

Agent

Title

7/1/2011

Date



*Duchesne County Planning, Zoning  
& Community Development  
734 North Center Street  
P.O. Box 317  
Duchesne, Utah 84021  
(435) 738-1152  
Fax (435) 738-5522*

**RECEIVED**  
**JUL 18 2011**  
DIV. OF OIL, GAS & MINING

July 15, 2011

Mr. Brad Hill, Permitting Manager  
Division of Oil, Gas and Mining  
PO Box 145801  
Salt Lake City, UT 84114-5801

RE: Integrated Water Management Injection Well (Cause No UIC-378.1)

Dear Mr. Hill:

We are in receipt of your notice regarding Integrated Water Management's request to operate a Class II salt water injection well at their facility located at 20250 W 2000 South, near the Blue Bench landfill, in Duchesne County.

Duchesne County is supportive of this request and recommends approval under conditions that your agency deems appropriate. The county has been receiving odor complaints recently due to operations at this facility and hopes that injection will eliminate the odor problem. We hope that this authorization can be granted as expeditiously as possible.

Thank you for the opportunity to comment.

Sincerely,

A handwritten signature in cursive script that reads "Mike Hyde".

Mike Hyde, AICP  
Community Development Administrator

pc: Integrated Water Management, PO Box 430, Altamont, UT 84001-0430  
Bob Ballou, Ballou Geologic Consulting, PO Box 816, Roosevelt, UT 84066



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

October 26, 2011

Integrated Water Management, LLC  
P.O. Box 430  
Altamont, UT 84001

Subject: Integrated Water Management Facility Well: IWM SWD 3-30 B4, Section 30, Township 2 South, Range 4 West, USM, Duchesne County, Utah, API Well # 43-013-50753


Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Integrated Water Management.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.
4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Ammon McDonald 801-538-5337 or Brad Hill at 801-538-5315.

Sincerely,

  
John Rogers  
Associate Director

JR/AM/js

cc: Bruce Suchomel, Environmental Protection Agency  
Duchesne County  
Well File

N:\O&G Permits\Injection Permits\Integrated Water Mng



November 1, 2011

To:

DOGM

Re: Monitoring of Chrisman Blann 1-31B4 well.

Please be advised that Integrated Water Management has permission to monitor the casing pressure on the Chrisman Blann 1-31 B4 well as outlined by personnel (Dennis Ingram) of the DOGM.

Thank you,

A handwritten signature in cursive script that reads "Gary L. Lamb".

Gary Lamb

El Paso Production Supervisor



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director


## TEMPORARY 90-DAY UNDERGROUND INJECTION CONTROL PERMIT Cause No. UIC-378.1

**Operator:** Integrated Water Management, LLC  
**Well:** IWM SWD 3-30 B4  
**Location:** Section 30, Township 2 South, Range 4 West, USM  
**County:** Duchesne  
**API No.:** 43-013-50753  
**Well Type:** Saltwater Disposal

### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on **October 26, 2011**.
2. Maximum Allowable Injection Pressure: 525 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Lower Uinta Formation (4,063' – 5,130')
5. A Radioactive Tracer Survey is to be run 90 days after date of injection approval, in order to demonstrate which perforated zones are accommodating water.
6. Maximum Cumulative Injection Volume:  $1.88 \times 10^7$  barrels; to be re-evaluated after the results of the RAT survey.
7. The off-setting well (Christman-Bland 1-31, 43-013-30198) shall be monitored on a weekly basis and reported to the Division monthly. In the event that pressure changes are noted, **Injection Shall Cease Immediately** and the Division shall be notified.

Approved by:

  
John Rogers  
Associate Director

11-07-2011

Date

JR/AM/js

cc: Bruce Suchomel, Environmental Protection Agency  
Duchesne County  
Well File

N:\O&G Permits\Injection Permits\Integrated Water Mng

1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114 -5801  
telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • [www.ogm.utah.gov](http://www.ogm.utah.gov)





**FILED**

SEP 12 2011

BEFORE THE BOARD OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH

SECRETARY, BOARD OF  
OIL, GAS & MINING

IN THE MATTER OF THE APPLICATION OF  
INTEGRATED WATER MANAGEMENT, LLC FOR  
ADMINISTRATIVE APPROVAL OF THE IWM  
SWD 3-30 B4 SWD WELL LOCATED IN  
SECTION 30, TOWNSHIP 2 SOUTH, RANGE 4  
WEST, DUCHESNE COUNTY, UT AS A CLASS II  
INJECTION WELL


**MOTION TO WITHDRAW REQUEST FOR  
FORMAL AGENCY ACTION**

Docket No. 2011-017  
Cause No. UIC-378.1

INTEGRATED WATER MANAGEMENT (IWM), LLC, Petitioner, by and through its undersigned counsel, submits the following motion to withdraw it's request for formal agency action and request for hearing and revert the action to the original informal action as filed by the Division.

On August 10, 2011, IWM filed a Request for Agency Action in order to have its application for a Class II injection well heard by the Board of Oil Gas and Mining as required by the rules because an objection to IWM's UIC application had been received by the Division from ProWater, LLC. However, ProWater, LLC has since notified the Division in writing withdrawing its objection to IWM's UIC application. Therefore, the hearing is no longer required under Rule R649-5-3 U.A.C. For this reason, IWM respectfully requests that the application be considered by the Division under the informal rules as originally noticed pursuant to R649-10-1 *et seq.* and the hearing before the Board scheduled for September 29, 2011 be cancelled.

Submitted this 9th day of September, 2011



Matthew M. Nelson  
Nelson Law, PLLC  
Attorney for Petitioner

90 S 400 W Ste 360  
Salt Lake City, UT 84101  
801-456-1286  
mattmnelson1@gmail.com

---

BEFORE THE BOARD OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH

---

IN THE MATTER OF THE APPLICATION OF  
INTEGRATED WATER MANAGEMENT, LLC FOR  
ADMINISTRATIVE APPROVAL OF THE IWM  
SWD 3-30 B4 SWD WELL LOCATED IN  
SECTION 30, TOWNSHIP 2 SOUTH, RANGE 4  
WEST, DUCHESNE COUNTY, UT AS A CLASS II  
INJECTION WELL

**REQUEST FOR AGENCY ACTION**

Docket No.  
Cause No.

INTEGRATED WATER MANAGEMENT (IWM), LLC, Petitioner, by and through its undersigned counsel, petitions the Board of Oil, Gas and Mining for an order approving the IWM SWD 3-30 B4 SWD Well as a Class II injection well and authorizing the underground injection of produced water for purposes of water disposal, and shows as follows:

1. Integrated Water Management, LLC ("IWM") is a Utah limited liability company in good standing, having its principal place of business in SLC, Utah. IWM is qualified to and is doing business in Utah.
2. The Board of Oil, Gas and Mining (the "Board") has jurisdiction of the parties and subject matter of this Request for Agency Action, pursuant to Section 40-6-5(5)(a) of the Utah Code Annotated and Rules R649-5-1 and R649-5-3(4) of the Utah Administrative Code ("U.A.C.").

PROCEDURAL POSTURE

3. IWM originally filed its application for administrative approval of the IWM SWD 3-30 B4 Well located in the SESE of Section 30, Township 2 S., Range 4 W. Duchesne County, Utah (the "Subject Well" and "Subject Lands," respectively) as a Class II underground injection well for the disposal of produced water on April 7, 2011. IWM gave notice of the Application

pursuant to the requirements of Rule R649-5-3, U.C.A., and provided a copy of the Application to all operators, owners, and surface owners within a one-half mile radius of the Subject Well as required by Rule R649-5-2, U.A.C. On July 12, 2011, the Division published notice of the Application in the Salt Lake Tribune and Uintah Basin Standard. Following publication of the notice of the Application, the Division received a letter dated July 27, 2011, from ProWater, LLC objecting to the application.

4. The purpose of this Request for Agency Action is to set the matter for hearing by the Board at the Board's regularly scheduled hearing on September 28, 2011.

#### UNDERGROUND INJECTION OF WATER

5. Petitioner seeks approval of the Subject Well as a Class II underground injection well and the authorization of operations for the underground injection of produced water into the Uinta Formation for water disposal purposes.

6. The Application for Permit to Drill ("APD") for the Subject Well was filed with the Division on April 28, 2011, and the APD was approved on June 7, 2011. The Subject Well was spud on June 18, 2011, later completed, cased, cemented, perforated, and set with production tubing with a production packer.

7. IWM will operate the Subject Well and the proposed injection operations.

8. The formation to be approved by the Board for water injection disposal operations is the Uinta Formation. The Uinta Formation is mainly a fluvial sand/shale deposit, the proposed gross injection interval is from 4063' to 5130' with a total of 180 feet of perforations, four shots per foot.

9. In this area, the injection interval in the Uinta Formation is not currently, nor is it ever expected to be, an underground source of drinking water ("USDW"). A swab test of the

10. The following wells have been drilled or completed within a one-half mile radius of the Subject Well:

- a) Katherin 2-29 B4;
- b) Christman Blann 1-31 B4;
- c) Water Well 43-2422;
- d) Water Well 43-10499;
- e) Water Well 43-9196.

11. The water for the injection medium for the proposed injection operations will come from oil and gas producing wells in the Uintah Basin. IWM seeks authority to inject up to 5,000 barrels of produced water per day at an average injection pressure of 500 psi with a maximum injection pressure of 800 psi. Note that injection pressures are estimates. A step-rate test will be run along with a MIT and the results provided to the DOGM. Pressures are estimated from surrounding and adjacent SWD wells operated by other operators.

12. Copies of various electrical or radioactive logs that were run in the Subject Well prior to the installation of casing and after casing was set and cemented and have been filed with the Division and may be examined at the offices of the Division.

#### OWNERSHIP

13. IWM owns fee simple title to the Subject Lands.

14. The minerals in the lands embraced within the Subject Lands and within a one-half mile radius of the Subject Well are owned by El Paso Oil and Gas.

15. Besides IWM, the surface owners within a one-half mile radius of the Subject Well are listed as exhibit "A" and made a part hereof.

16. A plat showing the area involved and identifying all wells, including the proposed injection well, within a one-half mile radius of the proposed Subject Well is attached hereto as

17. The names and addresses of all operators and owners as defined in Section 40-6-2, Utah Code Annotated, and of all surface owners within a one-half mile radius of the proposed Subject Well are set forth in Exhibit "F" attached hereto and made a part hereof.

18. The Affidavit required by Rule R649-5-1 (2.9), U.A.C., is attached hereto as Exhibit "C" and made a part hereof.

WHEREFORE, Petitioner respectfully requests the Board to:

A. Set this matter for hearing at the regularly scheduled meeting of the Board to be held on September 28, 2011 to consider IWM's Application.

B. Give notice of this Request for Agency Action and the hearing as provided by the laws of the State of Utah and regulations issued pursuant thereto. The names and addresses of the parties interested in this matter are set forth in Exhibit "F" to this Request for Agency Action.

C. Conduct a hearing at which Petitioner and all authorized parties may be allowed to present evidence regarding IWM's Application.

D. To find that:


(1) The IWM SWD 3-30 B4 Well, as proposed, is suitable for approval as a Class II injection well.

(2) Good cause appears to authorize underground water disposal operations for produced water using the IWM SWD 3-30 B4 Well, as proposed.

E. Enter an order approving the IWM SWD 3-30 B4 Well as a Class II injection well and authorizing the underground injection of produced water into the Uinta Formation for

F. Provide such other relief as may be just and proper under the circumstances.

Dated this 10th day of August, 2011

A handwritten signature in black ink, appearing to read "Matthew M. Nelson". The signature is written in a cursive style with a horizontal line drawn across the middle of the letters.

Matthew M. Nelson  
Nelson Law, PLLC  
Attorney for Petitioner

90 S 400 W Ste 360  
Salt Lake City, UT 84101  
801-456-1286  
mattmnelson1@gmail.com



## Exhibit "A"

### Owner List

Brent Farnsworth  
PO Box 153  
Duchesne, UT 84021-0153

William A. Robinson  
243 E. Escondido Blvd #518  
Escondido, CA 92025

J. Chrisman  
146 Avenida Cota  
San Clemente, CA 92672-3327

Jerry And Joann Craysper  
840 E House Mountain Dr  
Cottonwood, AZ 86326-2893

Heidi Kennelly  
PO Box 2074  
Mesquite, NV 89024-2074

Jose Luis Tomayo  
4200 Dennis Dr  
Salt Lake City, UT 84120-1615

Antonio Gander Jr.  
14808 Sabine Dr  
LA Mirada, CA 90638-2143


Ronnie W And Cristine Case  
PO Box 70161  
Salt Lake City, UT 84170-0161

Duchesne/Wasatch Blue Bench  
Landfill C/o Manager  
PO Box 228  
Duchesne, UT 84021-0228

Lois Bleazard  
PO Box 510033  
Mountain Home, UT 84051-0033

El Paso E & P  
Attention: Cathy Hammock  
1099 18th St Ste 1900  
Denver, CO 80202-1905

Exhibit "B"  
Plat





## Exhibit "C"

BEFORE THE BOARD OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF  
INTEGRATED WATER MANAGEMENT, LLC FOR  
ADMINISTRATIVE APPROVAL OF THE IWM  
SWD 3-30 B4 SWD WELL LOCATED IN  
SECTION 30, TOWNSHIP 2 SOUTH, RANGE 4  
WEST, DUCHESNE COUNTY, UT AS A CLASS II  
INJECTION WELL

**AFFIDAVIT AND CERTIFICATE OF MAILING**

Docket No.


Cause No.

State of Utah            )  
                                  :§  
County of Salt Lake    )


I, Matthew M. Nelson, having been duly sworn state that:


- A. I reside in Salt Lake County, UT.
- B. I am an attorney licensed in all Courts of Utah.
- C. I make this statement pursuant to the requirements of R649-5-2(2.12).
- D. I have caused to be mailed the Request for Agency action, the associated Exhibits, and UIC Form 1 to the persons listed in Exhibit "D" of the Request for Agency action as requires by R641-104-135 and R649-5-2(2.12), of the Utah Administrative Code, by US Mail, postage prepaid.

Dated this 10th day of August, 2011.

  
Matthew M. Nelson

Subscribed and sworn to before me on this 10 day of August, 2011 by Matthew M. Nelson

  
NOTARY PUBLIC



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 1

**APPLICATION FOR INJECTION WELL**

Name of Operator Integrated Water Management	Utah Account Number N	Well Name and Number IWM SWD 3-30 B4
Address of Operator PO Box 430      CITY Altamont      STATE UT      ZIP 84001	Phone Number (435) 454-4646	API Number
Location of Well  Footage : 800' FEL, 300' FSL      County : Duchesne  QQ, Section, Township, Range: SESE      30      2S      4W      State : UTAH		Field or Unit Name  Lease Designation and Number

Is this application for expansion of an existing project?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
---	------------------------------	--

Will the proposed well be used for:	Enhanced Recovery?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
	Disposal?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Storage?	Yes <input type="checkbox"/>	No <input type="checkbox"/>

Is this application for a new well to be drilled?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
---	---	-----------------------------

If this application is for an existing well, has a casing test been performed?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
Date of test: _____		

Proposed injection interval:      from 4,000      to 5,500

Proposed maximum injection:      rate 5,000      bpd      pressure 800      psig

Proposed injection zone contains oil ☒, gas ☐, and / or fresh water ☐ within ½ mile of the well.

List of attachments: Attached are write up with exhibits

**ATTACH ADDITIONAL INFORMATION AS REQUIRED BY CURRENT  
UTAH OIL AND GAS CONSERVATION GENERAL RULES**

I hereby certify that this report is true and complete to the best of my knowledge.

Name (Please Print) Robert Ballou

Title PG- Consultant

Signature 

Date 4/7/2011

## Exhibit "D" Mailing List

Brent Farnsworth  
PO Box 153  
Duchesne, UT 84021-0153

William A. Robinson  
243 E. Escondido Blvd #518  
Escondido, CA 92025

J. Chrisman  
146 Avenida Cota  
San Clemente, CA 92672-3327

Jerry And Joann Craysper  
840 E House Mountain Dr  
Cottonwood, AZ 86326-2893

Heidi Kennelly  
PO Box 2074  
Mesquite, NV 89024-2074

Jose Luis Tomayo  
4200 Dennis Dr  
Salt Lake City, UT 84120-1615

Antonio Gandera Jr.  
14808 Sabine Dr  
LA Mirada, CA 90638-2143

Ronnie W and Cristine Case  
PO Box 70161  
Salt Lake City, UT 84170-0161

Duchesne/Wasatch Blue Bench  
Landfill C/O Manager  
PO Box 228  
Duchesne, UT 84021-0228

Lois Bleazard  
PO Box 510033  
Mountain Home, UT 84051-0033

El Paso E & P  
Attention: Cathy Hammock  
1099 18th St Ste 1900  
Denver, CO 80202-1905

Duchesne County Planning  
PO Box 317  
Duchesne, UT 84021-0317

Bruce Suchomel  
US Epa Region Viii  
MS 8-p-w-gw  
1595 Wynkoop St  
Denver, CO 80202-1129

ProWater, LLC  
12223 Highland Ave, Ste B503  
Rancho Cucamonga, CA 91739

# ProWater

September 7, 2011

Mr. Brad Hill  
Oil & Gas Permitting Manager  
P.O. Box 145801  
Salt lake City, Utah 84114-5801

Dear Mr. Hill,


Re: Notice of Agency Action Cause No. UIC-378.1

I would like to **rescind our complaint toward** the application of Integrated Water Management LLC for administrative approval of the IWM SWD 3-30B4 Well (API#43-013-50753) located in Section 30, Township 2S, Range 4W, Duchesne County, Utah as a Class II Injection Well. We have completed our due diligence and have reevaluated our position.

Our existing facility is the Blue Bench SWD 13-1 Injection Well (API#43-013-30971) located in Section 13, Township 3S, Range 5W, Duchesne County, Utah.

Thank you for this consideration.

Sincerely,



Keith Morlock  
President  
ProWater, LLC



# ProWater

July 27, 2011

Mr. Brad Hill  
Oil & Gas Permitting Manager  
P.O. Box 145801  
Salt lake City, Utah 84114-5801

RECEIVED

AUG 02 2011

DIV. OF OIL, GAS & MINING

Dear Mr. Hill,

Re: Notice of Agency Action Cause No. UIC-378.1


I would like to **protest** the application of Integrated Water Management LLC for administrative approval of the IWM SWD 3-30B4 Well (API#43-013-50753) located in Section 30, Township 2S, Range 4W, Duchesne County, Utah as a Class II Injection Well. The proximity of the IWM well, to our current SWD well, would result in the direct injection of their water into the same formation and depths that we currently injecting into. This proposed IWM injection well is approximately 3 miles from our injection well and newly constructed water cleaning facility. They currently are permitted for evaporation pits, they are adding a centrifuge for additional capacity, but the injection well would severely hinder us from being able to inject into our zone and directly reduce its life expectancy.

I will need some time to prepare a formal response that shows how the IWM Well will cause substantial harm to our existing operation by interfering with our ability to inject into the formation that we currently use. Please allow for this preparation time when scheduling the hearing.

Our existing facility is the Blue Bench SWD 13-1 Injection Well (API#43-013-30971) located in Section 13, Township 3S, Range 5W, Duchesne County, Utah.

Thank you for this consideration.


Sincerely,



Keith Morlock  
President  
ProWater, LLC.

3-10-05

BLUE BENCH #13-1
BLUE BENCH DISPOSAL NENE SEC 13 T3S - R5W DUCHESNE CO., UTAH
WELLBORE SCHEMATIC
<i>After P+A.</i>



Keith Morlock  
Pro Water, LLC  
12223 Highland Ave. Ste B503  
Rancho Cucamonga, CA 91739



Mr. Brad Hill  
Oil & Gas Permitting Manager  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

8411485801 8900



# AFFIDAVIT OF PUBLICATION

County of Duchesne,  
STATE OF UTAH

I, Geoff Liesik on oath, say that I am the EDITOR of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for 1 consecutive issues, and that the first publication was on the 19 day of July, 20 11, and that the last publication of such notice was in the issue of such newspaper dated the 19 day of July, 20 11, and that said notice was published on Utahlegals.com on the same day as the first newspaper publication and the notice remained on Utahlegals.com until the end of the scheduled run.

*Geoff Liesik*

Editor

Subscribed and sworn to before me this

20 day of July, 20 11

*Bonnie Parrish*

Notary Public



## NOTICE OF AGENCY ACTION CAUSE NO. UIC-378.1

BEFORE THE DIVISION OF OIL, GAS AND MINING, DEPARTMENT OF NATURAL RESOURCES, STATE OF UTAH.

IN THE MATTER OF THE APPLICATION OF INTEGRATED WATER

MANAGEMENT LLC FOR ADMINISTRATIVE APPROVAL OF THE TWM SWD 3-30 B4 WELL (API#43-013-50753) LOCATED IN SECTION 30, TOWNSHIP 2S, RANGE 4W, DUCHESNE COUNTY, UTAH, AS A CLASS II INJECTION WELL.

THE STATE OF UTAH

*Working features*

transactions  
e storage of  
• More seci  
is Here!  
onic Checkin

*bring*

Late Mike McArthur in  
me to Janis Joplin -  
Some Three Dog Nig  
(Joy To The World, Ne  
To Spain, Mama Tol  
To Come) would be ni



4770 S. 5600 W.  
P.O. BOX 704005  
WEST VALLEY CITY, UTAH 84170  
FED.TAX I.D.# 87-0217663

The Salt Lake Tribune

WWW.SLTTRIB.COM

MEDIAOne  
A NEWSPAPER AGENCY COMPANY  
WWW.MEDIAONEUTAH.COM

Deseret News

WWW.DESERETNEWS.COM

PROOF OF PUBLICATION

CUSTOMER'S COPY

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	DATE
DIV OF OIL-GAS & MINING, 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114	9001402352	7/19/2011

ACCOUNT NAME			
DIV OF OIL-GAS & MINING,			
TELEPHONE	ADORDER# / INVOICE NUMBER		
8015385340	0000708718 /		
SCHEDULE			
Start 07/18/2011		End 07/18/2011	
CUST. REF. NO.			
20110712			
CAPTION			
BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL			
SIZE			
54	Lines	2.00	COLUMN
TIMES	RATE		
3			
MISC. CHARGES	AD CHARGES		
TOTAL COST			
140.00			

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH  
NOTICE OF AGENCY ACTION

CAUSE NO. UIC-378.1

IN THE MATTER OF THE APPLICATION OF INTEGRATED WATER MANAGEMENT LLC FOR ADMINISTRATIVE APPROVAL OF THE UMW SWD 3-30 B4 WELL (API #43-013-50753) LOCATED IN SECTION 30, TOWNSHIP 2S, RANGE 4W, DUCHESE COUNTY, UTAH, AS A CLASS II INJECTION WELL.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Integrated Water Management LLC for administrative approval of the UMW SWD 3-30B4 well (API #43-013-50753), located in SE/4 SE/4, Section 30, Township 2S, Range 4W, Uinta Baseline & Meridian, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. Rule 6649-10, Administrative Procedures.

Selected zones in the lower Uinta Formation (4063'-5130' bgs) will be used for water disposal by injection. The maximum requested injection pressure and rate will be determined based on fracture gradient information submitted by Integrated Water Management LLC.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Oil & Gas Permitting Manager, at P.O. Box 145801, Salt Lake City, Utah 84114-5801, phone number (801) 538-5315. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedure rule. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interest.

Dated this 12th day of July, 2011.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING  
/s/ Brad Hill  
Oil & Gas Permitting Manager  
708718

UPAXLP

AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH LEGAL BOOKER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF **BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-378.1 IN THE MATTER OF THE APPL FOR DIV OF OIL-GAS & MINING**, WAS PUBLISHED BY THE NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH. NOTICE IS ALSO POSTED ON UTAHLEGAL.S.COM ON THE SAME DAY AS THE FIRST NEWSPAPER PUBLICATION DATE AND REMAINS ON UTAHLEGAL.S.COM INDEFINATELY.

PUBLISHED ON Start 07/18/2011 End 07/18/2011

SIGNATURE

*Barney Taylor*

7/19/2011

VIRGINIA CRAFT  
Notary Public, State of Utah  
Commission # 581489  
My Commission Expires  
January 12, 2014  
*Virginia Craft*

THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"  
PLEASE PAY FROM BILLING STATEMENT

2250/REB/EEVICAADMIN/GF11/6131

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH  
NOTICE OF AGENCY ACTION  
CAUSE NO. UIC-378.1

IN THE MATTER OF THE APPLICATION OF INTEGRATED WATER MANAGEMENT LLC FOR ADMINISTRATIVE APPROVAL OF THE IWM SWD 3-30 B4 WELL (API #43-013-50753) LOCATED IN SECTION 30, TOWNSHIP 2S, RANGE 4W, DUCHESNE COUNTY, UTAH, AS A CLASS II INJECTION WELL.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.


Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Integrated Water Management LLC for administrative approval of the IMW SWD 3-30B4 well (API #43-013-50753), located in SE/4 SE/4, Section 30, Township 2S, Range 4W, Uinta Baseline & Meridian, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. Rule R649-10, Administrative Procedures.

Selected zones in the lower Uinta Formation (4063'-5130' bgs) will be used for water disposal by injection. The maximum requested injection pressure and rate will be determined based on fracture gradient information submitted by Integrated Water Management LLC.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Oil & Gas Permitting Manager, at P.O. Box 145801, Salt Lake City, Utah 84114-5801, phone number (801) 538-5315. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedure rule. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 12<sup>th</sup> day of July, 2011.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING

  
\_\_\_\_\_  
Brad Hill  
Oil & Gas Permitting Manager

**Integrated Water Management LLC**  
**IMW SWD 3-30B4**  
**Cause No. UIC-378.1**

Publication Notices were sent to the following:

Marie O'Keefe, Senior Regulatory Analyst  
El Paso E & P  
1099 18<sup>th</sup> St., Suite 1900  
Denver, CO 80202

Uintah Basin Standard  
268 S 200 E  
Roosevelt, UT 84066  
via e-mail [legals@ubstandard.com](mailto:legals@ubstandard.com)

Salt Lake Tribune  
PO Box 45838  
Salt Lake City, UT 84145  
via e-mail [naclegal@mediaoneutah.com](mailto:naclegal@mediaoneutah.com)

Duchesne County Planning  
P.O. Box 317  
Duchesne UT 84021-0317

Bruce Suchomel  
US EPA Region VIII  
MS 8-P-W-GW  
1595 Wynkoop Street  
Denver, CO 80202-1129

Robert Ballou  
Ballou Geologic Consulting  
P.O. Box 816  
Roosevelt, UT 84066

  
\_\_\_\_\_  
Jean Sweet



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

July 13, 2011

Via e-mail: [naclegal@mediaoneutah.com](mailto:naclegal@mediaoneutah.com)

The Salt Lake Tribune  
PO Box 45838  
Salt Lake City, UT 84145

Subject: Notice of Agency Action – Integrated Water Management LLC Cause No. UIC-378.1

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: [jsweet@utah.gov](mailto:jsweet@utah.gov).

Please send proof of publication and billing for **account #9001402352** to:

Division of Oil, Gas and Mining  
Suite 1210  
PO Box 145801  
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet  
Executive Secretary

Enclosure





## Order Confirmation for Ad #0000708718-01

<b>Client</b>	DIV OF OIL-GAS & MINING	<b>Payor Customer</b>	DIV OF OIL-GAS & MINING
<b>Client Phone</b>	801-538-5340	<b>Payor Phone</b>	801-538-5340
<b>Account#</b>	9001402352	<b>Payor Account</b>	9001402352
<b>Address</b>	1594 W NORTH TEMP #1210,P.O. BOX 145801 SALT LAKE CITY, UT 84114 USA	<b>Payor Address</b>	1594 W NORTH TEMP #1210,P.O. BO SALT LAKE CITY, UT 84114
<b>Fax</b>	801-359-3940	<b>Ordered By</b>	<b>Acct. Exec</b>
<b>Email</b>	earlenerussell@utah.gov	Jean	mfultz

<b>Total Amount</b>	<b>\$140.00</b>			
<b>Payment Amt</b>	<b>\$0.00</b>			
<b>Amount Due</b>	<b>\$140.00</b>	<b>Tear Sheets</b>	<b>Proofs</b>	<b>Affidavits</b>
		0	0	1
<b>Payment Method</b>		<b>PO Number</b>	20110712	

### Confirmation Notes:

### Text:

<b>Ad Type</b>	<b>Ad Size</b>	<b>Color</b>
Legal Liner	2.0 X 54 Li	<NONE>

<b>Product</b>	<b>Placement</b>	<b>Position</b>
Salt Lake Tribune::	Legal Liner Notice - 0998	Public Meeting/Hear-ing Notices
<b>Scheduled Date(s):</b>	07/18/2011	
<b>Product</b>	<b>Placement</b>	<b>Position</b>
sltrib.com::	Legal Liner Notice - 0998	Public Meeting/Hear-ing Notices
<b>Scheduled Date(s):</b>	07/18/2011	
<b>Product</b>	<b>Placement</b>	<b>Position</b>
utahlegals.com::	utahlegals.com	utahlegals.com
<b>Scheduled Date(s):</b>	07/18/2011	

### Ad Content Proof Actual Size

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH  
NOTICE OF AGENCY ACTION

CAUSE NO. UIC-378.1

IN THE MATTER OF THE APPLICATION OF INTEGRATED WATER MANAGEMENT LLC FOR ADMINISTRATIVE APPROVAL OF THE IWM SWD 3-30 84 WELL (API #43-013-50753) LOCATED IN SECTION 30, TOWNSHIP 2S, RANGE 4W, DUCHESNE COUNTY, UTAH, AS A CLASS II INJECTION WELL.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Integrated Water Management LLC for administrative approval of the IWM SWD 3-3084 well (API #43-013-50753), located in SE/4 SE/4, Section 30, Township 2S, Range 4W, Uinta Baseline & Meridian, Duchesne County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. Rule R649-10, Administrative Procedures.

Selected zones in the lower Uinta Formation (4063'-5130' bgs) will be used for water disposal by injection. The maximum requested injection pressure and rate will be determined based on fracture gradient information submitted by Integrated Water Management LLC.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Oil & Gas Permitting Manager, at P.O. Box 145801, Salt Lake City, Utah 84114-5801, phone number (801) 538-5315. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedure rule. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 12th day of July, 2011.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING  
/s/  
Brad Hill  
Oil & Gas Permitting Manager  
708718

UPAXLP



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

July 13, 2011

Via e-mail: [legals@ubstandard.com](mailto:legals@ubstandard.com)

Uintah Basin Standard  
268 S 200 E  
Roosevelt UT 84066

Subject: Notice of Agency Action – Integrated Water Management LLC Cause No. UIC-378.1

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: [jsweet@utah.gov](mailto:jsweet@utah.gov).

Please send proof of publication and billing to:

Division of Oil, Gas and Mining  
Suite 1210  
PO Box 145801  
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet  
Executive Secretary

Enclosure



**Jean Sweet - Re: Notice of Agency Action – Integrated Water Management LLC Cause No. UIC-378.1**

---

**From:** Cindy Kleinfelter <classifieds@ubstandard.com>  
**To:** Jean Sweet <jsweet@utah.gov>  
**Date:** 7/14/2011 11:16 AM  
**Subject:** Re: Notice of Agency Action – Integrated Water Management LLC Cause No. UIC-378.1

---

On 7/13/2011 1:36 PM, Jean Sweet wrote:

To Whom It May Concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: [jsweet@utah.gov](mailto:jsweet@utah.gov).


Please send proof of publication and billing to:

Division of Oil, Gas and Mining  
Suite 1210  
PO Box 145801  
Salt Lake City, UT 84114-5801


Sincerely,


Jean Sweet, Executive Secretary  
Utah Div. of Oil, Gas & Mining  
1594 West Temple, Suite 1210  
Salt Lake City, UT  
801-538-5329  
[jsweet@utah.gov](mailto:jsweet@utah.gov)

This will be published July 19, 2011.  
Thank you.  
Cindy



Rate	Pressure	
1200	286	14
2400	321	35
3600	385	64
4800	475	90
6000	595	120
7200	736	141
8400	0	





Underrange

Trace	Type	Ruler Value
◆ TriPlex.Injection Flow Rate	Current	-



# 165T-5 Triplex Plunger Pump

## Performance Data

PUMP	English Units					100 RPM		200 RPM		250 RPM		300 RPM		350 RPM		400 RPM	
	Plunger Dia. In.	Plunger Area Sq. In.	BPD per RPM	GPM per RPM	Max. Press. PSI	BPD	GPM	BPD	GPM	BPD	GPM	BPD	GPM	BPD	GPM	BPD	GPM
165T-5L	4.000	12.5664	27.9770	0.8160	780	2798	81.6	5596	163.2	6995	204.0	8394	244.8	9792	285.6	11191*	326*
	→ 3.750	11.0447	24.5892	0.7172	887	2459	71.7	4918	143.4	6148	179.3	7377	215.2	8607	251.0	9836	286.9
	3.500	9.6211	21.4199	0.6247	1019	2142	62.5	4284	124.9	5355	156.2	6426	187.4	7497	218.7	8568	249.9
	3.250	8.2958	18.4692	0.5387	1181	1847	53.9	3694	107.7	4618	134.7	5541	161.6	6465	188.5	7388	215.5
	3.000	7.0686	15.7371	0.4590	1386	1574	45.9	3148	91.8	3935	114.7	4722	137.7	5508	160.6	6295	183.6
	2.750	5.9396	13.2235	0.3857	1650	1323	38.6	2645	77.1	3306	96.4	3968	115.7	4629	135.0	5290	154.3
165T-5M	2.750	5.9396	13.2235	0.3857	1650	1323	38.6	2645	77.1	3306	96.4	3968	115.7	4629	135.0	5290	154.3
	2.500	4.9087	10.9285	0.3187	1996	1093	31.9	2186	63.7	2733	79.7	3279	95.6	3825	111.6	4372	127.5
	2.375	4.4301	9.8630	0.2877	2212	987	28.8	1973	57.5	2466	71.9	2959	86.3	3453	100.7	3946	115.1
	2.250	3.9761	8.8521	0.2582	2465	886	25.8	1771	51.6	2214	64.5	2656	77.5	3099	90.4	3541	103.3
	2.125	3.5466	7.8959	0.2303	2763	790	23.0	1580	46.1	1974	57.6	2369	69.1	2764	80.6	3159	92.1
	2.000	3.1416	6.9943	0.2040	3120	700	20.4	1399	40.8	1749	51.0	2099	61.2	2448	71.4	2798	81.6
165T-5H	2.000	3.1416	6.9943	0.2040	3120	700	20.4	1399	40.8	1749	51.0	2099	61.2	2448	71.4	2798	81.6
	1.875	2.7612	6.1473	0.1793	3549	615	17.9	1230	35.9	1537	44.8	1845	53.8	2152	62.8	2459	71.7
	1.750	2.4053	5.3550	0.1562	4074	536	15.6	1071	31.2	1339	39.0	1607	46.9	1875	54.7	2142	62.5
	1.625	2.0739	4.6173	0.1347	4725	462	13.5	924	26.9	1155	33.7	1386	40.4	1617	47.1	1847	53.9
	1.500	1.7671	3.9343	0.1147	5000	394	11.5	787	22.9	984	28.7	1181	34.4	1377	40.2	1574	45.9
Brake Horsepower Required						42		83		104		124		144		165	

PUMP	Metric Units					100 RPM		200 RPM		250 RPM		300 RPM		350 RPM		400 RPM	
	Plunger Dia. mm	Plunger Area cm²	M³/Hr per RPM	L/Sec. per RPM	Max. Press. kPa	M³/Hr	L/Sec.	M³/Hr	L/Sec.	M³/Hr	L/Sec.	M³/Hr	L/Sec.	M³/Hr	L/Sec.	M³/Hr	L/Sec.
165T-5L	102	81.073	0.1853	0.0515	5377	18.5	5.1	37.1	10.3	46.3	12.9	55.6	15.4	64.9	18.0	74.1*	20.6*
	95	71.256	0.1629	0.0452	6118	16.3	4.5	32.6	9.0	40.7	11.3	48.9	13.6	57.0	15.8	65.1	18.1
	89	62.072	0.1419	0.0394	7023	14.2	3.9	28.4	7.9	35.5	9.9	42.6	11.8	49.7	13.8	56.8	15.8
	83	53.521	0.1223	0.0340	8145	12.2	3.4	24.5	6.8	30.6	8.5	36.7	10.2	42.8	11.9	48.9	13.6
	76	45.604	0.1042	0.0290	9559	10.4	2.9	20.8	5.8	26.1	7.2	31.3	8.7	36.5	10.1	41.7	11.6
	70	38.320	0.0876	0.0243	11376	8.8	2.4	17.5	4.9	21.9	6.1	26.3	7.3	30.7	8.5	35.0	9.7
165T-5M	70	38.320	0.0876	0.0243	11376	8.8	2.4	17.5	4.9	21.9	6.1	26.3	7.3	30.7	8.5	35.0	9.7
	64	31.669	0.0724	0.0201	13765	7.2	2.0	14.5	4.0	18.1	5.0	21.7	6.0	25.3	7.0	29.0	8.0
	60	28.581	0.0653	0.0181	15252	6.5	1.8	13.1	3.6	16.3	4.5	19.6	5.4	22.9	6.4	26.1	7.3
	57	25.652	0.0586	0.0163	16994	5.9	1.6	11.7	3.3	14.7	4.1	17.6	4.9	20.5	5.7	23.5	6.5
	54	22.881	0.0523	0.0145	19052	5.2	1.5	10.5	2.9	13.1	3.6	15.7	4.4	18.3	5.1	20.9	5.8
165T-5H	51	20.268	0.0463	0.0129	21512	4.6	1.3	9.3	2.6	11.6	3.2	13.9	3.9	16.2	4.5	18.5	5.1
	48	17.814	0.0407	0.0113	24471	4.1	1.1	8.1	2.3	10.2	2.8	12.2	3.4	14.3	4.0	16.3	4.5
	44	15.518	0.0355	0.0099	28092	3.5	1.0	7.1	2.0	8.9	2.5	10.6	3.0	12.4	3.4	14.2	3.9
	41	13.380	0.0306	0.0085	32580	3.1	0.8	6.1	1.7	7.6	2.1	9.2	2.5	10.7	3.0	12.2	3.4
	38	11.401	0.0261	0.0072	34474	2.6	0.7	5.2	1.4	6.5	1.8	7.8	2.2	9.1	2.5	10.4	2.9
Kilowatts Required						31		62		78		92		108		123	

Volumetric Rate is based on 100% Volumetric Efficiency. Brake Horsepower/Kilowatts Required is based on 90% Mechanical Efficiency. For Operation below 200 RPM, an auxiliary lubrication system is required. Not all plunger sizes are shown. Contact National Oilwell for additional information. \*Spherical Valves must be installed when the pump is fitted with 4.0" (102mm) plungers

The information and data on this sheet is accurate to the best of our knowledge and belief, but are intended for general information only. Applications suggested for the materials are described only to help readers make their own evaluations and decisions, and are neither guarantees nor to be construed as express or implied warranties of suitability for these or other applications. National Oilwell makes no warranty either express or implied beyond that stipulated in National Oilwell Standard Terms and Conditions of Sale.

Authorized Distributor:

**NOV NATIONAL OILWELL VARCO**

www.nov.com • mission.sales@nov.com  
10000 Richmond, Houston, Texas 77042  
(713)346-7500 (phone) • (713)346-7366 (fax)



April 28, 2011

Mr. Brad Hill  
State of Utah  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

Re: Letter of No Objection to Hardline Exception  
Integrated Water Management Saltwater Disposal Well #3-30B4  
SE/4SE/4 of Section 30, Township 2 South, Range 4 West  
Duchesne County, Utah

Mr. Hill,

El Paso, as offset operator, has no objection to Integrated Water Management drilling a saltwater disposal well, the IWM SWD 3-30B4, to be located 800' from the east line and 300' from the south line of Section 30, Township 2 South, Range 4 West, Duchesne County, Utah, at the proposed injection interval of 4,000' - 5,500' and with a maximum injection pressure as deemed acceptable to the Division of Oil, Gas and Mining.

If you have any questions, please call me at 303-291-6422.

Very truly yours,

El Paso E&P Company, L.P.

A handwritten signature in black ink, appearing to read "Catherine L. Hammock". The signature is fluid and cursive.

Catherine L. Hammock  
Sr. Staff Landman - Altamont Business Area



# STEP RATE TEST DATA

Well: WMSWD 33054 Date: 10/27/11 Operator: RL Follow Water Manual <sup>Integrated</sup>

STEP #1 Test Rate ( 5% of maximum rate) .3 (bbl/min)

Time (min)	0	5	10	15	20	25	30
Pressure (psi)	0	420					

STEP #2 Test Rate ( 10% of maximum rate) .6 (bbl/min)

Time (min)	0	5	10	15	20	25	30
Pressure (psi)	0	180	250	260	270	280	280

Note @ this point tested @ higher PPMP had little change in pressure -

STEP #3 Test Rate ( 20% of maximum rate) 2.0 (bbl/min)

Time (min)	0	5	10	15	20	25	30
Pressure (psi)	280	300	300	300	525	525	525

Note small drops in pressure as shown - Note Raised to 5.0 bbl/min on chart.

STEP #4 Test Rate ( 40% of maximum rate) 2 (bbl/min)

Time (min)	0	5	10	15	20	25	30
Pressure (psi)	400	400	400	400	400	400	400

@ this point called DAN - did 4.5 bbl/min

STEP #5 Test Rate ( 60% of maximum rate) \_\_\_\_\_ (bbl/min)

Time (min)	0	5					
Pressure (psi)	400	400					

STEP #6 Test Rate ( 80% of maximum rate) \_\_\_\_\_ (bbl/min)

Time (min)	0	5					
Pressure (psi)	525	525					

did 4.6 bbl/min

STEP #7 Test Rate ( 100% of maximum rate) \_\_\_\_\_ (bbl/min)

Time (min)							
Pressure (psi)							

ISIP : \_\_\_\_\_ (psi)

Test Run / Witnessed By: \_\_\_\_\_

Note pressure would NOT hold - expected to have pressure double when rate doubled - will re-evaluate as directed by Dan in 6 months after partial fill up - If constant w/ wells in the area the well injection pressure will be < 800#. Calculated pressure was ~ 890# for this interval - 3

STATE OF UTAH  
DIVISION OF OIL GAS AND MINING

## INJECTION WELL - PRESSURE TEST

Well Name: IWM SWD 3-3064 API Number: 43-013-50753  
 Qtr/Qtr: SE/SE Section: 30 Township: 2S Range: 4W  
 Company Name: NEWFIELD  
 Lease: State ✓ Fee ✓ Federal        Indian         
 Inspector: Alvin L. Ingram Date: 10/27/11

## Initial Conditions:

Tubing - Rate: 0 Pressure: 0 OPEN psi

Casing/Tubing Annulus - Pressure: 1360 psi

## Conditions During Test:

BARTON

Time (Minutes)	Annulus Pressure	Tubing Pressure
0	<u>1360</u> <u>1200</u>	<u>0</u> <u>0</u>
5	<u>1360</u> <u>1205</u>	
10	<u>1360</u> <u>1210</u>	
15	<u>1350</u> <u>1210</u>	
20	<u>1345</u> <u>1210</u>	
25	<u>1340</u> <u>1205</u>	
30	<u>1330</u> <u>1200</u>	<u>0</u> <u>0</u>

Results: Pass/Fail

## Conditions After Test:

Tubing Pressure: 0 psi

Casing/Tubing Annulus Pressure: 1200 psi

COMMENTS: Tested by closing valve & leaving Pump Hooked Up  
@ 10:25 Am (FAIL); Disconnected pump truck & in stall  
Barton Gauge w/ no escape @ 11:15 Am (PASS)

Operator Representative

Memo to John Rogers

Re: IWM SWD Application.

John:

As the supervisor over these programs I wanted to re-state our case and clarify some issues and update you on what IWM is doing to resolve this situation. It is the wish of IWM that this situation be dealt with administratively. Steps have been taken by IWM that will satisfy the DOGM (engineering reports etc.), and allow this issue to be resolved. Additional work could then be done by IWM (Step Rate Test, MIT) to allow IWM to receive a permit to inject in their SWD well.

You are probably aware as well that Brad Hill notified me that Pro Water has removed their objection and IWM's corporate council Matt Nelson has been instructed by Steve Alder to notify the board. I told Brad at that time some of the things that IWM is doing as outlined below and he appeared to be OK with what we were doing.

I have listed two rules that seem to be the crux of what the issues are:

Rule 649-3-4.1.

Prior to the commencement of drilling, deepening or plugging back of any well, exploratory drilling such as core holes and stratigraphic test holes, or any surface disturbance associated with such activity, the operator shall submit Form 3, Application for Permit to Drill, Deepen, or Plug Back and obtain approval. Approval shall be given by the division if it appears that the contemplated location and operations are not in violation of any rule or order of the board for drilling a well.

Notice was sent on April 8th to DOGM in the form of a completed application for a SWD well. The division was notified, the El Paso wells are working wells with no issues, the well files were reviewed at that time. If there was a problem then IWM should have been notified and possible action could have been taken before the drilling of the well.

Rule 649-5- 2.11.

A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter improper intervals.

In this matter I believe that "No conduit exists that would allow fluid to enter improper intervals". I support that statement with the following points:

- The 7" casing was cemented from TD to 6900'. It was done that way intentionally to allow a solid foundation for the setting of the main production casing (the 4 1/2") and allow for the 7" casing to be cut off and pulled when the well is finally plugged. This is consistent with most wells drilled in the area. Additionally in every well in the area all production has been at depths greater than 10,000'. Since the casing is cemented to 6900' fluid affecting any production zone in offset wells is not an issue.
- The 9 5/8" casing was cemented from 4519' to 2300'. No fluid can travel on the backside of the 9 5/8" casing.
- In the unlikely event that a hole developed in the 9-5/8" casing it would have to be large enough for any measurable amount of fluid to travel up the casing between the 7" and the 9-5/8" and enter a zone that is deemed an improper interval.
- The Conductor pipe was set at 300' which is below the interval where a majority of the water wells drilled in the area are currently pumping from.

In order to further explore every option and assure that the above requirement (Rule 649-5- 2.11) was being adhered to the following individuals were consulted and given information concerning this situation:

1. Vince Guinn PE with over 20 years experience in the Uintah Basin.
2. Bill Ryan PE with over 30 years experience in the Uintah Basin.
3. Ken Allen PE with over 30 years experience in the Uintah Basin.
4. Ellis Peterson PE with over 15 years experience in the Uintah Basin.
5. Steve Owen PE (Steve was the PE for Husky that drilled the 1-31 B4)

All agreed after a review of the well bore schematic and other additional data that since the 1-31 B4 is a producing well, MIT is in effect and that the likely hood of fluid entering "improper intervals" was virtually nonexistent. Both Elis Peterson and Bill Ryan suggested that to afford any extra degree of assurance the backsides of the 1-31 B4 could be monitored by installing a simple pressure gauge.

Additional important factors:

- The IWM well is down dip by approximately 68' to the 1-31 B4. It is generally agreed that when the fluid enters the IWM well bore that the plume of water will be in a general north south eclipse with more of the fluid going down dip or north away from the 1-31 B4.
- In order for any fluid to travel up the casing between the 7" and the 9- 5/8" sufficient pressure would have to be available to push the fluid up 3000'.

To support the above statements, IWM has retained a highly respected and certified Hydrologic Engineer (John Wood P.E.) and also a very experienced and certified Hydrologist (Rebecca Guston, PG in Utah with an MS in Hydrology and a BS

in Geology). Draft copies of those reports have been received by IWM. Both of these reports fully support the above issues.

It is IWM's position is to be pro active to provide applicable data for this issue. Copies of the final reports will be provided to the DOGM. Both reports deal with the pressure issues and capacity as it relates to Rule 649-5- 2.11.

In discussing this issue during a telephone conference in John Wood's office with Becca Guston (prior to them completing their reports), a suggestion was discussed (Proposed by Ellis Peterson and Bill Ryan), that a possible double check of the integrity of the casing may be to install at IWM's expense a separate gage on the wellhead on the backside of the 9-5/8" casing. The monitoring of these gages would insure that Mechanical Integrity of the casing is assured.

Summary:

- IWM will demonstrate with the Hydrological Engineering Reports that under the conditions outlined it is extremely improbable that any fluid could enter any strata above 2300'.
- If a further assurance is deemed necessary, IWM will instigate a monitoring program and report to the state the casing condition of the 1-31 B4 ASSURING that no fluid could enter Improper Intervals.
- Through these efforts IWM will satisfy the requirements as outlined by DOGM guidelines and regulations.

Thank you for your time and consideration in this matter. I would like to arrange a meeting with whoever needs to be there to provide closer to this matter.

Bob Ballou

	A	B	C	D	E	F	G	H	I	J	K	L
1	Produced Fluids #		1	2	3	4	5		Click here to run SSP	Click here: B/D, psia, F	Click here: m^3/D, bar, C	
2	Parameters	Units	Input	Input	Input	Input	Input					
3	Select the brines	Select fluid by checking the box(es),	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Mixed brine:				
4	Sample ID							Cell H28 is	Goal Seek SSP	Click here to output SI	Click here to output SR	
5	Date		6/22/2011	8/16/2010				STP calc. pH.				
6	Operator	Row 3	IWM	Bill Barrett				Cells H35-38 are used in mixed brines				
7	Well Name		Injection	12-24-12-14					calculations.	Initial(BH)	Final(WH)	SI/SR (Final-Initial)
8	Location		Formation									
9	Field		Water	Prickly Pear								
10	Na <sup>+</sup>	(mg/l)*	27,333.00	15,909.00				27,334.91				
11	K <sup>+</sup> (if not known =0)	(mg/l)	166.00	356.00				166.03	Saturation Index values			
12	Mg <sup>2+</sup>	(mg/l)	23.00	352.00				23.00	Calcite			
13	Ca <sup>2+</sup>	(mg/l)	228.00	1,913.00				228.02	0.00	-0.13	-0.13	
14	Sr <sup>2+</sup>	(mg/l)	47.00	0.00				47.00	Barite			
15	Ba <sup>2+</sup>	(mg/l)	11.00	4.00				11.00	2.06	2.00	-0.06	
16	Fe <sup>2+</sup>	(mg/l)	70.00	83.00				70.00	Halite			
17	Zn <sup>2+</sup>	(mg/l)	0.00	0.00				0.00	-3.76	-3.77	-0.01	
18	Cl	(mg/l)	39,100.00	27,900.00				39,102.73	Gypsum			
19	SO <sub>4</sub> <sup>2-</sup>	(mg/l)	830.00	1,040.00				830.06	-2.78	-2.79	-0.01	
20	F	(mg/l)						0.00	Hemihydrate			
21	Alkalinity**	(mg/l)	522.00	1,220.00				522.04	-3.55	-3.55	0.00	
22	Carboxylic acids**	(mg/l)	0.00	0.00				0.00	Anhydrite			
23	TDS (Measured)	(mg/l)	67,971.00	48,046.00				67,823.03	-3.04	-3.02	0.01	
24	Calc. Density (STP)	(g/ml)	1.043	1.031				1.043	Celestite			
25	CO <sub>2</sub> Gas Analysis	(%)						0.00	-1.09	-1.10	-0.01	
26	H <sub>2</sub> S Gas Analysis***	(%)	0.0000	0.0000				0.0000	Iron Sulfide			
27	Total H2Saq	(mgH2S/l)						0.00				
28	pH, measured (STP)	pH	9.76	6.79				11.58	Zinc Sulfide			
29	Use pH measured at STP to calculate SI?	1-Yes,0-No	0					0	Calcium fluoride			
30	Gas/day(thousand cf/day)	(Mc/D)	329					329				
31	Oil/Day	(B/D)	0					0	Iron Carbonate			
32	Water/Day	(B/D)	45					45	1.87	1.76	-0.11	
33												
34	For mixed brines, enter values for temperatures and pressures							(ENTER H35-H39)	Inhibitor needed (mg/L)			
35	Initial T (BH)	(F)	65.0					340.0	Calcite	NTMP		
36	Final T (WH)	(F)	65.0					77.0	0.00	0.00		
37	Initial P (BH)	(psia)	100.0					7,000.0	Barite	BHPMP		
38	Final P (WH)	(psia)	100.0					15.0	0.77	0.88		
39	Use TP on Calcite sheet?	1-Yes,0-No	1	0	0	0	0	0	pH			
40									7.07	6.91		
41	API Oil Grav.	API grav.						30.00	Viscosity (CentiPoise)			
42	Gas Sp.Grav.:	Sp Grav.						0.60	0.897	0.840		
43	MeOH/Day	(B/D)						0	Heat Capacity (cal/ml/°C)			
44	MEG/Day	(B/D)						0	0.993	0.992		
45	SiO <sub>2</sub>	(mg/l) SiO <sub>2</sub>						0.00	Inhibitor needed (mg/L)			
46	Pb <sup>2+</sup>	(mg/l)						0.00	Gypsum	HDTMP		
47	Br <sup>-</sup>	(mg/l)						0.00	0.00	0.00		
48	Conc. Multiplier		1	1	1	1	1	1	Anhydrite	HDTMP		
49									0.00	0.00		
50	Quality Control Checks at STP:		Click here to run the following quality control checks on the input data, above.									
51	H <sub>2</sub> S Gas	(%)										
52	Total H2Saq (STP)	(mgH2S/l)										
53	pH Calculated	(pH)										
54	PCO <sub>2</sub> Calculated	(%)										
55	Alkalinity Calculated	mg/l as HCO <sub>3</sub>										
56	ECations=	(equiv./l)										
57	EAnions=	(equiv./l)										
58	Calc TDS=	(mg/l)										
59	Inhibitor Selection	Input	Unit	#	Inhibitor	Unit Converter (From metric to English)						
60	Protection Time	120	min	1	NTMP	From Unit	Value	To Unit	Value			
61	Have ScaleSoftPitzer			2	BHPMP	°C	100	°F	212			
62	pick inhibitor for you?	0	1-Yes,0-No	3	PAA	m <sup>3</sup>	100	ft <sup>3</sup>	3,531			
63	If No, inhibitor # is:			4	DTPMP	m <sup>3</sup>	100	bbl(42 US gal)	629			
64	If you select Mixed,			5	PPCA	MPa	1,000	psia	145,074			
65	1 <sup>st</sup> inhibitor # is:	1	#	6	SPA	Bar	100	psia	1,450			
66	% of 1 <sup>st</sup> inhibitor is:	50	%	7	HEDP	Torr	10,000	psia	193			
67	2 <sup>nd</sup> inhibitor # is:	2	#	8	HDTMP	Gal	10,000	bbl(42 US gal)	238			
68	Display act. coeffs?	0	1-Yes,0-No	9	Average	Liters	10,000	bbl(42 US gal)	63			
69				10	Mixed							
70	* Concentrations are in mg/L of brine (except methanol and MEG, which are in units of barrels per day, the same as the water and oil)											



November 2, 2011

Mr. Robert Ballou  
Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066

Re: Integrated Water Management Facility  
Waste Water Injection Well  
Duchesne, Utah

Dear Mr. Ballou,

In accordance with your request, we have prepared this addendum to the hydrologic study dated September 21, 2011 of the Integrated Water Management (IWM) disposal well located in Section 30, Township 2 South, Range 4 West, Uintah Special Meridian. The hydrologic study was conducted to address concerns raised by the Utah Division of Oil, Gas and Mining (UDOGM) regarding the IWM disposal well. UDOGM had expressed the concern that waste water injection in the IWM well may create a conduit that could enable fluids to migrate up or down the wellbore of a nearby gas production well, and enter improper intervals.

The purpose of the previous hydrologic study was to address this concern by constructing a three-dimensional groundwater flow model to simulate the effects on the nearby gas production well in question due to waste water injection in the IWM disposal well over a period of 100 years. Assumptions made in the groundwater flow model included completely saturated conditions and an average porosity of 15 percent. However, additional information has become available that indicates that the zone of injection for the IWM well is not saturated. Mr. Shawn Moulton of Halliburton was contracted to analyze geophysical data from the IWM well using SASHA Water Saturation Analysis V2 software to assess the degree of saturation within perforated intervals. While installing the IWM well, a total of 180 feet of perforations were created within highly conductive zones between 4063 and 5130 feet below ground surface. Mr. Moulton indicated that water saturation in the perforated zones of the IWM well range between 25 and 50 percent, and average approximately 30 percent saturation.

Unfortunately, the three-dimensional groundwater flow model constructed for the site using Visual MODFLOW cannot be modified to less than 100 percent saturation conditions. Therefore, a few calculations were made to estimate the time period during which all void spaces in the perforated interval would be filled to 100 percent saturated conditions. These calculations are included in Appendix A to this document.

## FINDINGS

Assuming 5,000 barrels of waste water will be injected into the IWM well per day, 360 days per year, the estimated time to fill all pore spaces within ¼-mile of the 180-foot perforated interval of the IWM well would be approximately 10.4 years. If the area of review is extended to 1,650 feet from the IWM well, which is the distance to the 1-31 B4 well, then the estimated time to fill all pore spaces would increase to approximately 16.3 years.

Our services consist of professional opinions and recommendations made in accordance with generally accepted environmental principles and practices at the time of execution. This warranty is in lieu of all other warranties either expressed or implied.

Should you have any questions, please do not hesitate to contact us.

Sincerely,  
*GRANITE ENVIRONMENTAL, INC.*

A handwritten signature in black ink, appearing to read "Rebecca Gustin". The signature is fluid and cursive, with the first name "Rebecca" being more prominent than the last name "Gustin".

Rebecca Gustin, P.G.  
Senior Geologist



## APPENDIX A

### Pore Space Calculations

Assumptions made for calculating the time to fill the pore spaces around the IWM well:

1. Two areas of review will be considered. The first is the ¼-mile distance designated by the EPA for impacts due to injected water. The second is the distance to the 1-31 B4 well, which is 1,650 feet from the IWM well.
2. The average porosity of the formation is approximately 15 percent.
3. The average water saturation in the pores of the formation is approximately 30 percent. Therefore 70 percent of the pore space in the formation is available for water input.
4. Between the interval of 4063 and 5130 feet below ground surface, 180 feet of perforations have been installed in the IWM injection well. Calculations of volume will include only the perforated intervals.
5. The injection rate for the IWM well will be 5,000 barrels per day for 360 days per year.

#### Calculations for ¼-mile area of review

Volume of formation (V) considered:

$$V = \pi R^2 H$$

where R = radius of review = 1,520 ft

H = height of perforated intervals = 180 ft

$$V = 9.84 \times 10^8 \text{ ft}^3$$

Available pore space within the formation within the volume in question is assumed to be 15 percent. Therefore, the available volume for fluids ( $V_a$ ) within the formation is calculated to be:

$$V_a = 0.15 (9.84 \times 10^8 \text{ ft}^3) = 1.48 \times 10^8 \text{ ft}^3$$

If 30 percent of the pore spaces are already occupied by groundwater, as indicated in the geophysical logs from the IWM well, then 70 percent of the pore spaces are available for fluid injection. Therefore, the available volume for injected fluids ( $V_i$ ) within the formation is calculated to be:

$$V_i = 0.70 (1.48 \times 10^8 \text{ ft}^3) = 1.03 \times 10^8 \text{ ft}^3$$

The available volume for injected fluids ( $V_i$ ) in terms of barrels, given that there are 5.5 ft<sup>3</sup> in one barrel, is then given as:

$$V_i = (1.03 \times 10^8 \text{ ft}^3) \frac{1 \text{ barrel}}{5.5 \text{ ft}^3} = 1.88 \times 10^7 \text{ barrels}$$

Given an injection rate of 5,000 barrels per day, 360 days per year, the time ( $T_{1,520 \text{ ft}}$ ) to fill all available pore spaces within ¼-mile of the IWM well is given as:

$$T_{1,520 \text{ ft}} = (1.88 \times 10^7 \text{ barrels}) \left( \frac{\text{day}}{5,000 \text{ barrels}} \right) \left( \frac{\text{year}}{360 \text{ days}} \right) = 10.4 \text{ years}$$

Similarly, if the area of review were increased to 1,650 feet, the time ( $T_{1,650 \text{ ft}}$ ) to fill all available pore spaces within the area of review is given as:

$$T_{1,650 \text{ ft}} = 16.3 \text{ years}$$



October 6, 2011

Mr. Robert Ballou  
Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066

Re: Addendum to Hydrologic Study  
Integrated Water Management Facility  
Waste Water Injection Well  
Duchesne, Utah

Dear Mr. Ballou,

In accordance with your request, we have prepared this addendum to the hydrologic study of the Integrated Water Management (IWM) disposal well located in Section 30, Township 2 South, Range 4 West, Uintah Special Meridian, to address concerns raised by the Utah Division of Oil, Gas and Mining (UDOGM) regarding the IWM disposal well. Rebecca Gustin, P.G. of Granite Environmental spoke with Mr. Dan Jarvis of UDOGM on September 22, 2011 regarding the hydrologic study dated September 21, 2011. Mr. Jarvis had two questions that he needed clarified with regard to the hydrologic study.

First, Mr. Jarvis asked what the pumping pressure was for the modeled injection well in the hydrologic study. In the Visual MODFLOW software, only pumping rate is considered when modeling groundwater flow around an injection well. However, the pumping rate is directly related to the pumping pressure. For example, if pumping pressure were decreased in an injection well, the pumping rate would correspondingly decrease. Therefore, if pumping pressure were increased or decreased, pumping rate would increase or decrease, and the corresponding groundwater flow around the injection well would change.

Second, Mr. Jarvis expressed concerns that injected water from the IWM injection well could potentially reach the uncemented interval of the 7-inch casing in the 1-31 B4 well, and travel down the outside of the casing and enter improper intervals. In this hydrologic model, it has been assumed that the geological formations are saturated with water beginning at a depth of 800 feet below ground surface (bgs). Therefore the borehole outside the uncemented region of the 7-inch casing in the 1-31 B4 well between 4519 ft bgs and 6899 feet bgs is likely filled with water. If injected water from the IWM well reaches the uncemented region of the 7-inch casing of 1-31 B4 well it will encounter formation groundwater. The only way that the injected water could travel downward would be if there was a significant density difference between the injected water and the surrounding groundwater. In other words, the injected groundwater would have to be significantly more saline, with corresponding higher

density, than the existing groundwater in order to have downward flow of the injected water around the 1-31 B4 well.

## CONCLUSIONS

It is our opinion that the waste water injection activities at the IWM well will minimally impact the 1-31 B4 well. As stated in the hydrologic report of September 21, 2011, the pressure head in the 1-31 B4 well will be slightly increased by the injection activities, but the pressure head is not high enough to overcome the weight of the water column between the 7-inch and the 9-5/8-inch casings from 4519 feet bgs up to 2301 feet bgs. The modeled injection rate was 210,000 gallons per day, and if injection pressure were to change, the corresponding injection rate would change, and corresponding heads would change in the groundwater around the injection well. In addition, injected water from the IWM well is unlikely to travel down the outside of the 7-inch casing because there is no significant density difference between the injected water and existing groundwater in the region.

Our services consist of professional opinions and recommendations made in accordance with generally accepted environmental principles and practices at the time of execution. This warranty is in lieu of all other warranties either expressed or implied.

Should you have any questions, please do not hesitate to contact us.

Sincerely,

*GRANITE ENVIRONMENTAL, INC.*

A handwritten signature in black ink, appearing to read "Rebecca Gustin". The signature is fluid and cursive, with a large initial "R" and a long, sweeping underline.

Rebecca Gustin, P.G.  
Senior Geologist



September 21, 2011

Mr. Robert Ballou  
Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066

Re: Integrated Water Management Facility  
Waste Water Injection Well  
Duchesne, Utah

Dear Mr. Ballou,

In accordance with your request, we have prepared this hydrologic study of the Integrated Water Management (IWM) disposal well located in Section 30, Township 2 South, Range 4 West, Uintah Special Meridian, to address concerns raised by the Utah Division of Oil, Gas and Mining (UDOGM) regarding the IWM disposal well. UDOGM has expressed the concern that waste water injection in the IWM well may create a conduit that could enable fluids to migrate up or down the wellbore of a nearby gas production well, and enter improper intervals. The purpose of this hydrologic study is to address this concern by constructing a three-dimensional groundwater flow model to simulate the effects on the nearby gas production well in question due to waste water injection in the IWM disposal well over a period of 100 years.

## **BACKGROUND**

According to the information that you have supplied to us, the IWM disposal well has been constructed with perforated intervals between 4068 feet below ground surface (bgs) and 5130 feet bgs, and planned injection rates will range between 3000 and to 5000 barrels per day.

Also, it is our understanding that the nearby gas production well (1-31 B4) is located approximately 1650 feet south of the IWM well. The 1-31 B4 well was constructed in the early 1970s with a 4-1/2-inch production liner from 9384 feet bgs to 12,400 ft bgs, a 7-inch casing from the surface to 10,062 feet bgs that is cemented from 6899 feet bgs to 10,062 feet bgs, and a 9-5/8-inch casing from the surface to 4519 feet bgs, with cement between 2301 feet bgs and 4519 feet bgs. Figure 1 depicts the construction of the 1-31 B4 well.

UDOGM has noted that there is no cement between the 7-inch and the 9-5/8-inch casing from 4519 feet bgs to 6899 feet bgs, and waste water will be injected from the IWM well within this interval. The concern is that waste water from the IWM well could migrate to the 1-31 B4 well, enter the annulus between the 7-inch and the 9-5/8-inch casings, and be pushed up to the top of the cemented interval of the 9-5/8-inch casing (2301 feet bgs). If the waste water is able to migrate into this interval, then the

concern is that waste water may enter into the surrounding formation through any holes that might potentially be present in the 9-5/8-inch casing.

Therefore, we have constructed a three-dimensional groundwater flow model to show whether the injection activities at the IWM well could potentially raise the hydraulic head at the 1-31 B4 well enough to allow waste water to travel from the bottom to the top of the cemented interval of the 9-5/8-inch casing, a vertical distance of 2218 feet.

## **REGIONAL HYDROGEOLOGY**

According to United States Geological Survey Groundwater Atlas of the United States (1995), the region is underlain by an unconfined aquifer approximately 800 feet bgs, with groundwater flow generally north-northeast with a gradient of approximately 0.008 ft/ft. According to Picard (1959), regional stratigraphy consists of the Duchesne River Formation at the surface, underlain by the Uinta Formation, and then the Green River Formation. All three formations were formed in fluvial and lacustrine environments, and are characterized by alternating beds of shale, limestone and dolomite, and sandstone and siltstone.

## **HYDROLOGIC MODEL**

A mathematical groundwater flow model of the region around the IWM and 1-31 B4 wells was constructed using Visual MODFLOW 2010.1, a three-dimensional finite difference groundwater model. In this model the MODFLOW-2005 groundwater flow engine with the WHS Solver package (pre-conditioned conjugate gradient stabilized) by Waterloo Hydrologic was used to model the groundwater flow. The region was modeled as a 10,000-foot by 10,000-foot area, centered on the IWM injection well. A 200-foot by 200-foot grid was constructed on top of the model to discretize the modeling domain for the numerical simulation.

Physical model parameters used on the MODFLOW numerical model include hydraulic conductivity, porosity, effective porosity, and specific yield:

- An average hydraulic conductivity of 1 gallon/day/ft<sup>2</sup> was chosen based on recommended ranges of hydraulic conductivity for sandstone presented in Freeze and Cherry, 1979. Hydraulic conductivity was assumed to be isotropic in the horizontal direction and anisotropic in the vertical direction, such that  $K_x = K_y = 0.1 K_z$ . Of note, we made a conservative assumption that the aquifer in question was made of homogeneous sandstone, with uniform physical model parameters. In reality, the aquifer consists of interbedded lower conductivity materials (shale, siltstone), and higher conductivity materials (sandstone).
- Porosity was assumed to be 15%, based upon your recommendations.
- Effective porosity was also assumed to be 15%, giving a conservative estimate.
- Specific yield, which is roughly equivalent to the effective porosity in an unconfined aquifer, was assumed to be 15%.

Groundwater flow boundary conditions were created for the model using constant head boundaries on the north and south sides of the model, creating a south to north groundwater flow regime located approximately 800 feet bgs with a horizontal gradient of approximately 0.008 ft/ft and no vertical gradient.

The IWM injection well was modeled by creating a pumping well with screened interval from 4068 feet bgs to 5130 feet bgs. The injection rate was held steady at 5000 barrels per day (210,000 gallons per day) for 100 years.

## **FINDINGS**

The results of the model are presented in Figures 2 through 4 of this report. Figure 2 presents the results of the model in map view, at a depth of 4500 feet bgs (bottom of the cemented interval of the 9-5/8-inch casing of the 1-31 B4 well). An increase in hydraulic head of approximately 400 feet is observed at the injection well, and approximately 100 feet at the 1-31 B4 well. Figure 3 presents the results of the model in map view at a depth of approximately 2300 feet bgs, which corresponds to the top of the cemented interval of the 9-5/8-inch casing of the 1-31 B4 well. An increase in hydraulic head of approximately 11 feet is observed at the injection well, and approximately 2 feet at the 1-31 B4 well. This indicates that the increase in hydraulic head from injection activities results in an increase in the pressure head at the two wells, but not a significant increase in elevation head at the top of the cemented interval of the 9-5/8-inch casing of the 1-31 B4 well.

Figure 4 presents the results of the model in a north-south cross-sectional view.

## **CONCLUSIONS**

It is our opinion that the waste water injection activities at the IWM well will minimally impact the 1-31 B4 well. The pressure head in the 1-31 B4 well will be increased slightly by the injection activities, but the pressure head is not high enough to overcome the weight of the water column between the 7-inch and the 9-5/8-inch casings from 4519 feet bgs up to 2301 feet bgs. Therefore waste water is very unlikely to migrate up the wellbore of the 1-31 B4 well, and enter an improper interval.


## **REFERENCES**

- Robson, S.G. and Banta, E.R., USGS Groundwater Atlas of the United States; Arizona, Colorado, New Mexico and Utah, USGS Publication HA 730-C, 1995.
- Picard, M. Dane, Green River and Lower Uinta Formation Subsurface Stratigraphy in Western Uinta Basin, Utah, Intermountain Association of Petroleum Geologists, 1959.
- Freeze, R. Allan, Cherry, John A., Groundwater, Prentice-Hall, Inc., 1979.

Our services consist of professional opinions and recommendations made in accordance with generally accepted environmental principles and practices at the time of execution. This warranty is in lieu of all other warranties either expressed or implied.

Should you have any questions, please do not hesitate to contact us.

Sincerely,  
*GRANITE ENVIRONMENTAL, INC.*


A handwritten signature in cursive script, appearing to read "Rebecca Gustin".

Rebecca Gustin, P.G.  
Senior Geologist



43013301980000 Christman-Bland compl  
Casing Schematic

①



prepared by Ammon McDonald DOG-M



1-31 B4 Well Construction

Integrated Waste Management Facility  
Waste Water Injection Well  
Duchesne, UT



PROJECT NO.

DATE

Sept 21, 2011

FIGURE 1

Potentiometric Surface Map, 4500 Ft BGS



### Potentiometric Surface Map

Integrated Water Management Facility  
Waste Water Injection Well  
Duchesne, UT



PROJECT NO.

DATE

Sept 21, 2011


FIGURE 2

Potentiometric Surface Map, 2300 Ft BGS



**Potentiometric Surface Map**  
**Integrated Water Management Facility**  
**Waste Water Injection Well**  
**Duchesne, UT**

PROJECT NO.	DATE	FIGURE 3
	Sept 21, 2011	



APPROXIMATE SCALE (ft.)



### North-South Cross-Section

Integrated Water Management Facility  
Waste Water Injection Well  
Duchesne, UT

PROJECT NO.

DATE

Sept 21, 2011

FIGURE 4

## **Rebecca Brown-Gustin, E.I.T., P.G.**

923 West 650 South  
Heber City, Utah 84032  
435-714-0424

**Education** M.S. Geological Engineering, University of Idaho, in progress, December 2011  
M.S. Hydrogeology, New Mexico Institute of Mining and Technology, 1992  
B.S. Geology, New Mexico Institute of Mining and Technology, 1990

**Registration** Professional Geologist: Utah #5505561-2250  
Engineer-In-Training: Utah

**Certifications** Utah Certified Underground Storage Tank Consultant #CC0219  
Utah Certified Soil and Groundwater Sampler #GS1523  
OSHA 40-Hour Hazardous Materials Operation  
OSHA 8-Hour Hazardous Materials Supervisor  
OSHA 8-Hour Refresher, March 2010

### **Professional Courses**

Applied Groundwater Flow and Contaminant Transport Modeling, Schlumberger  
Water Services  
Groundwater Pollution and Hydrology Course, Princeton Groundwater, Inc.  
The Remediation Course, Princeton Groundwater, Inc.  
Contaminant Chemistry and Transport Workshop Series, Northwest Environmental  
Training Center  
Monitored Natural Attenuation of Petroleum and Chlorinated Hydrocarbons In Soil  
and Groundwater, Northwest Environmental Training Center  
ASTM Environmental Site Assessments for Commercial Real Estate

### **Experience**

Ms. Gustin has been a practicing hydrogeologist for 12 years. She has performed Phase I and Phase II Environmental Site Assessments, conducted soil and groundwater monitoring, and written feasibility studies and remedial action plans. She has participated in remediation design and implementation for several petroleum and chlorinated solvent impacted sites. Ms. Gustin has also constructed groundwater flow and solute transport numerical models using a variety of modeling codes including Visual MODFLOW, MODPATH, MT3D, RT3D, BIOCHLOR, and VLEACH.

### **Project Management**

Ms. Gustin has been responsible for project management of personnel and budgets for environmental projects ranging from \$1000 up to \$500,000. As the owner of two small businesses between 1997 and 2009, Ms. Gustin has been responsible for all business aspects of the companies including marketing, client relations, job proposals, project cost accounting, company financial planning, general accounting, payroll, corporate tax preparation, contractor licensing, and insurance.

### **Environmental Due Diligence**

Ms. Gustin has performed many Phase I Environmental Site Assessments (ESAs) and Transaction Screens on properties ranging from vacant land to heavy industrial complexes. The Phase I ESAs were conducted in general accordance with the scope and limitations of the *Standard Practice for Environmental Site Assessments: Phase I Site Environmental Site Assessment Process* as presented in ASTM E 1527-05.

### **Site Investigations**

**Private Client, Site Investigation:** Ms. Gustin conducted several site investigations at an oil refinery in Woods Cross, Utah. Site investigations began with a Phase II ESA designed to detect any potential impacts to soil and groundwater resulting from oil refining operations and from past use of the property to store hazardous materials. When petroleum product and solvent impacts were discovered, further site investigations were conducted to characterize the horizontal and vertical extent of soil and groundwater impacts. Approximately 4,000 cubic feet of heavily impacted soil was removed from the site, and a sparge well was installed to remediate remaining impacted groundwater from the excavation site.

**State of Utah School and Institutional Trust Lands Administration, Site Investigation:** Ms. Gustin performed a Phase II ESA on a SITLA property in Saratoga Springs, Utah that was formerly leased to a company that manufactured explosive materials that were sold to mining companies. The investigation included a detailed ground penetrating radar (GPR) survey to locate possible buried debris, excavation and sampling of soils in areas of GPR anomalies, and drilling with continuous soil sampling in areas where explosive mixtures were reportedly disposed.

### **Feasibility Studies and Remediation**

**Private Client, Feasibility Study:** Ms. Gustin conducted a feasibility study of a laundry facility in Salt Lake City, Utah that had formerly been used as a dry cleaner. Extensive tetrachloroethene (PCE) impacts to soil and groundwater were discovered at two locations at the facility. Challenges were encountered when contemplating possible remedial strategies for this facility because impacted soil and groundwater are located beneath occupied buildings, and because soils beneath the facility are composed of silt and clay with low hydraulic conductivities. After an exhaustive search for innovative remediation technologies for solvent-impacted low conductivity soils, Ms. Gustin concluded that thermal remediation of the site was the best remedial technology to address the impacted soil and groundwater at the site.

**Farmington Junior High School, Remediation:** Ms. Gustin directed the remediation of fuel oil-impacted soils and groundwater from an area adjacent to the Farmington Junior High School in Farmington, Utah. The source of the fuel oil was from storage tanks and pipelines that formerly supplied fuel oil to boilers at a plant nursery that occupied the property before the school was constructed. Remediation activities included excavation of impacted soils, pumping of impacted groundwater while excavation activities proceeded, and final treatment of impacted groundwater using amendments to augment the biodegradation of the petroleum products. Ms. Gustin subsequently directed activities to install monitoring wells around the school, and to investigate possible vapor intrusion issues into the school.

### **Groundwater Fate and Transport Modeling**

**Private Client, Groundwater Fate and Transport Model:** Ms. Gustin constructed a three-dimensional groundwater flow and contaminant fate and transport model using Visual MODFLOW of a facility with two areas of PCE impacts to soil and groundwater resulting from past dry cleaning activities. The model was used to estimate the stability of the contaminant plumes, predict future pathways of contaminant migration, and was used as a tool in a feasibility study to evaluate the effectiveness of different remedial strategies.

**Private Client, Vadose Zone Transport Model:** Ms. Gustin constructed a vadose zone leaching model using the VLEACH program to estimate the impact on underlying groundwater resources due to the mobilization and migration of a sorbed organic contaminant located in the vadose zone. For this project, PCE was detected at very high concentrations next to a dry cleaning facility that was located approximately 70 feet above the groundwater table. Subsurface soils consisted of interbedded silty sand and cobble, and isolated, intermittent clay layers that acted as aquitards to the flow of PCE down towards the groundwater table. The conclusion to the transport model was that expected concentrations of PCE in groundwater at the groundwater table were well below Maximum Contaminant Levels, and therefore impacted soils remaining next to the dry cleaner facility would not significantly degrade groundwater. The facility received regulatory closure from the State of Utah in the spring of 2010.

### **Underground Storage Tank Consulting**

Ms. Gustin has been a UST Consultant for several gas stations throughout Utah. UST Consultant duties have included interfacing with the State of Utah Division of Environmental Response and Remediation project managers, conducting site investigations to assess the extent of soil and groundwater impacts from spills or leaking USTs, preparing corrective action plans for sites requiring remediation, and preparing closure documents. Remediation techniques that Ms. Gustin has used at UST sites have included free product removal, excavation, air sparing, soil vapor extraction, bioventing and biosparging, and monitored natural attenuation. Ms. Gustin has also assisted in the removal of several USTs, and facilitated the subsequent closure of these sites.

### **Employment History**

2010 – present	Granite Environmental, Inc. <i>Senior Geologist/Project Manager</i>	Salt Lake City, Utah
2006 – 2010	Wasatch Environmental, Inc. <i>Project Hydrogeologist/Project Manager</i>	Salt Lake City, Utah
2004 – 2009	Performance Drilling, Inc. <i>Owner, Geologist</i>	Salt Lake City, Utah
1999 – 2000	Masson & Associates <i>AutoCAD Designer</i>	Escondido, California
1997 – 2004	Gustin Transcription Services <i>Owner, Lead Medical Transcriptionist</i>	Albuquerque, New Mexico
1992 – 1997	Golder Associates, Inc. <i>Staff and Project Hydrogeologist</i>	Los Alamos, New Mexico
1992	Los Alamos National Laboratory <i>Intern Hydrogeologist</i>	Los Alamos, New Mexico
1991	Oak Ridge National Laboratory <i>Intern Hydrogeologist</i>	Oak Ridge, Tennessee

<b>Memberships</b>	Utah Geological Association (UGA) – Board member 2008-2010 American Society for Testing and Materials (ASTM) – D18 Subcommittee National Ground Water Association (NGWA) American Society for Civil Engineers (ASCE)
--------------------	---

Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066  
Office 435-722-3555 Fax 435-722-3556 Cell 435-724-2500  
rballou@stratanet.com  
August 29, 2011

RE: Christman Bland 1-31 B4/IWM SWD 3-30B4

Brad/Ammon:

Over the weekend I happened to have the opportunity to have an extended visit with Gary Lamb of El Paso. Gary is the individual that provided me the Cement Bond Logs for the two wells in the proximity of our SWD well. He also provided to me the use of the complete well file and all of the available logs of the 1-31 B4.

We discussed the current situation and he suggested that considering the distance from the wells, the current state of the well bore and that the 1-31 was up dip to the IWM SWD well that there was very slim possibility that production water would ever even come in contact with the 7" casing of the 1-31 B4. Additionally, even if it did the only way it would have an avenue of travel would be if a hole developed in the 7" casing (and if this happened El Paso would know that).

Considering that the situation he considers is a non problem he suggested that if and when a hole develops in the 7" that would allow production water to enter into the 7", that at that time El Paso would pull the production tubing, appropriate wire line tools would be run to determine the location of the hole and a squeeze job would be done at that time. At that time IWM would be willing to cover the costs of that operation.

Incidentally El Paso is anxious for us to have the SWD well in operation as they are a customer of IWM and we have had to deny them access to our facility until we can handle the fluid.

Update on what our efforts have been:

- I have met with an individual, (Lynn Monson who currently works for Newfield Production) that does all of Newfield's step rate tests. We have arranged for him to help us on a consulting basins next Saturday to run a step rate test and a MIT test.



- I have provided data to John Wood of Civco Engineering on the Pro Water objection. He reviewed my data and he provided me a document wherein he states that he concurs with my calculations regarding the impact (or lack of) on the Blue Bench Facility.
- We have had Central Hydraulic build a Tri Plex pump and it is being set on a pad that has been poured.
- We poured a pad for the water holding tank and ordered the lines and pump.
- We have given out the job to construct a pump shack and have ordered the electronics.

We believe that IWM is an asset to the operators in the region. We know that with the addition of the SWD well (and the oil processing equipment that was purchased last week and is being delivered this week) that we will have a facility that has taken the steps to deal with issues effecting the local operators, the County and the State.

IWM requests that with the completion of the MIT and the data obtained on the Step Rate Test that with the exception of the delaying tactics of Pro Water that IWM be given a permit to inject as a SWD facility.

Thank you for your consideration on this matter. I am available to come to Salt Lake or provide any other assistance.

Regards,

Bob Ballou

**CIVCO Engineering, Inc.**  
**Civil Engineering Consultants**  
PO Box 1758 \* 1256 W 400 S, Suite 1  
Vernal, Utah 84078

---

October 17, 2011

Robert Ballou  
849 Canyon View Drive #416-3  
Roosevelt, Utah 84066

Dear Mr. Ballou:

I have reviewed the data regarding the installation of a disposal well located at the Integrated Water Management (IWM) facility in Section 30, Township 2 South, Range 4 West, Uintah Special Meridian.

In my September 13, 2011 letter to you, I made the assumption that the injection zone was unconfined and unsaturated. I have reviewed Rebecca Gustin's hydrologic study in which she assumed unconfined and saturated conditions. The conclusions she reached are much more conservative than my own. However, the methodology she used was correct. I spoke with her and she agreed that if the zone is unsaturated the results would be much less conservative.

There is no cement seal in the annular space between the 9-5/8" casing and the 7" casing for Well 1-31 B4. The State of Utah, Division of Oil, Gas, and Mining (Division) is concerned with the possibility of the contaminants from the IWM injection well entering existing ground water at an improper interval through this conduit.

The bottom of the 9-5/8" casing for Well 1-31 B4 is at an elevation of approximately 1,381 feet above MSL. The IWM well is perforated at different intervals between 1,020 feet above MSL and 2,087 feet above MSL. These perforations are in the same elevation range as the Well 1-31B4 9" casing bottom. There are two conditions that would need to occur for the water from the IWM injection well to enter an improper interval.

The first condition is that the contaminants would have to migrate to Well 1-31 B4. All indications are that the IWM injection well is down gradient and possibly cross gradient from the Well 1-31 B4. Given this condition, the contaminants from IWM injection well would travel away from well 1-31B4.

# **CIVCO Engineering, Inc.**

## **Civil Engineering Consultants**

PO Box 1758 \* 1256 W 400 S, Suite 1

Vernal, Utah 84078


---

The second condition is that an open conduit would exist for contaminants to migrate to an improper interval. The annular space between the 9-5/8" casing and the 7" casing of Well 1-31 B4 does not have a cement plug, thus forming a conduit. However, both casings are installed to the surface which forms a closed conduit. The 9-5/8" casing would have to have a catastrophic failure to form an open conduit. Also, in order for water to rise higher than that of the surrounding aquifer, the casing would have to penetrate a confined aquifer and would have to be sealed between the casing and the confining layer. This aquifer does not demonstrate characteristics of a confined aquifer. Given the nature of the aquifer, any failure of the casing within the aquifer would only equalize any differences of water elevation between that of the surrounding aquifer and any water in the annular space. The water injected at the IWM injection well would stay in the same aquifer it is injected into. The background water in this zone is generally considered to be brackish and is not fit for human consumption.


According to the model developed by Rebecca Gustin, under the worst case scenario, two feet of additional head could be developed at Well 1-31 B4 (approximately 1psi). This differential head would not be enough to move contaminants up the annular space at Well 1-31 B4. Volatile organic constituents are generally lighter than water and are the only constituents that are likely to move upwards from where they are injected. The water that is injected in the IWM well has been treated through three evaporation ponds prior to being injected. The average detention time for this will be between 178 days and 297 days. This is sufficient time for volatile organics to dissipate prior to injection. Any other contaminants would migrate with the hydraulic gradient and slightly down.

After reviewing the data, it is my opinion that the water injected into the IWM well will not affect Well 1-31 B4 well or adversely affect any other water bearing zones.

If you have any questions, please give me a phone call. Thank you.



John S. Wood, SE



# **CIVCO Engineering, Inc.**

## **Civil Engineering Consultants**

**PO Box 1758 \* 1256 W 400 S, Suite 1**

**Vernal, Utah 84078**

---

**John S. Wood, SE**

**Education:** 1986, BS, Civil Engineering, Brigham Young University  
1987, MS, Civil Engineering w/emphasis in environmental engineering  
– hydrogeology, Brigham Young University

**Experience:** State of California, Regional Water Quality Control Board, Central Valley Region, Toxics and Groundwater Protection Unit, 1987-1988.

US Bureau of Land Management, Vernal Field Office, project over sight on leaking underground storage tank assessment and removal, 1990-1992.

US Bureau of Land Management, Vernal Field Office, reviewed a well drilling proposal by the USGS for a water well located in the Book Cliffs, 1993-1994.

US Bureau of Land Management, Vernal Field Office, Source Protection Plan review for Clay Basin, 1996.

US Forest Service, Ashley National Forest, Source Protection Plan review, 2002.

US Forest Service, Ashley National Forest, Upper Country Water District, Upper Cow Spring Development EA, team member responsible for hydrology and engineering review, 2002-2004.

Wood Engineering, Inc. production water disposal facility design and construction over sight for Brennan Bottom and Iowa Tank Lines, 2007-2009

CIVCO Engineering, Inc. production water disposal facility design and construction over sight for Iowa Tank Lines and Integrated Water Management, 2010-2011.

**CIVCO Engineering, Inc.**  
**Civil Engineering Consultants**  
PO Box 1758 \* 1256 W 400 S, Suite 1  
Vernal, Utah 84078

---

September 13, 2011

Robert Ballou  
849 Canyon View Drive #416-3  
Roosevelt, Utah 84066

Robert:

I have reviewed the data regarding the installation of a disposal well located at the Integrated Water Management facility in Section 30, Township 2 South, Range 4 West, Uintah Special Meridian.

In order for the casing to provide a conduit for contamination of aquifers, a failure of the casing would have to occur. The cement seals will prevent the conduit between the casings.

I performed my calculations to determine the possibility of the IWM well affecting the 1-31 B4 well located 1650 feet from the IWM well. Based on very conservative values, if there were no flow in the aquifer and the injected water filled the aquifer in a cylinder from the difference in the elevations of the aquifer levels at the wells, it would take 2,588 days to fill the voids of the aquifer.

I calculated the flow of water based on the hydraulic conductivity of 1 gal/day/ft<sup>2</sup> (K). The radius of influence with this K would be 200 feet. The capacity of the aquifer at 1650 foot radius would be 203,642 bbl/day. IWM will discharge an average of 3000 bbl/day.

These numbers demonstrate that the IWM will not affect the 1-31 B4 well.

If you have any questions, please give me a phone call. Thank you.

John S. Wood, SE

# CIVCO Engineering, Inc.

Civil Engineering Consultants

P.O. Box 1758 • Vernal, Utah 84078

(435) 789-5448 • Fax (435) 789-4485 • email: civco@civcoengineering.com

SHEET NO.: 1 OF 2

DATE 9-12-11

PROJECT NO.: \_\_\_\_\_ LOCATION IWM Injection Well BY JSW

Given:  $R = 1650'$   $h = H_1 - H_2 = 68'$  Porosity = 15%  
HYDRAULIC CONDUCTIVITY  $K = 10^{-5}$  cm/sec  
RANGE FOR K SANDSTONE  $\approx 1$  gal/day/ft<sup>2</sup>  
 $10^{-8}$  cm/sec TO  $10^{-3}$  cm/sec

1) Calculate Storage w/ NO Flow

Assume a cylinder w/ 68' HEAD VERY CONSERVATIVE

$$V = 0.15 \left( \frac{\pi R^2 h}{2} \right) = 0.15 \left( \frac{\pi (1650')^2 68'}{2} \right)$$
$$= 43598115.10 \text{ ft}^3$$
$$= 7764677 \text{ bbl}$$

① 3000 bbl/day = 2588 DAYS TO IMPACT WELL

2) Calculate w/ Flow

3000 AVE BBL/DAY

$$Q = KA$$

$$A = \frac{Q}{K}$$

$$= \frac{3000 \text{ BBL/D} \times 42.8 \text{ BBL}}{1 \text{ gal/day/ft}^2}$$

$$= 126000 \text{ ft}^2$$

$$A = \pi r^2$$

$$r = \sqrt{\frac{A}{\pi}}$$

$$= \sqrt{\frac{126000}{\pi}} = 200.26'$$

$$r = 200'$$

# CIVCO Engineering, Inc.

Civil Engineering Consultants  
P.O. Box 1758 • Vernal, Utah 84078

(435) 789-5448 • Fax (435) 789-4485 • email: civco@civcoengineering.com

SHEET NO.: 2 OF 2

DATE 9-12-11

PROJECT NO.: \_\_\_\_\_ LOCATION IWM PROJECTION (Well) BY JSW


3 CAPACITY OF AQUIFER W/O INTERFERENCE W/  
EXISTING WELL


$$A = \pi 1650^2 \\ = 8,552,985 \text{ ft}^2$$

$$Q = KA \\ = 1812 \text{ ft/day} \times 8,552,985 \text{ ft}^2 \times \frac{1561}{428}$$

$$Q = 203,642 \text{ bbl/day} \quad \text{CAPACITY OF AQUIFER}$$

THESE ARE ROUGH CALCULATIONS BUT DEMONSTRATE  
THAT THE IWM WELL WILL HAVE NO  
IMPACT ON THE EXISTING WELL





October 14, 2011

Robert L. Ballou  
Ballou Geologic Consulting  
PO Box 816  
Roosevelt, Utah 84066

Re: Integrated Water Management SWD 3-30 B4 Injection Well  
Section 30, Township 2 South, Range 4 West, Uintah Special Meridian.

Dear Mr. Ballou:

Per your request, Peterson Energy Management, Inc. has reviewed a hydrology report prepared by Granite Environmental, Inc. on September 21, 2011; certain flow calculations prepared by John Wood of CIVCO Engineering dated September 13, 2011; and other relevant information that you supplied us, including well logs on the IWM SWD 3-30 B4 well. In addition we examined El Paso's Christman Bland 1-31 B4 electric log suite and well file as found on the UDOGM web site.

For illustrative purposes, we have constructed a well bore diagram showing both wellbores, which is attached. According to the structure map provided to us, the El Paso producing well is approximately 68 feet up dip from the injection well.

Facts highlighted in our findings:

1. The well bores are 1650 feet apart.
2. The sands being injected into are interbedded with shale stringers, thus confining the injected water into discrete sand lenses.
3. The depositional environment in the area of the two wells in question is lagunal or fluvial in nature and was not conducive to continuous, correlative, or extensive sand body deposition. The resulting lenticular sand lenses are small in aerial extent. The sands in the SWD 3-30 B4 well simply do not extend across the 1650' lateral length to the El Paso Christman Bland 1-31 B4 producing wellbore.
4. Even if some sands were to be continuous and present in both wellbores, according to Granite Environmental Inc.'s model, the energy developed in the injection process in the IMW SWD 3-





30-B4 well would only produce 2 feet of head at the Christman Bland 1-34-B4 producing well. This is insufficient to cause break out in the confining shale layers. Furthermore, this pressure is also insufficient to overcome the hydrostatic head in the annular space of the producing well, i.e. to drive fluids from a depth of 4519' up to the interval above cement top at 2300' in the Christman Bland 1-34 B4.

5. The Christman Bland 1-34 B4 produces from perforations below 10,400'. Regarding the interval of 4519' to 6899' in this well, there is no known hydrocarbon production from this interval in any well within a several miles radius of the producing Christman Bland 1-34 B4 well. Furthermore, a detailed review of mud logs in surrounding wells shows no evidence of any zones in the interval from 4519' to 6899' that could produce commercially. To produce from the uncemented interval in the Christman Bland 1-34 B4, El Paso have to perforate, cement squeeze and re-perforate, all to test an interval that has no evidence of hydrocarbons whatsoever. In our opinion there is no likelihood of this happening.
6. The surface casing in the Christman Bland 1-34 B4 was cemented from the 9 5/8" shoe at 4519' to a cement top of approximately 2300', as confirmed by a temperature log run after the cement job. In 1973 this was an acceptable method of determining top of cement. The maximum temperature at 4519' is estimated to be less than 150° F, based on observed temperatures in surrounding wells. Cement strength degradation is only thought to occur at temperatures above 200° F. As a result the surface casing job pumped in 1973 is, in our opinion, still providing adequate isolation and preventing fluid flow in the annular space of the Christman Bland 1-34 B4 well.

In our opinion, for the above reasons the water injected into the IWS SWD 3-30 B4 well will not reach to and will have no effect upon any interval in the Christman Bland 1-34-B4 well.

Respectfully submitted,

Peterson Energy Management, Inc.

Andy Peterson PE, President

Attachment

**PETERSON ENERGY**  
MANAGEMENT INC.



2154 West Eisenhower Boulevard

Loveland, Colorado 80537

970-669-7411

info@petersonenergy.com

www.petersonenergy.com

October 24, 2011

Mr. Robert Ballou  
Ballou Geologic Consulting  
P.O. Box 816  
Roosevelt, Utah 84066

Re: Testimonials for Peterson Energy Management, Inc.

Dear Mr. Ballou:

Per your request, please find attached testimonials from a selection of our current clients. The word of our clients clearly demonstrates their confidence in Peterson Energy Management and their appreciation for the work we do.

Regards,

Chris Arnold  
Business Development Manager  
Peterson Energy Management, Inc.

Enclosure



**Peterson Energy Management: Client Testimonials**

“Peterson Energy Management has completed every well Sovereign Energy LLC has ever drilled, including all the drilling and completion activities of Colton LLC since Sovereign acquired Colton in 2006. Outsourcing this important component of our business to PEM has freed up our time to concentrate on business development and acquisitions. Sovereign and Colton rely upon PEM as if they were in-house.”

—Thomas S. Metzger, Manager  
Sovereign Energy LLC

“People make all the difference in the world. Peterson Energy has already found the best field supervisors, which means I don't have to spend time looking for quality people or dealing with the consequences of having hired the wrong ones.”

—Tom Rogers, VP-Operations  
Texas American Resources

“We run a tight ship here with a small staff, but I still need to get assistance from contractors. Peterson Energy personnel perform as if they are motivated employees – a quality connection that I intend to keep open.”

—Kevin Brakovec, Drilling Engineer Lead - DJ Basin  
Encana Oil & Gas

“No one wants to deal with excuses or non-motivated people. I really appreciate the positive, can-do attitude of Peterson Energy's wellsite supervisors.”

—David Blandford, Partner  
Matrix Energy, LLC

Peterson Energy Management has played a significant role in the execution of our drilling and completion programs in Colorado, Kansas, Wyoming and soon to be California. I would recommend their services to anyone, as a matter of fact I have already on more than one occasion.

Kevin Kane,  
Operations Manager  
Bayswater Exploration & Production, LLC

**PETERSON ENERGY**  
MANAGEMENT INC.



2154 West Eisenhower Boulevard

Loveland, Colorado 80537

970-669-7411

[info@petersonenergy.com](mailto:info@petersonenergy.com)

[www.petersonenergy.com](http://www.petersonenergy.com)

In the summer of 2010, Slawson Exploration Company, Inc. retained Peterson Energy Management to manage an exploration project in Weld Co., Colorado. Andy Peterson was given responsibility for the entire project, including the drilling and completion of the wells all the way through battery construction and the installation of artificial lift. With only a weekly phone call, we successfully drilled six wells under budget with minimal problems. Peterson communicated well, managed our project in a professional, efficient manner, and allowed us to develop that prospect without any significant drain on our resources. Peterson Energy Management not only met, but exceeded our expectations, and we would heartily recommend them to other Operators with similar needs.

Matt Houston  
Operations Manager  
Slawson Exploration Co., Inc.

## Wellsite Supervision

- Drilling, completing and fracturing
  - Horizontal & Underbalanced
  - High-rate multistage fracturing
- Location construction
- Workover, maintenance and tank battery construction
- Frac flowback and well testing
- Operations management

## Petroleum Engineering

- Well design:
  - Horizontal wells / high rate-high volume fracturing programs / injection and disposal wells
- AFEs, cost estimates and bid preparation
- Well performance optimization
- Drilling, production and reservoir engineering
- Facility design and construction
- Project review and analysis
- Specialized permitting: waterflood, EPA disposal wells and SPCC plans
- DFIT and pressure buildup test analysis
- Directional plan preparation
- Expert witness testimony



## Current Clients: Drilling

- Bayswater Exploration: Weld, CO
- Bill Barrett Corp: Laramie, WY
- Blue Tip Energy Mgmt.: Carbon, UT
- Bonanza Creek: Jackson, CO
- CMO, Inc.: Kern, CA
- Dejour Energy: Rio Blanco, CO
- FIML Natural Resources: Scott, KS
- Genesis ST Operating: Rio Blanco, CO
- Great Plains Resources: Wichita, KS
- Gunnison Energy Corp: Gunnison, CO
- High Sierra Water Services: Weld, CO
- KP Kauffman: Weld, CO
- Recovery: Kimball, NE; Laramie, WY
- Resolute Energy Corp.: Washakie, WY
- Schlumberger Water Svcs: Logan, CO
- Synergy Resources Corp.: Weld, CO
- Weaver Boos: Roosevelt, MT
- Wellstar Corp: Laramie, WY

## Current Clients: Completions

- Bayswater Exploration: Weld, CO
- Black Raven Energy: Morgan, CO
- Bonanza Creek: Jackson & Weld, CO
- Enerplus: Dunn, ND
- Foundation Energy: Weld, CO; Uintah, UT
- High Sierra Water Services: Weld, CO
- Kinder-Morgan: Cheyenne, NE
- KP Kauffman: Weld, CO
- Laramie Energy: Albany WY
- Matrix Energy: Weld, CO
- Mineral Resources, Inc.: Weld, CO
- Recovery: Laramie, WY
- Red Willow Production: Roosevelt, MT
- Schlumberger Water Svcs: Logan, CO
- Slawson Exploration: Weld, CO
- Synergy Resources: Weld, CO
- Wellstar Corp: Campbell, WY
- Whiting Petroleum: Johnson, WY



**IWM SWD 3-30 B4 Chart showing: Perf  
interval, max ROP, Ave ROP and gross feet  
of perfs**


Bed #	Zones of Interest	ROP Max	ROP Ave.	Comments- Tourqe etc.	Gross Feet of Perfs
1	4063-4068	88.6	77		5
2	4103-4118	92.9	67		15
3	4148-4153	62	38		5
4	4176-4182	61	60		6
5	4190-4198	125.9	95		8
6	4268-4278	104	82		10
7	4282-4286	50.4	45		4
8	4308-4323	96.3	76		13
9	4415-4420	56	50		5
10	4466-4481	91.5	75		15
11	4483-4486	111	95		3
12	4492-4500	78	70		8
13	4508-4518	71	40	Drill break was interrupted by rig maint.	10
14	4529-4534	38	35	Not much of a drilling break but went from 11 to 35 fair porosity	5
15	4542-4550	74	65		8
16	4556-4560	90.5	82		4
17	4575-4600	45-50	37	Not much of a drilling break, thinnly laminated sands with interbedded shales, good low res	5
18	4632-4638	62	50		6
19	4642-4646	88	70	Thin but good break and porosity.	4
20	4654-4664	40	38	Not good drilling break but everything else is good.	10
21	4706-4718	102	84		12
22	4778-4784	136	75		6
23	5007-5012	20	15	No break but fair porosity and low res.	5
24	5122-5130	95	80		8
				total # of feet- Will perf with 4" carriers 39 grm shaped charge with pen of 58"	180

43013301980000 Christman-Bland compl

$\approx 1,700'$  S

Casing Schematic

(SSW)



$\approx 3,690' - 5,250'$   
\*needs cmt.



Well name:

**43013301980000 Christman-Bland compl**Operator: **McCollough Oil**String type: **Conductor**

Project ID:

**43-013-30198-0000**Location: **Duchesne County****Design parameters:****Collapse**Mud weight: 8.400 ppg  
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 69 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 185 ft

Cement top: Surface

**Burst**Max anticipated surface pressure: 95 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 131 psi  
  
Annular backup: 2.33 ppg**Tension:**8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)**Non-directional string.**

Tension is based on air weight.

Neutral point: 263 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	13.375	48.00	H-40	ST&C	300	300	12.59	264.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	740	5.653	95	1730	18.23	14	322	22.36 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 810-538-5281

Date: August 25, 2011  
Salt Lake City, Utah**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>43013301980000 Christman-Bland compl</b>		
Operator:	<b>McCollouch Oil</b>	Project ID:	<b>43-013-30198-0000</b>
String type:	<b>Surface</b>		
Location:	<b>Duchesne County</b>		

**Design parameters:**
**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 128 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 185 ft

Cement top: 2,301 ft

**Burst**

Max anticipated surface pressure: 3,977 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 4,519 psi  
  
Annular backup: 2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 3,954 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 10,062 ft  
Next mud weight: 10.800 ppg  
Next setting BHP: 5,645 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 4,519 ft  
Injection pressure: 4,519 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4519	9.625	40.00	K-55	ST&C	4519	4519	8.75	1923.9

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1972	2570	1.303	3977	3950	0.99	181	486	2.69 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 810-538-5281

Date: August 25, 2011  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 4519 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>43013301980000 Christman-Bland compl</b>		
Operator:	<b>McCollouch Oil</b>		
String type:	Production	Project ID:	43-013-30198-0000
Location:	Duchesne County		

**Design parameters:**
**Collapse**

Mud weight: 10.800 ppg  
Internal fluid density: 2.230 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 206 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

**Burst:**

Design factor 1.00

Cement top: 6,899 ft

**Burst**

Max anticipated surface pressure: 3,432 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 5,645 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 8,531 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
2	9000	7	23.00	HCL-80	FL-4S	9000	9000	6.25	1989.3
1	1062	7	26.00	N-80	FL-4S	10062	10062	6.151	228.1

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
2	4007	5568	1.390	5412	6340	1.17	197	349	1.78 J
1	4480	5410	1.208	5645	7240	1.28	-10	474	-45.18 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 810-538-5281

Date: August 25, 2011  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 10062 ft, a mud weight of 10.8 ppg. An internal gradient of .116 psi/ft was used for collapse from TD.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>43013301980000 Christman-Bland compl</b>		
Operator:	<b>McCollouch Oil</b>		
String type:	Production Liner	Project ID:	43-013-30198-0000
Location:	Duchesne County		

**Design parameters:**
**Collapse**

Mud weight: 14.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 239 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 9,384 ft

**Burst**

Max anticipated surface pressure: 6,612 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 9,340 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Liner top: 9,384 ft

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 11,758 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	3000	4.5	13.50	P-110	FL-4S	12400	12400	3.795	251.4

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	9340	10680	1.143	9340	12410	1.33	32	252	7.92 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 810-538-5281

Date: August 25, 2011  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 12400 ft, a mud weight of 14.5 ppg. The Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*



STATE OF UTAH

SUBMIT IN DUPLICATE\*

(See other instructions on reverse side)

OIL &amp; GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

5. LEASE DESIGNATION AND SERIAL NO.

#163.319.002

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Christman-Bland

9. WELL NO.

No. 1-31

10. FIELD AND POOL, OR WILDCAT

Altamont

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

31, T2S, R4W

12. COUNTY OR PARISH  
Duchesne13. STATE  
Utah1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other \_\_\_\_\_

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other \_\_\_\_\_

2. NAME OF OPERATOR

McCulloch Oil Corporation

3. ADDRESS OF OPERATOR

2000 Classen Bldg., Suite 614-E., Oklahoma City, Okla. 73127

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface 1257' FNL &amp; 1552' FEL, Sec. 31, T2S, R4W

At top prod. interval reported below Same

At total depth Same

14. PERMIT NO.

DATE ISSUED

#43-013-30198

15. DATE SPUDDED 2-5-73 16. DATE T.D. REACHED 7-15-73 17. DATE COMPL. (Ready to prod.) August 28, 1973 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\* GL - 6091' 19. ELEV. CASINGHEAD 6091'

20. TOTAL DEPTH, MD &amp; TVD 12,025' 21. PLUG, BACK T.D., MD &amp; TVD 11,950' 22. IF MULTIPLE COMPL., HOW MANY\* 23. INTERVALS DRILLED BY → 24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\* Wasatch 10,409-11,545' 25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN

DIL; CNL; BHC Sonic

27. WAS WELL CORRED

No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
13-3/8"	23 & 26#	300'	17-1/2"	400 sks. Class "H"	None
9-5/8"	36#	4519'	12-1/4"	625 sks. Class "H"	None
7"		10,052'	8-3/4"	465 sks. Class "H"	None

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
4-1/2"	9738'	12,024'	621		2-7/8"	10,350'	10,350'

31. PERFORATION RECORD (Interval, size and number)

10,409-11,545' (58 holes)

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
10,409-11,545'	25,000 gals. 15% HCl

33.\* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)					WELL STATUS (Producing or shut-in)	
August 1, 1973		Flowing					Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO	
9-1-73	24	20/64"	→	466	771	22	1654	
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)		
1000	0	→	466	771	22			

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Vented

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Electric Log

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Stephen D. Owen

TITLE

Steve Owen, Engineer

DATE

9-11-73

\*(See Instructions and Spaces for Additional Data on Reverse Side)

# CHRISTMAN BLANN 1-31B4

Sec 31; 2S; 4W

Average Production:

19 25 BOPD

150 125 BOPD

85 MCFD

Downhole Pump:

Jet

Surface Equipment:

J100 belt drive

Comments:

SWD line to L. Russel 2-32B4

2 7/8" Scab Liner  
9399-10,350'  
Cemented w/45 sx

1.90 Heat String to 1870'

7 5/8" 40 # K-55 @ 4519'

2 7/8" Tubing EUE 8rd N80

Packer: 7" Lokset @ 9254  
(Bottom part of a previous Lokset  
was left @ 9265' Mar '80)

TOL: 4 1/2" @ 9738'

9920' Tight spot in 4 1/2"

7" Shoe: 10,052' 23+26 # 1/-80

Perfs: 10,409-11,545' Aug '73

58 holes

Perfs: 10,805-11,953' May '73

16 holes

PRTD  
IFKH

31-Aug-94

4 1/2" Shoe: 12,024' 13.5 # P-110  
CMT W/621 SX 50/50 132

STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

SUBMIT IN TRIPLICATE\*  
(Other instructions on reverse side)

### SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

<p>1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/></p> <p>2. NAME OF OPERATOR McCulloch Oil Corporation</p> <p>3. ADDRESS OF OPERATOR 140 West 2100 South, Salt Lake City, Utah</p> <p>4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1257' FNL &amp; 1552' FEL, SE NW NE, Sec. 31</p> <p>14. PERMIT NO. 43-013-30198</p>	<p>5. LEASE DESIGNATION AND SERIAL NO. #163.319.002</p> <p>6. IF INDIAN, ALLOTTEE OR TRIBE NAME</p> <p>7. UNIT AGREEMENT NAME</p> <p>8. FARM OR LEASE NAME CHRISTMAN-BLAND</p> <p>9. WELL NO. #1-31</p> <p>10. FIELD AND POOL, OR WILDCAT Altamont</p> <p>11. SEC., T., R., M., OR B.L. AND SURVEY OR AREA Sec. 31, T. 2 S., R. 4 W.</p> <p>12. COUNTY OR PARISH Duchesne</p> <p>13. STATE Utah</p>
<p>15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6091' GL</p>	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON\* ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐

FRACTURE TREATMENT ☐

SHOOTING OR ACIDIZING ☐

(Other) ☐

REPAIRING WELL ☐

ALTERING CASING ☐

ABANDONMENT\* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

#### REPORT FOR THE MONTH OF FEBRUARY, 1973

#### CONFIDENTIAL

Feb. 6: Depth: 230' (230') Spud Well 12:00 p.m. 2/5/73. Repairing swivel. Mud: 8.4, 60, NC.

Feb. 7: Depth: 300' (70') Nippling up. Ran 9 joints H-40, 48# 13 3/8" casing. Set @ 299'. Cemented with 450 sacks Class "G" with 2% CaCl. Cement circulated. 1.2  $\frac{1.3}{5x}$

Feb. 8: Depth: 300' (0') Testing BOP

Feb. 9: Drilling @ 1155' (855') Sand, Shale. Mud: Water

Feb. 10: Drilling @ 1380' (225') Shale, Sand. Mud: Water. Dev. 3/4" @ 1190'.

Feb. 11: Drilling @ 1960' (580') Shale, Sand. Mud: Water

Feb. 12: Fishing @ 2428' (468') Sand, Shale. Mud: Water. Twist drill pipe off one joint above drill collar. Left 18 DC, 1-12 1/4" stabilizer and 1-12 1/4" near bit reamer in hole. Going in hole with overshot.

Feb. 13: Trip @ 2674' (246') Sand, Shale. Mud: Water. GIH with 9 5/8" overshot with 7 7/8" grapple. Recovered Fish.

Feb. 14: Drilling @ 2917' (243') Sand, Shale. Mud: Water.

Feb. 15: Drilling @ 3400' (483') Sand, Shale. Mud: Water

Feb. 16: Drilling @ 3870' (470') Sand, Shale. Mud: Water

Feb. 17: Drilling @ 4430' (560') Sand, Shale. Mud: Water

Feb. 18: Depth: 4560' (130') Sand, Shale. Mud: Water. Ran Multi-shot 300'-4430'. Rig up to run 9 5/8" casing.

Feb. 19: Depth: 4560' (0') Ran 109 joints 9 5/8" casing, 40#, K-55, ST&C. Set @ 4519'

18. I hereby certify that the foregoing is true and correct

SIGNED

*Bob Alef*

TITLE District Manager

DATE MAR 1 1973

(This space for Federal or State office use)

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

SUBMIT IN TRIPLICATE\*  
(Other instructions on reverse side)

### SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input checked="" type="checkbox"/> OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. #163.319.002	
2. NAME OF OPERATOR McCulloch Oil Corporation		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 140 West 2100 South, Salt Lake City, Utah, 84115		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface		8. FARM OR LEASE NAME CHRISTMAN-BLAND	
14. PERMIT NO.		9. WELL NO. #1-31	
15. ELEVATIONS (Show whether DF, RT, OR, etc.)		10. FIELD AND POOL, OR WILDCAT Altamont	
16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA	
17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*		12. COUNTY OR PARISH 13. STATE	

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON\*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT\*

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

#### FEBRUARY REPORT CONTINUED

Feb. 19: Cemented with 500 sacks 50/50 POZ, 8% gel, 1/4# flocele/sack. Followed with 300 sacks Class "G", 1/4# flocele/sack. Plug down @ 7 p.m. 2/18/73. 100% circulation.

Feb. 20: Depth: 4560' (0') Nippling up BOP, ran temperature survey, top of cement @ 2300'.

Feb. 21: Depth: 4560' (0') Nippled up and picking up 6 3/4" drill collars.

Feb. 22: Depth: 4560' (0') Waiting on gas buster and pit repair.

Feb. 23: Depth: 4560' (0') Nippled up gas buster and choke manifold. Installed kill line and repairing accumulator unit.

Feb. 24: Depth: 4560' (0') Preparing to drill out from under 9 5/8" casing.

Feb. 25: Drilling @ 5140' (580') Silt, Sand. Mud: Water

Feb. 26: Drilling @ 5564' (424') Silt, Sand. Mud: Water

Feb. 27: Drilling @ 5955' (391') Sand, Shale. Mud: Water

Feb. 28: Trip @ 6418' (463') Sand, Shale. Mud: Water

18. I hereby certify that the foregoing is true and correct

SIGNED Bob AlexanderTITLE District ManagerDATE MAR 1 1973

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:



STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

SUBMIT IN TRIPLICATE\*  
(Other instructions on reverse side)

### SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

<b>1. OIL WELL</b> <input checked="" type="checkbox"/> <b>GAS WELL</b> <input type="checkbox"/> <b>OTHER</b> <input type="checkbox"/> <b>2. NAME OF OPERATOR</b> McCulloch Oil Corporation <b>3. ADDRESS OF OPERATOR</b> 140 West 2100 South, Salt Lake City, Utah 84115 <b>4. LOCATION OF WELL</b> (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface		<b>5. LEASE DESIGNATION AND SERIAL NO.</b> #163,319,002 <b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME</b>  <b>7. UNIT AGREEMENT NAME</b>  <b>8. FARM OR LEASE NAME</b> CHRISTMAN-BLAND <b>9. WELL NO.</b> #1-31 <b>10. FIELD AND POOL, OR WILDCAT</b>  <b>11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA</b>  <b>12. COUNTY OR PARISH</b> <b>13. STATE</b>
<b>14. PERMIT NO.</b>	<b>15. ELEVATIONS</b> (Show whether DF, RT, OR, etc.)	

**16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data**

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	<input type="checkbox"/>	WATER SHUT-OFF	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	PULL OR ALTER CASING	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	MULTIPLE COMPLETE	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	ABANDON*	<input type="checkbox"/>
(Other)	<input type="checkbox"/>	CHANGE PLANS	<input type="checkbox"/>
	<input type="checkbox"/>		<input type="checkbox"/>
	<input type="checkbox"/>		<input type="checkbox"/>
	<input type="checkbox"/>		<input type="checkbox"/>

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

**17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS** (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

**REPORT FOR MARCH, 1973 - Continued**

March 18: Circulating and conditioning hole to run 7" casing @ 10,062'. Through logging @ 10:00 p.m. 3/17/73. Ran Sonic and DHC. clean up trip to run 7". Background gas 3200, Trip gas 12,000. Mud: 10.8, 68, 5.8.

March 19: Depth: 10,062' (0') Layed down 4 1/2" drill pipe and drill collars. Now running 7" casing. Mud: 10.8, 68, 5.

March 20: WOC @ 10,062'. Ran 236 joints 7", 23#, 26#, N-80. Set @ 10,052'. Cemented with 265 sacks Halco Lite, 1/4# flocele/sack. Followed with 200 sacks Class "G", 1/4# flocele/sack, .3% HR-4. Plug down at 4:24 p.m. 3/19/73. Full returns during job.

March 21: WOC @ 10,062'. Ran Temperature Survey. Found top of cement @ 6900'. Nipple up and test BOP to 5000#. Preparing to pick up 3 1/2" drill pipe.

March 22: Depth: 10,062' (0') Circulating. Build mud volume @ 10,062'. Pick up 4 1/2" drill collars and 3 1/2" drill pipe. Drill cement from 10,007'-10,052'.

March 23: Drilling @ 10,120' (58') Sand, Lime, Shale. Mud: 11.1, 45, 4. Background gas 180, Connection gas 200.

March 24: Drilling @ 10,222' (102') Sand, Shale. Mud: 11.1, 50, 4.8. Background gas 80, Connection gas 100.

March 25: Drilling @ 10,314' (92') Sand, Shale. Mud: 11.0, 45, 4.8. Background gas 80, Connection gas 140.

March 26: Drilling @ 10,396' (82') Shale, Lime. Mud: 11.1, 47, 5.2. Background gas 50, Connection gas 110.

**18. I hereby certify that the foregoing is true and correct**

SIGNED B. G. Alexander TITLE District Manager DATE April 11, 1973

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
 CONDITIONS OF APPROVAL, IF ANY:

STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

SUBMIT IN TRIPLICATE\*  
(Other instructions on reverse side)

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. <input checked="" type="checkbox"/> OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NO. #163.319.002
2. NAME OF OPERATOR McCulloch Oil Corporation		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
3. ADDRESS OF OPERATOR 140 West 2100 South, Salt Lake City, Utah 84115		7. UNIT AGREEMENT NAME
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface		8. FARM OR LEASE NAME CHRISTMAN-BLAND
14. PERMIT NO.		9. WELL NO. #1-31
15. ELEVATIONS (Show whether DF, RT, OR, etc.)		10. FIELD AND POOL, OR WILDCAT Altamont
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA 31, T. 2 S., R. 4 W.
		12. COUNTY OR PARISH Duchesne
		13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

**APRIL, 1973, REPORT CONTINUED**

April 17: Total Depth: 12,025'. Ran 54 joints 4 1/2", 13.5#, P-110, FL4S liner. Set liner @ 12,024'. Top of hanger @ 9738'. Float collar @ 11,978'. Cemented with 621 sacks 50/50 POZ, 1/4# flocele/sack, 1.25% D-8R, mixed with 15.1#/gal. Slurry volume 118 barrels. Good circulation throughout job with back flow when drill pipe was pulled out of liner. Job complete 11:55 p.m. 4/16/73.

April 18: Found top cement @ 7600'. 2138' of cement on top of liner. Drilled 7600'-8752' (1152'). Mud: 14.5, 48, 8.

April 19: Drilled out cement to 9384', top of liner. Tested with 900 psi on top of 14.5# mud for 15 minutes. OK. Layed down drill pipe. Preparing to run Baker Bridge plug.

April 20: Ran bridge plug and set @ 2455'. Rig released 12:00 midnight 4/19/73.

April 21: Moving out Rotary

April 22: Moving out Rotary

April 23: Moving out Rotary

April 24: Rigging up workover rig

April 25: Rigging up workover rig

April 26: Rigged up workover unit, pressure tested BOP stack to 5000 psi. Preparing to pick up tubing.

April 27: Recovered Baker bridge plug @ 2545'. GIH with 3 3/4" bit to top of liner @ 9536'. Shut down for night.

18. I hereby certify that the foregoing is true and correct

SIGNED B. G. Alexander

TITLE District Manager

DATE APR 27 1973

(This space for Federal or State office use)

APPROVED BY \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

43-013-30198

Christman

SUBMIT IN TRIPPLICATE\*

(Other instructions on reverse side)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL & GAS

5. Lease Designation and Serial No.

6. If Indian, Allottee or Tribe Name

7. Unit Agreement Name

8. Farm or Lease Name

CHRISTMAN-BLAND

9. Well No.

#1-31

10. Field and Pool, or Wildcat

Altamont Development

11. Sec., T., R., M., or Blk. and Survey or Area

Sec. 31, T. 2 S., R. 4 W.,

12. County or Parrish 13. State

Duchesne Utah

17. No. of acres assigned to this well  
640

20. Rotary or cable tools

Rotary

22. Approx. date work will start\*

February, 1973

## APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. Type of Well

Oil Well ☒Gas Well ☐

Other

Single Zone ☒Multiple Zone ☐

2. Name of Operator

McCulloch Oil Corporation

3. Address of Operator

140 West 2100 South, Suite 120, Salt Lake City, Utah, 84115

4. Location of Well (Report location clearly and in accordance with any State requirements.)\*

At surface

1257' FNL &amp; 1552' FEL, SE NW NE Section 31

At proposed prod. zone

14. Distance in miles and direction from nearest town or post office\*

15. Distance from proposed\*

location to nearest

property or lease line, ft.

(Also to nearest drig. line, if any)

1257'

16. No. of acres in lease

17. No. of acres assigned to this well

18. Distance from proposed location\* to nearest well, drilling, completed, or applied for, on this lease, ft.

None

19. Proposed depth

12,400'

21. Elevations (Show whether DF, RT, GR, etc.)

6091' GL

23.

## PROPOSED CASING AND CEMENTING PROGRAM

Size of Hole (4 3/4")	Size of Casing	Weight per Foot	Setting Depth	Quantity of Cement
17 1/2" 1.67033	13 3/8"	48#	300'	375 cu ft
12 1/4" 0.81846	9 5/8"	40#	5000'	785 cu ft
8 3/4" 0.41758	7"	26#	10,000'	450 cu ft
6 1/8" 0.20461	4 1/2"	13.5#	12,400'	255 cu ft

1. Well to be drilled and casing cemented as proposed above

2. Mud Program

0'-8100'± Water

8100'-12,400' 8.3 to 15#/gal. as necessary to control hole.

3. Blowout Preventer Program

a. 13 3/8" casing - 12" - 3000 psi Hydril

b. 9 5/8" casing - 10" - 5000 psi Single Gate

10" - 5000 psi Double Gate

10" - 5000 psi Hydril

c. 7" casing - same as 9 5/8" casing.

4. Blowout Control Equipment

a. Degasser

b. 5000 psi Choke Manifold with Gas Buster

(over)

PLEASE HOLD INFORMATION  
CONFIDENTIAL

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

Signed W. W. LuptonTitle District ManagerDate 1/23/73

(This space for Federal or State office use)

Permit No. 43-013-30198

Approval Date

Approved by


Conditions of approval, if any:

Title

Date

04-06 El Paso Katherine 3-29B4comp  
Casing Schematic

≈ 2,000' E.  
(ENE)



Well name:	<b>04-06 El Paso Katherine 3-29B4comp</b>		
Operator:	<b>El Paso Production</b>		
String type:	Production	Project ID:	43-013-32923
Location:	Duchesne County		

**Design parameters:**
**Collapse**

Mud weight: 8.900 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 209 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 7,324 ft

**Burst**

Max anticipated surface pressure: 5,399 psi  
Internal gradient: -0.061 psi/ft  
Calculated BHP 4,768 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on air weight.

Neutral point: 8,924 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	10313	7	29.00	P-110	LT&C	10313	10313	6.059	2151.1

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4768	8530	1.789	5399	11220	2.08	299	797	2.66 J

Prepared by: Clinton Dworshak  
Div of Oil, Gas & Mining

Phone: 801-538-5280

Date: August 25, 2011  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 10313 ft, a mud weight of 8.9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>04-06 El Paso Katherine 3-29B4comp</b>	
Operator:	<b>El Paso Production</b>	
String type:	Production Liner	Project ID: 43-013-32923
Location:	Duchesne County	

**Design parameters:**
**Collapse**

Mud weight: 13.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 250 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,500 ft

Cement top: 10,017 ft

Liner top: 10,017 ft

**Non-directional string.**
**Burst**

Max anticipated surface pressure: 7,701 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 9,291 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.

Neutral point: 12,581 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	3248	5	18.00	HCP-110	LT&C	13248	13248	4.151	323.9

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	9291	13470	1.450	9291	13940	1.50	58	495	8.47 J

Prepared by: Clinton Dworshak  
Div of Oil, Gas & Mining

Phone: 801-538-5280

Date: August 25, 2011  
Salt Lake City, Utah

**Remarks:**

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 13248 ft, a mud weight of 13.5 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

43-013-32923

Katherine

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

<b>1a. TYPE OF WELL:</b> OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____  <b>b. TYPE OF WORK:</b> NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____						<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> <b>Fee</b>			
<b>2. NAME OF OPERATOR:</b> El Paso E&P Company, LP						<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME</b> N/A			
<b>3. ADDRESS OF OPERATOR:</b> 1099 18th St, Ste 1900 CITY Denver STATE CO ZIP 80202				<b>PHONE NUMBER:</b> (303) 291-6400		<b>7. UNIT or CA AGREEMENT NAME</b> N/A			
<b>4. LOCATION OF WELL (FOOTAGES)</b> AT SURFACE: 670' FSL, 1217' FWL  AT TOP PRODUCING INTERVAL REPORTED BELOW: same  AT TOTAL DEPTH: same						<b>8. WELL NAME and NUMBER:</b> Katherine 3-29B4			
<b>14. DATE SPUDDED:</b> 4/19/2006						<b>9. API NUMBER:</b> 4301332923			
<b>15. DATE T.D. REACHED:</b> 7/2/2006						<b>10. FIELD AND POOL, OR WILDCAT</b> Altamont			
<b>16. DATE COMPLETED:</b> 11/13/2006						<b>11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> SWSW 29 2S 4W			
ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>						<b>12. COUNTY</b> Duchesne			
<b>17. ELEVATIONS (DF, RKB, RT, GL):</b> 6181.6' GL						<b>13. STATE</b> UTAH			
<b>18. TOTAL DEPTH:</b> MD 13,260 TVD 13,260		<b>19. PLUG BACK T.D.:</b> MD TVD		<b>20. IF MULTIPLE COMPLETIONS, HOW MANY? *</b>		<b>21. DEPTH BRIDGE MD PLUG SET:</b> MD TVD			
<b>22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)</b> CBL, COMP ZDL/NEUTRON/GR/CAL, HDIL/GR/CAL						<b>23.</b> WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)			
<b>24. CASING AND LINER RECORD (Report all strings set in well)</b>									
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12 1/4"	9 5/8 N80	40	0	6,510		HiFill 875	495	Surface	N/A
8 3/4"	7" P110	29	0	10,313		HiFill 290	140	8350 Cal	N/A
7"	5" P110	18	10,017	13,248		Cemnet	106	11200 Cal	N/A
<b>25. TUBING RECORD</b>									
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	
2 7/8"	7,625								
<b>26. PRODUCING INTERVALS</b>					<b>27. PERFORATION RECORD</b>				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) WASATCH	10,238	12,901	10,238	12,901	12,412 12,901	3 1/8"	165	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B)					11,970 12,335	3 1/8"	195	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)					11,389 11,921	3 1/8"	315	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
<b>28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.</b>									
DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL								
12412 - 12901	73,070 lbs 20/40 Carboprop; 5000 gal 15% HCL								
11970 - 12335	70,640 lbs 20/40 Carboprop; 4000 gal 15% HCL								
11389 - 11921	140,000 lbs 20/40 Carboprop; 5000 gal 15% HCL								
<b>29. ENCLOSED ATTACHMENTS:</b> <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION								<b>30. WELL STATUS:</b> Producing	
<input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> CORE ANALYSIS								<input type="checkbox"/> DST REPORT <input type="checkbox"/> OTHER: _____	

(CONTINUED ON BACK)

RECEIVED

FEB 08 2007

DIV OF OIL GAS &amp; MINING



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
2. NAME OF OPERATOR: EL PASO PRODUCTION OIL AND GAS COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1339 EL SEGUNDO NE ALBUQUERQUE NM 87113		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 670' FSL, 1217' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 29 2S 4W		8. WELL NAME and NUMBER: KATHERINE 3-29B4 9. API NUMBER: 4301332923 10. FIELD AND POOL, OR WILDCAT: ALTAMONT/BLUEBELL
		COUNTY: DUCHESNE STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 6/15/2006	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <u>PRODUCTION CSG</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

CONTINUE DRILLING F/ 6510' - 10,303'. RUN 7" 29# LT&C CSG TO 10,303'. M&P 155 SX 50/50 POZ+, 11.0 PPG, 3.81 YIELD LEAD. TAIL W/ 135 SX 13.5 PPG, 1.46 YIELD. FLOATS HELD. RD HALLIBURTON.

NAME (PLEASE PRINT) <u>CHERYL CAMERON</u>	TITLE <u>REGULATORY ANALYST</u>
SIGNATURE <u><i>Cheryl Cameron</i></u>	DATE <u>6/20/2006</u>

(This space for State use only)

RECEIVED  
JUN 22 2006





STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

FEE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

KATHERINE 3-29B4

9. API NUMBER:

4301332923

10. FIELD AND POOL, OR WILDCAT:

ALTAMONT/BLUEBELL

1. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

EL PASO PRODUCTION OIL AND GAS COMPANY

3. ADDRESS OF OPERATOR:

1330 EL SEGUNDO NE

CITY

ALBUQUERQUE

STATE

NM

ZIP

87113

PHONE NUMBER:

(505) 344-9380

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 670' FSL, 1217' FWL

COUNTY: DUCHESNE

QTR/QR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 29 2S 4W

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION



NOTICE OF INTENT  
(Submit in Duplicate)

Approximate date work will start:



SUBSEQUENT REPORT  
(Submit Original Form Only)

Date of work completion:

4/27/2006



ACIDIZE



ALTER CASING



CASING REPAIR



CHANGE TO PREVIOUS PLANS



CHANGE TUBING



CHANGE WELL NAME



CHANGE WELL STATUS



COMINGLE PRODUCING FORMATIONS



CONVERT WELL TYPE



DEEPEN



FRACTURE TREAT



NEW CONSTRUCTION



OPERATOR CHANGE



PLUG AND ABANDON



PLUG BACK



PRODUCTION (START/RESUME)



RECLAMATION OF WELL SITE



RECOMPLETE - DIFFERENT FORMATION



REPERFORATE CURRENT FORMATION



SIDETRACK TO REPAIR WELL



TEMPORARILY ABANDON



TUBING REPAIR



VENT OR FLARE



WATER DISPOSAL



WATER SHUT-OFF



OTHER: SURF CSG

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

DRILLED 17 1/2" HOLE 282' DEEP. SET 13 3/8" W/ GUIDE SHOE, 3 CENTRALIZERS, AND BAFFLE PLATE, SET @ 224'. CMT W/ 350 SX GLASS G 2% CACL W/ 1/4#/SK FLOCELE, 1.15 YIELD, 15.8 PPG, 4.97 WTR. 31 BC TO SURF.

NAME (PLEASE PRINT) CHERYL CAMERON

TITLE REGULATORY ANALYST

SIGNATURE

*Cheryl Cameron*

DATE

4/28/2006

(This space for State use only)

RECEIVED

MAY 04 2006

# El Paso Production Company

## Katherine 3-29B4

API #: 4301332923  
Sec. 16, T2S – R3W  
Altamont Bluebell Field  
Duchesne County, Utah

### Procedure:

1. MIRU WO rig. Pump heated 2% KCl water as needed to help unseat pump. Unseat pump and POOH with rods and pump.
2. ND wellhead, NU BOP. Release 7" TAC @ 7,296' and TOH with tubing and BHA.
3. PU and TIH with 6" bit and 7" casing scraper to top of liner @ 10,017'. TOOH w/ bit and scraper.
4. PU and TIH with 4-1/8" bit and 5" casing scraper to 11,410'. TOOH w/ bit and scraper.
5. RU wireline unit and RIH with CBP and set @ 11,384'. POOH. Dump bail 10' of cement on CBP. POOH.
6. Pressure test casing to 4,000 psi for 30 minutes. If the casing does not test, consider isolating a possible leak with a bridge plug and packer and performing remedial action.
7. RU wireline with 5k lubricator and test to 5,000 psi with water. RIH and shoot squeeze holes at 11,130' with 3-1/8" HSC, 22.7 gm charges, 3 jspf and 120° phasing. All perforations are to be correlated to the High Definition Induction Log/ Compensated Z-Densilog/ Compensated Neutron Log dated July 5, 2006. POOH.
8. RIH with CICR and set @ 11,080'. POOH and RD wireline.
9. TIH with +/- 1,200' of 2-3/8", 4.7#/ft N-80 tubing followed by 2-7/8", 6.5 #/ft N-80 tubing (TOL @ 10,017') and sting into CICR. Pressure test annulus to 1,000 psi. Establish injection rate and pressure into squeeze holes with 2% KCl water.
10. RU cementers. Mix and pump 75 sks Low Fluid Loss Class G cement at 15.6 ppg followed by 25 sks Class G cement w/ retarder as needed at 16.0 ppg. (Cement designs based on 225°F @ 11,130'.) Sting out of CICR. Pull 2 jts of tubing and reverse tubing clean. TOOH.
11. RU WL unit and run CBL/VDL/GR/CCL log from CICR to top of 5" liner. Consult with Denver office on cement coverage. Correlate log to High Definition Induction Log/ Compensated Z-Densilog/ Compensated Neutron Log dated July 5, 2006. If cement coverage is adequate then proceed to



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒  
(highlight changes)

APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: FEE	6. SURFACE: Fee
B. TYPE OF WELL: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
2. NAME OF OPERATOR: EL PASO PRODUCTION OIL AND GAS COMPANY		8. UNIT or CA AGREEMENT NAME:	
3. ADDRESS OF OPERATOR: 1339 EL SEGUNDO NE ALBUQUERQUI NM 87113		PHONE NUMBER: (505) 344-9380	9. WELL NAME and NUMBER: KATHERINE 3-29B4
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 670' FSL, 1217' FWL AT PROPOSED PRODUCING ZONE:		10. FIELD AND POOL, OR WILDCAT: ALTAMONT/BLUEBELL	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 9.1 MILES NORTHEAST OF DUCHESNE, UT		12. COUNTY: DUCHESNE	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 670'	16. NUMBER OF ACRES IN LEASE: 640	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 640	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 3200'	19. PROPOSED DEPTH: 13,250	20. BOND DESCRIPTION: 400JU0705	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6181.6' GR	22. APPROXIMATE DATE WORK WILL START: 3/30/2006	23. ESTIMATED DURATION: 60 DAYS	

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
17 1/2	13 3/8 J-55 54.5#	250	50/50 POZ 120 SX 1.98 12.5
12 1/4	9 5/8 N-80 40#	6,500	50/50 POZ 950 SX 1.98 12.5 LEAD
			PREM + 260 SX 1.22 14.35 TAIL
			950 SX 1.98 12.50 TAIL
8 3/4	7 HCP-110 29#	10,300	50/50 POZ 440 SX 1.46 13.50 LEAD
6 1/8	5 HCP-110 18#	13,250	PREM + 160 SX 1.56 15.60

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN                                   |
| <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER        | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) CHERYL CAMERON

TITLE REGULATORY ANALYST

SIGNATURE

*Cheryl Cameron*

DATE 4/3/2006

(This space for State use only)

API NUMBER ASSIGNED:

43-013-32423

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date:

By:

*[Signature]*  
(See Instructions on Reverse Side)


RECEIVED

APR 04 2006

DIV. OF OIL, GAS & MINING

# Drilling Prognosis

COMPANY NAME	El Paso Production	DATE	September 30, 2005
WELL NAME	Katherine #3-29B4	TD	13,250' MD/TVD
FIELD	Altamont - Bluebell 270 8217	COUNTY	Duchesne STATE Utah
SURFACE LOCATION	553' FSL, 1,535' FWL, SE/SW, SEC. 29, T2S, R4W	Elev.	6,183'
OBJECTIVE ZONE(S)	Green River, Wasatch	BHL	Straight Hole
BOPE INFO	13-5/8" 5M double BOP stack and 5M kill lines and choke manifold 1,000' - 10,300'. A 7-1/16" 10M triple stack from 10,300' - TD		



**DRILLING PROGRAM****CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
SURFACE	13-3/8	0-1000'	54.50	J-55	BTC	2,730	1,130	853,000
						5.36	2.41	5.52
INTERMEDIATE	9-5/8"	0 - 6,500'	40.00	N-80	LTC	5,750	3,090	737,000
						1.58	1.02	2.05
PRODUCTION	7"	0 - 10,300'	29.00	HCP-110	LTC	11,320	9,200	797,000
						2.05	1.72	2.00
PRODUCTION LINER	5"	10,000' - 13,250'	18	HCP-110	Vam FJL	13,940	13,470	353,000
						1.97	1.50	2.31

CEMENT PROGRAM		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE							
	Lead	800	50/50 Poz Premium + 10% Cal-Seal + 25 pps Floccle	582	100%	12.50	1.98
	Tail	200	Premium + 2% Calcium Chloride + 25 pps Floccle	273	100%	15.80	1.17
INTERMEDIATE							
	Lead	3,000	CBM Light	287	25%	10.50	4.10
	Tail	500	50/50 Poz + 0.6% Halaq-322 + 5 pps Gilsontite + 5% Salt + 1 pps Granulite	178	25%	14.35	1.22
PRODUCTION							
	Lead	7000-10300	50/50 Poz + 0.25 lb/sk Floccle + 5 pps Silicate	440	25%	13.50	1.48
	Fill	3,300	+ 0.1% HR-12 + 2% CFR-3				
PRODUCTION LINER							
	Fill	10300-13250	Premium + .5% Halaq-344 + 35% SSA-1	160	15%	15.60	1.56
	Fill	2,950	+ 0.4% CFR-3 + 4% HR-12				
	Liner Lap	100					

**FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Float shoe, 1 joint, float collar. Centralize 5' above shoe & 5 centralizers every third collar. Thread lock FE & bottom joint
INTERMEDIATE	Float shoe, 1 joint, float collar. Centralize every 4th joint to 3000'. Thread lock all FE
PRODUCTION	Float shoe, 1 joint, float collar. Centralize every 4th joint to 8000'. Thread lock all FE
LINER	Float shoe, 1 joint, float collar. Centralize every 4th joint to top of pay. Thread lock all FE

PROJECT ENGINEER: Buddy Novak

DRILLING MANAGER: Scott Palmer

## Wellbore Diagram

API Well No: 43-013-32923-00-00 Permit No:

Well Name/No: KATHERINE 3-29B4

Company Name: EL PASO E&amp;P COMPANY, LP

Location: Sec: 29 T: 2S R: 4W Spot: SWSW

Coordinates: X: 554015 Y: 4458064

Field Name: ALTAMONT

County Name: DUCHESNE

## String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)
HOL1	6510	12.25		
SURF	6510	9.625	40	6510
HOL2	10303	8.75		
II	10303	7	29	10313
HOL3	13260	7		
PROD	13248	5	18	13248
T1	7625	2.875		

## Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
II	10303	8350	PC	155
II	10303	8350	G	135
PROD	13248	10017	G	100
SURF	6510	0	UK	875

## Perforation Information

Top (ft sub)	Bottom (ft sub)	Shts/Ft	No Shts	Dt Squeeze
10985	12901			

## Formation Information

Formation Depth

Cement from 6510 ft. to surface

Surface: 9.625 in. @ 6510 ft.

Hole: 12.25 in. @ 6510 ft.

Cement from 10303 ft. to 8350 ft.

Intermediate: 7 in. @ 10303 ft.

Hole: 8.75 in. @ 10303 ft.

Cement from 13248 ft. to 10017 ft.

Tubing: 2.875 in. @ 7625 ft.

Production: 5 in. @ 13248 ft.

Hole: Unknown

Hole: 7 in. @ 13260 ft.

TD: 13260 TVD: 13260 PBD:





Search all of Utah.gov »




## Utah Division of Water Rights

## Output Listing

Version: 2009.05.06.00 Rundate: 08/31/2011 01:44 PM

Radius search of 2640 feet from a point N300 W800 from the SE corner, section 30, Township 2S, Range 4W, US  
 b&m Criteria: wrtypes=W,C,E podtypes=S,U,D,Sp,P,R,T status=U,A,P usetypes=all



0 350 700 1050 1400 ft

## Water Rights

WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
-----------	-------------------------	----------	--------	----------	------	-----	------	------------



<del>44</del> -11994	Underground		A	20070906 DIS	0.000 1.730	TYRELL G. AND MARIAH J. FARNSWORTH  P.O. BOX 143
	S250 E400 W4 29 2S 4W US					
43-12186	Underground	<a href="#">well info</a>	A	20090120 M	0.000 0.730	DUCHESNE/WASATCH BLUEBENCH LANDFILL  SPECIAL SERVICE DISTRICT
	S1382 W1262 NE 31 2S 4W US					
43-2422	Underground		P	19701013 S	0.015 0.000	CITY DEVELOPMENT INC.  90 SOUTH 400 WEST, SUITE 360
	N174 W864 SE 30 2S 4W US					
43-9896	Underground	<a href="#">well info</a>	P	19970710 DO	0.000 0.500	DUCHESNE COUNTY BLUE BENCH LANDFILL  C/O MANAGER
	S1503 E773 NW 32 2S 4W US					



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 1

**APPLICATION FOR INJECTION WELL**

Name of Operator Integrated Water Management			Utah Account Number N	Well Name and Number Gertiz-Murphy 1-6 C4
Address of Operator PO Box 430      CITY Altamont      STATE UT      ZIP 84001			Phone Number (435) 454-4646	API Number 4301330573
Location of Well Footage : 1976' FNL 1778' FEL      County : Duchesne				Field or Unit Name
QQ, Section, Township, Range: SWNE 6 3S 4W      State : UTAH				Lease Designation and Number

Is this application for expansion of an existing project?      Yes ☒      No ☐

Will the proposed well be used for:	Enhanced Recovery?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
	Disposal?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Storage?	Yes <input type="checkbox"/>	No <input type="checkbox"/>

Is this application for a new well to be drilled?      Yes ☐      No ☒

If this application is for an existing well, has a casing test been performed?      Yes ☐      No ☒  
Date of test: \_\_\_\_\_

Proposed injection interval:      from 4,000      to 7,000

Proposed maximum injection:      rate 6,000      bpd      pressure 800      psig

Proposed injection zone contains oil ☐, gas ☐, and / or fresh water ☐ within ½ mile of the well.

List of attachments: Attachments prepared with body of application included. Following the conversion the new name of the well will be IWM SWD 2-6 C4

**ATTACH ADDITIONAL INFORMATION AS REQUIRED BY CURRENT  
UTAH OIL AND GAS CONSERVATION GENERAL RULES**

I hereby certify that this report is true and complete to the best of my knowledge.

Name (Please Print) Robert L. Ballou

Title Geologist/Agent

Signature \_\_\_\_\_

Date 1/19/2012

**RECEIVED**

**JAN 23 2012**

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING  
WATER DISPOSAL,  
STORAGE AND ENHANCED RECOVERY WELLS  
SECTION V - RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**

Integrated Water Management, a Utah Corporation is the operator of an existing SWD facility located 8 miles north and 1 mile east of Duchesne, Utah. IWM is bonded by the DOGM to conduct operations in its existing evaporation pits and SWD well associated with its SWD operations. This application is submitted as support for IWM to convert a previous producing well that is currently plugged and abandoned located approximately 1.5 miles south of IWM's current operations. This SWD well to be incorporated in conjunction with current operations. Applicant proposes to gravity feed filtered water to the proposed location (Geritz-Murphy 1-6 C4) and to dispose of such produced water by injection underground into the Uintah/Upper Green River formations underlying the proposed disposal well.

Applicant proposes to convert the 1-6 C4 API # 43-013-30573 into a SWD well to be designated the **IWM SWD 2-6 C4**, located 1976 feet from the north line and 1978 feet from the east line of section 6, 3S, 4W, Duchesne, County, Utah. Location of the proposed conversion site is shown in **Exhibit B** Note: **Exhibit A** details the surface owners within a 1/2 mile radius of the proposed well conversion location. As shown on **Exhibit B**, there are no other wells drilled within a 1/2 mile of the proposed location

- 2. The application for an injection well shall Include a properly completed Form DOGM-UIC-1 and the following:**
  - 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Exhibits A and B.
  - 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

A full suite of logs have been run on this well including a Triple combination (Electric log, Density/Neutron). All logs are currently on file with DOGM.
  - 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A cement bond log (CBL) is on file with DOGM.

**2.4 Copies of logs already on file with the Division should be referenced, but need not be re-filed.**

All copies of logs in area of review are on file with the Utah Division of Oil, Gas and Mining.

**2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The current well bore schematic (from the DOGM well file), is provided as **Exhibit C**. The original casing in the well is detailed on the original completion report included as **Exhibit D**. It details the condition of the wellbore following P&A procedures. Note: during P&A procedures the 7" intermediate casing was cut off @ 1552' and removed. A detailed procedure for reestablishing Mechanical Integrity of the casing string, perforation intervals and down hole operations are detailed in **Exhibit E**. Proposed casing program is to replace previously removed 7" casing by running new 7" casing. Note: 9 5/8" casing is set at 1502' and cemented to surface. Original 7" casing was set to 9900' and cemented with 850 sks of cement. CBL shows a cement top of 5920'.

**2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be Injected daily.**

The primary type and source of fluid to be used for injection will be production water that has been conditioned, filtered and gravity fed from IWM's disposal facility. The estimated average rate of injection will be 3000 BPD, and the estimated maximum rate of injection will be 6000 BPD.

**2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

Production water analysis will vary depending on the company and associated location that the production is coming from. Included are representative analysis of produced water from 3 IWM costumer wells . See **Exhibit F-1, F2,F3**.

Included are water analysis reports from four SWD wells in the immediate vicinity, (two drilled as SWD wells and not as recompletions from a producing oil and gas well, to a SWD well and one the well in section 36 as a conversion of a previous production well). These wells are;

To the north and west of the proposed IWM SWD 2-6C4, The **LDS Church 2-27 B5). Exhibit G1-A,G1-B**

To the north and east of the proposed IWM SWD 2-6 C4, The **Russell SWD 2-32B4. Exhibit G2-A,G2-B**

To the north and west of the proposed IWM SWD 2- C4, The **Rhodes Moon 1-36 B5. Exhibit G3**

To the south and west of the proposed IWM SWD 2-6C5, **The Blue Bench 1-13 C5, Exhibit G-4**

These water analysis reports are from actual swab tests of specific intervals and show that formation water from produced water and in the proposed injection interval, as noted, the Duchesne River-Uintah/Tgr formations because of their measured TDS amounts, are unfit for domestic livestock, irrigation or other general uses.

It is proposed that in the IWM SWD 2-6 C4, IWM will take a representative sample of formation water by production swab over an interval to be selected and approved by DOGM. IWM will notify the DOGM prior to taking such samples and conducting such tests in order that the DOGM may witness the tests and take independent samples if desired. Results will be forwarded to DOGM.

**2.8 The proposed average and maximum injection pressures.**

Judging from the data collected from the similar wells in the immediate area The proposed average injection pressure will be approximately 500 psig and the maximum injection pressure will not exceed 800 psig.

**2.9 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining Interval that could enable the injected fluid or formation fluid to enter the fresh water strata.**

The minimum fracture gradient for the IWM SWD 2-6 C4 calculates at 0.733 psig/ft. However a gradient step rate test will be run on the well to determine the maximum injection pressure. Historically this has not been an issue in the SWD wells located within a township of the IWM SWD 2-6 C4 as they all have operated at pressures of less than 800#, some much less.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief

**2.10 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.**

**Listed below are several wells listed that because of their close proximity to the subject well are listed as corollaries to the proposed IWM SWD 2-6C4.**

**In the Russell SWDW 2-32B4** the gross injection zones are 2464'-3726', (2464'-2470', 2548'-2558', 2630'-2638', 2884'-2890', 3054'-3062', 3720'-3726', two holes per foot). Records from 1/86 to 9/10 show that this well disposed of 6,836,018 BW with a maximum tubing pressure of 830 # and an average tubing pressure of about 600#. Note: this figure does not include the unreported water that was put away from 1975-1986.

**In the LDS 2-27 B5** the gross injection zones are (2088'-2860', 2088'-2098', 2129'-2136', 2312'-2317', 2370'-2374', 2377'-2383', 2407'-2413', 2416'-2419', 2515'-2522', 2559'-2561', 2817'-2819', 2840'-2860' one hole per foot); Records from 1/86 to 9/10 show that this well disposed of 33,654,635 BW with a maximum tubing pressure of 550 #. Note: this figure does not include the unreported water that was put away from 1975-1986. All perforations in the Duchesne River-Uintah formations.

**In the Blue Bench 1-13 C5** the gross injection zones listed in the current well file from DOGM are: 4106'-4121', 4832'-4847', 5268'-5283', 6085'-6090', 7231'-7257', 7467'-7528'. The well is currently a commercial SWD facility operated by Pro Water Inc. Current records show that over the last recorded 12 month interval the daily production has averaged about 6700 bbls a day.

**Note: The closest offset SWD to the proposed IWM SWD 2-6 C5 is the Rhodes 1-36 B5 a converted SWD well.**

**In the Rhodes 1-36 B5** the gross injection zone intervals are: 4114' to 5055' the operators original plan was to perforate from 5070'-4583' (phase I) and if needed phase II would be from 4452'-4052' with the injection packer set 4520' for phase I. Records show that both phase I and phase II were perf'd and injected into. All perforations in the lower Uinta Fm/ upper Tgr.

**The reservoirs that all of the injection wells are injecting in is composed primarily of clastic fluviatile, lacustrine, and transitional sediments and is composed of sandstones, siltstones and shales. Carbonates are also encountered increasing with depth with numerous sandstones containing waters of varying degrees of salinity, porosity and permeability.**

**Other close by wells that appear to be of a similar nature to the proposed IWM SWD 2-6 C4 include: the Tew 1-9 B5 a converted SWD well with a perforation interval of 3700-5800' and 5900-6400'. Also the Erich 2-11 B5 that has injected into 4 injection intervals: 3749-3985', 4027-4496, 4576-5573', 5607-5810'.**

- 2.11 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter improper intervals.**

There are no wells drilled within the 1/2 mile radius of the proposed IWM SWD 2-6 C4.

- 2.12 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.**


**See Exhibit I.**

**List, Exhibit H.**

**2.13 Any other Information that the Board or Division may determine is necessary to adequately review the application.**

The proposed injection zone is in the - Uintah Formation, upper Tgr fm. The IWM SWD 2-6 C4 well was patterned after the 1-36 B5 in closest in proximity to the IWM SWD 2-6 C4. The proposed injection zone will be determined by examination of the current well logs in the 1-6 C4 but if consistent with other nearby SWD wells (1-36 B5 as noted but also the Blue Bench 1-13 C5, the gross interval zones will be from 4000' to 7000'. The confining stratum directly above the injection zone is the Duchesne River formation and below the injection zones is the Green River Formation.

Integrated Water Management will supply any additional information requested by the Utah Division of Oil, Gas and Mining.



## Integrated Water Management


IWM SWD 2-6C4

Section 6 3S 4W

Surface Owners within 1/2 Mile Radius

Exhibit A





**Integrated Water Management  
IWM SWD 2-6 C4  
Section 6 3S 4W  
Location: 1976' FNL, 1978' FEL  
Exhibit B**

## **IWM**

### **Conversion Procedure      EXHIBIT E**

**Gertiz-Murphy 1-6 C4 to be converted to IWM SWD 2-6 C4**

**SW NE Sec. 6, T3S-R4W**

**Duchesne, Co., Utah**

**API number 43-013-30573**

**KB 6034' GL 6011' TD: 11,900' (6/81) Original well Drilled by Gulf Oil**

**PBTD:                      8250' CIBP (7/95)**

**Surface Casing:        9 5/8" @1502'**

**Intermediate csg:     7" 26/29# N-80 set @ 9900'**

- 
1. Weld on new wellhead on 9 5/8" in preparation to set BOP.
  2. MIRU work over rig.
  3. NU BOP.
  4. Prepare to drill out first cement plug, top of cement at 1255'.
  5. Drill to 1500' (bottom of 9 5/8" casing). Add stabilizers in preparation of drilling additional 23' to 7" casing stub.
  6. Locate 7" casing stub, wash over and mill to top dress.
  7. Run casing patch, test casing patch; if OK run remainder of casing to surface.
  8. Pressure test with rig pump.
  9. Drill remainder of cement plug in 7", estimated to be to 1620' (total thickness of cement 365').
  10. Drill cement plug out from 3181 to 3398 in 7". Pressure test with rig pump.
  11. Clean out hole in preparation to squeeze cement behind 7". Note: CBL shows cement top at approximately 5920'.

12. TIH and perforate 7" casing in preparation to sqz at 5900'
13. Test and establish an injection rate with rig pump; looking for rates of 3-4 bbl a minute.
14. If OK Set cement retainer just above uppermost perms.
15. TIH and sqz with 400 sks, 30% excess to a height of about 3500'
16. Allow cement to cure and run CBL to confirm overall cement job and determine cement top.
17. If cement job is adequate and cement top is as planned perforate selected intervals from 4000' to 7000'.
18. TIH with 3 1/2" tubing and set Arrow set pkr, 50' above top perms.
19. Rig to swab and swab representative water sample.
20. TOH remove BOP and prepare well for injection.

STATE OF UTAH  
DIVISION OF OIL GAS AND MINING

## PLUGGING OPERATIONS

Well Name: GERITZ MURPHY 1-6C4 API Number: 43-013-30573  
 Qtr/Qtr: SW/NE Section: 6 Township: 3S Range: 4W  
 Company Name: BARRETT RESOURCES  
 Lease: State \_\_\_\_\_ Fee YES Federal \_\_\_\_\_ Indian \_\_\_\_\_  
 Inspector: DENNIS L. INGRAM Date: 6/22/99

Casing Tested: YES X NO \_\_\_\_\_ Results: 1000 PSI F/15 MINUTES--OK!  
 Cementing Company: BASIN CONCRETE

Draw a wellbore diagram as plugged:

COMMENTS: SET RETAINER WITH 260 JOINTS  
TUBING. INJECTION RATE WAS 1.67 BPM @ 400  
PSI. TUBING TAIL FOR SALINE PLUG WAS 3398'.  
CASING STUB WAS 1525'. TAGGED SHOE PLUG  
WITH TUBING AND TAG SHOE. LEFT TOP PLUG OUT  
AT LANDOWNER REQUEST FOR WATER WELL--  
SEE DIAGRAM




Exhibit C

- Exhibit D

7

SUBMIT IN DUPLICATE\*

(See other instructions on reverse side)

STATE OF UTAH  
OIL & GAS CONSERVATION COMMISSION

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG \*

5. LEASE DESIGNATION AND SERIAL NO.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Geritz Murphy

9. WELL NO.

1-6-C4

10. FIELD AND POOL, OR WILDCAT

Wasatch  
Altamont Field

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec. 6-3S-4W

12. COUNTY OR  
PARISH  
Duchesne13. STATE  
Utah

1a. TYPE OF WELL:

OIL

WELL

☒

GAS

WELL

☐

DRY

☐

Other

b. TYPE OF COMPLETION:

NEW

WELL

☒

WORK

OVER

☐

DEEP-

EN

☐

PLUG

BACK

☐

DIFF.

RESVR.

☐

Other

2. NAME OF OPERATOR

Gulf Oil Corporation

3. ADDRESS OF OPERATOR

P.O. Box 2619, Casper, WY 82602-2619

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)\*

At surface 1976' FNL &amp; 1978' FEL, Sec. 6-3S-4W, SW/4, NE/4

At top prod. interval reported below Same

At total depth Same

14. PERMIT NO.

43-013-30573

DATE ISSUED

5-8-81

15. DATE SPUDDED

5-1-81

16. DATE T.D. REACHED

6-12-81

17. DATE COMPL. (Ready to prod.)

9-27-81

18. ELEVATIONS (DF, REB, RT, GR, ETC.)\*

6034' KB, 6011' GL

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD &amp; TVD

11,900

21. PLUG, BACK T.D., MD &amp; TVD

11,855 PBTD

22. IF MULTIPLE COMPL., HOW MANY\*

23. INTERVALS DRILLED BY

ROTARY TOOLS

0-TD

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)\*

Wasatch- 10,770'-10,780', 10,752'-10,758', 10,682'-10,668', 10,670'-10,674',  
10,658'-10,662', 10,640'-10,648', 10,626'-10,630', 10,606'-10,618',  
10,564'-10,567'

25. WAS DIRECTIONAL SURVEY MADE

26. TYPE ELECTRIC AND OTHER LOGS RUN

DIL/SFL, CNFD, BHC, CPL, G/CCL/CBL, Temp Spinner, State Temp Survey

27. WAS WELL CORED

NO

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
20"		50'			
9 5/8"	36	1502'	14 3/4"	650 SXS	
7"	29, 26	9900'	8 3/4"	850 SXS	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
5"	9594.66	11,897	325		2 7/8	9708	9397'

31. PERFORATION RECORD (Interval, size and number)

See Attached Sheet

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
See Attached Sheet	

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
8-25-81		Flowing				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
9-27-81	24 hrs	50/64"	→ 268	268	365	5	1362
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
100psi		→	268	365	5	45.5	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Currently being flared pending Sales Contract.

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

List of Perforations and Acid Jobs.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED E A McNamee TITLE Area Engineer

DATE Oct. 22, 1981

\* (See Instructions and Spaces for Additional Data on Reverse Side)







1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

## Water Analysis Report

Field :	Newfield	Sample Date :	4/18/2010
County :		Formation :	
Location :	FENCELINE 2-23-8-16	Rock Type :	
Lab ID :		Depth :	Analysed Date: 1/5/2011
Comments :			

CATIONS	mg/l		Measured	Calculated		ANIONS	mg/l
Potassium	42.8	Total Dissolve Solid	17205.00	0.00		Sulfate	10.0
Sodium	6,776.3	Total Hardness		29.93		Chloride	10,000.0
Calcium	8.2	PH	8.27	0.00		Carbonate	0.0
Magnesium	2.3	Total H2S aq	0.00	0.00		Bicarbonate	878.4
Iron	1.2	Manganese	1.38			Bromide	0.0
Barium	13.0	PO4 Residual	0.00			Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	-			Hydroxide	0.0
<b>SUM +</b>	<b>6,843.8</b>	APB Vials Turned	-			<b>SUM -</b>	<b>10,888.4</b>

Initial(BH)	Final(WH)
Saturation Index values	
Calcite (CaCO <sub>3</sub> )	
-0.36	-0.48
Barite (BaSO <sub>4</sub> )	
0.12	0.54
Halite (NaCl)	
-3.01	-2.96
Gypsum	
-4.34	-4.35
Hemihydrate	
-4.90	-5.11
Anhydrite	
-4.32	-4.59
Celestite	
0.00	0.00
Iron Sulfide	
0.00	0.00
Zinc Sulfide	
0.00	0.00
Calcium fluoride	
0.00	0.00
Iron Carbonate	
0.74	0.46
Inhibitor needed (mg/L)	
Calcite	NTMP
0.00	0.00
Barite	BHPMP
0.00	0.00



Lab Manager: Andrea Craig  
Analysis by:

Exhibit F-1





1465 East 1650 south Vernal UT 84078 (435) 789-2069 www.nalco.com

## Water Analysis Report

Field :	Barrett	Sample Date :	8/16/2010
County :		Formation :	
Location :	Prickly Pear Fed #12-24-12-14	Rock Type :	
Lab ID :		Depth :	Analysed Date: 2/16/2011

Comments :

CATIONS	mg/l		Measured	Calculated		ANIONS	mg/l
Potassium	356.5	Total Dissolve Solid	48046.00	0.00		Sulfate	1,040.0
Sodium	15,909.1	Total Hardness		6226.52		Chloride	27,900.0
Calcium	1,913.0	PH	6.79	0.00		Carbonate	0.0
Magnesium	352.2	Total H2S aq	0.00	0.00		Bicarbonate	1,220.0
Iron	83.4	Manganese	0.12			Bromide	0.0
Barium	4.0	PO4 Residual	0.00			Organic Acids	0.0
Strontium	0.0	SRB Vials Turned	0.00			Hydroxide	0.0
<b>SUM +</b>	<b>18,618.2</b>	APB Vials Turned	0.00			<b>SUM -</b>	<b>30,160.0</b>

Initial(BH) Final(WH)

Saturation Index values

Calcite (CaCO<sub>3</sub>)

2.01 0.86

Barite (BaSO<sub>4</sub>)

0.70 1.82

Halite (NaCl)

-2.08 -2.15

Gypsum

-0.20 -0.42

Hemihydrate

0.85 -1.21

Anhydrite

1.28 -0.75

Celestite

0.00 0.00

Iron Sulfide

0.00 0.00

Zinc Sulfide

0.00 0.00

Calcium fluoride

0.00 0.00

Iron Carbonate

1.81 1.12





Inhibitor needed (mg/L)

Calcite NTMP

105.51 0.00

Barite BHPMP

8.91 0.65



Lab Manager: Andrea Craig  
Analysis by:

Exhibit F-2

# Production Water Report and Scaling Tendencies

Creg Wilkins

12/17/2003

Version : 947

Analysis by : **Creg Wilkins**

Field :

County : **Uintah**

Lab ID# : **El Paso Production**

Sample Date : **13-Apr-09**

Location : **2-9B4**

Formation :

Depth :

Rock Type:

Porosity:

Permeability:

INPUT Sample Temp °F : **60.0**

INPUT Downhole Temp °F : **125.0**

INPUT Sample Press : **6.0**

INPUT sample pH, su **10.00**

Input mole % CO<sub>2</sub> **0.04**

pH resulting from CO<sub>2</sub> **10.02**

Calc Carbon Dioxide (Aq), mg/L **0.2**

Carbon Dioxide, CO<sub>2</sub> mg/L **0.0**

Total Sulfide, mg/L **6.0**

Dissolved Oxygen, ppm

Dissolved Oxygen, ppb **0.0**

INPUT TDS @180 °C, mg/L **54,491**

Calc TDS (less CO<sub>2</sub>), mg/L **54,491**

INPUT Resistivity @ 68°F **0.150**

Calculated Resistivity @ 68°F **0.150**

Input Conductivity, µmhos/cm **66,667**

Calc Cond@25 °C, µmhos/cm **66,667**

INPUT Density @ STP, g/mL **1.039**

Calc Density @STP, g/mL **1.039**

MicroBiological - # of bottles turned

SRBs : **( 1 )**

Aerobic Bacteria : **( 1 )**

**K<sup>+</sup>** **172.0**

**Na<sup>+</sup>** **20,990.9**

**Na<sup>+</sup> by Diff** **+ 0.00**

**Ca<sup>++</sup>** **60.0**

**Mg<sup>++</sup>** **378.2**

**Fe<sup>++</sup>** **3.8**

**Ba<sup>++</sup>** **125.0**

**Sr<sup>++</sup>** **0.0**

**Rr<sup>-</sup>** **0.0**

**SO<sub>4</sub><sup>=</sup>** **1,600.0**

**Cl<sup>-</sup>** **30,000.0**

**CO<sub>3</sub><sup>=</sup>** **1,560.0**

**HCO<sub>3</sub><sup>-</sup>** **1,342.0**

**OH<sup>-</sup>** **0.0**

**Organic Acid** **0.0**

Note: Organic Acids as Acetate

Titration - if values are placed in mls or digits - results will transfer to Water Report

Parameter	mls	Digits	Sample Size	Normality	Results
<b>CO<sub>2</sub></b>	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>3.636</b>	
<b>H<sub>2</sub>S</b>	<b>0</b>	<b>0.0</b>	<b>10</b>	<b>0.3998</b>	
<b>T reading</b>	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>8.0</b>	
<b>P reading</b>	<b>0</b>	<b>0.0</b>	<b>100</b>	<b>1.6</b>	
<b>Ca<sup>++</sup></b>	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
<b>THardness</b>	<b>0</b>	<b>0.0</b>	<b>50</b>	<b>0.8</b>	
<b>Cl<sup>-</sup></b>	<b>0</b>	<b>0.0</b>	<b>1</b>	<b>2.256</b>	

Comments: **Mn .45**

Exhibit F-3



(A)

PARTIAL

75 085

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE  
Sample Received on \_\_\_\_\_  
Analysis Authorization \_\_\_\_\_

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒

WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL NO.

2-2785 Sec 27, T2S, R5W (USM) DUCHESNE Co.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2817 TO 2860 LEVEL.

SUPPLY OWNED BY: \_\_\_\_\_

PRESENT USE OF SUPPLY: \_\_\_\_\_

PROPOSED USE OF SUPPLY: \_\_\_\_\_

SAMPLE COLLECTED BY: CLEON FREIGHT, OIL & GAS DIV. DATE: \_\_\_\_\_

REPORT RESULTS TO: R. HINSHAW RHT PHONE: \_\_\_\_\_

Address: BLDG 72.

DO NOT WRITE BELOW DOUBLE LINE

RESULTS OF ANALYSIS

Turbidity	J.T.U.	Iron (total) as Fe	mg/l
Conductivity	micromhos/cm	Iron in filtered sample as Fe	mg/l
pH	9.70	Lead as Pb	mg/l
Total Dissolved Solids	15240 181340	Magnesium as Mg	mg/l
Alkalinity (total) as CaCO <sub>3</sub>	2790	Manganese as Mn	mg/l
Aluminum as Al		Mercury as Hg	mg/l
Arsenic as As		Nitrate as N	mg/l
Barium as Ba		Nitrite as N	mg/l
Bicarbonate as HCO <sub>3</sub>	3500	Phosphate as PO <sub>4</sub>	mg/l
Boron as B		Phenols as Phenol	mg/l
Cadmium as Cd		Potassium as K	mg/l
Calcium as Ca		Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>		Silica as SiO <sub>2</sub>	mg/l
Chloride as Cl	27.25	Silver as Ag	mg/l
Chromium (hexavalent) as Cr		Sodium as Na	7055 mg/l
Copper as Cu		Sulfate as SO <sub>4</sub>	2220 mg/l
Cyanide as CN		Surfactant as MBAS	mg/l
Fluoride as F		Zinc as Zn	0.04 mg/l
Hardness (total) as CaCO <sub>3</sub>	10	Total Alpha	pci/l
Hydroxide as OH		Total beta	pci/l
Ammonia N as NH <sub>3</sub>			nci/l
			mg/l

Exhibit G1-A



PARTIAL

75 086

PLEASE NOTE: Sample cannot be analysed until all blanks are filled in (Slip must accompany sample)

STATE OF UTAH  
DEPARTMENT OF SOCIAL SERVICES  
DIVISION OF HEALTH  
44 MEDICAL DRIVE  
SALT LAKE CITY, UTAH 84113

DO NOT WRITE HERE JAN. 16 1975  
Sample Received on \_\_\_\_\_  
Analysis Authorization \_\_\_\_\_

WATER SAMPLE FOR CHEMICAL ANALYSIS ☒  
WATER SAMPLE FOR RADIOLOGIC ANALYSIS ☐

SAMPLE COLLECTED FROM: (check one)

Stream ☐

Spring ☐

Well ☒

City or Town water distribution system ☐

Other ☐

(describe) WASTE WATER INJECTION WELL

EXACT DESCRIPTION OF SAMPLING POINT: (see note on reverse side) WELL No.

2-27 B5 SEC 27, T2S, R5W (USM) DUCHESSNE CO.

STATE ENGINEER'S APPLICATION OR CLAIM NO. FROM PERFORATIONS AT 2088 TO 2383 LEVEL

SUPPLY OWNED BY: \_\_\_\_\_

PRESENT USE OF SUPPLY: \_\_\_\_\_

PROPOSED USE OF SUPPLY: \_\_\_\_\_

SAMPLE COLLECTED BY: CLEAN FIGHT, OIL & GAS DIV. DATE: \_\_\_\_\_

REPORT RESULTS TO: R. WINSLOW RIA PHONE: \_\_\_\_\_

Address: BLDG 72

DO NOT WRITE BELOW DOUBLE LINE

RESULTS OF ANALYSIS

Turbidity	J.T.U.	Iron (total) as Fe	mg/l
Conductivity <u>27800</u>	micromhos/cm	Iron in filtered sample as Fe	mg/l
pH <u>7.00</u>		Lead as Pb	mg/l
Total Dissolved Solids <u>17500</u>	<u>17560</u>	Magnesium as Mg	mg/l
Alkalinity (total) as CaCO <sub>3</sub> <u>4428</u>	mg/l	Manganese as Mn	mg/l
Aluminum as Al	mg/l	Mercury as Hg	mg/l
Arsenic as As	mg/l	Nitrate as N	mg/l
Barium as Ba	mg/l	Nitrite as N	mg/l
Bicarbonate as HCO <sub>3</sub>	mg/l	Phosphate as PO <sub>4</sub>	mg/l
Boron as B	mg/l	Phenols as Phenol	mg/l
Cadmium as Cd	mg/l	Potassium as K	mg/l
Calcium as Ca	mg/l	Selenium as Se	mg/l
Carbonate as CO <sub>3</sub>	mg/l	Silica as SiO <sub>2</sub>	mg/l
Chloride as Cl	<u>8000</u> mg/l	Silver as Ag	mg/l
Chromium (hexavalent) as Cr	mg/l	Sodium as Na	<u>7000</u> mg/l
Copper as Cu	mg/l	Sulfate as SO <sub>4</sub>	<u>500</u> mg/l
Cyanide as CN	mg/l	Surfactant as MBAS	mg/l
Fluoride as F	mg/l	Zinc as Zn	mg/l
Hardness (total) as CaCO <sub>3</sub> <u>176</u>	mg/l	Total Alpha	pci/l
Hydroxide as OH	mg/l	Total beta	pci/l
Ammonia N as NH <sub>3</sub>			i/l
			mg/l

Exhibit G-B



# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

(801) 722-2254

LABORATORY NUMBER W-2129

SAMPLE TAKEN \_\_\_\_\_

SAMPLE RECEIVED 4-18-75

RESULTS REPORTED 4-18-75

## SAMPLE DESCRIPTION

COMPANY Husky Oil Co.

LEASE \_\_\_\_\_

FIELD NO. Russell

WELL NO. 2-32B4

FIELD Altamont COUNTY Duchesne STATE Utah

SAMPLE TAKEN FROM \_\_\_\_\_

PRODUCING FORMATION Duchesne River - Uinta TOP 2548-2558 <sup>3726'</sup>

REMARKS \_\_\_\_\_

SAMPLE TAKEN BY Warren Johnston

## CHEMICAL AND PHYSICAL PROPERTIES

SPECIFIC GRAVITY @60/60° F. 1.0146 pH 8.28 RES. 0.30 OHM METERS @ 77°F


TOTAL HARDNESS 1155.47 mg/L as CaCO<sub>3</sub>

TOTAL ALKALINITY 360.0 mg/L as CaCO<sub>3</sub>


CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca++	273.0	13.65		
MAGNESIUM - Mg++	114.0	9.34		
SODIUM - Na+	8450.0	367.39		
BARIUM (INCL. STRONTIUM) - Ba++	10.6	0.15		
TOTAL IRON - Fe++ AND Fe+++	2.55	0.09	390.62	
BICARBONATE - HCO <sub>3</sub> <sup>-</sup>	360.0	5.90		
CARBONATE - CO <sub>3</sub> <sup>-</sup>	0	0		
SULFATE - SO <sub>4</sub> <sup>-</sup>	1500.0	31.25		
CHLORIDE - CL <sup>-</sup>	11695.3	329.45	366.69	
TOTAL DISSOLVED SOLIDS	20120.			

## MILLEQUIVALENTS PER LITER

LOGARITHMIC



STANDARD



ANALYST \_\_\_\_\_

CHECKED \_\_\_\_\_

Exhibit G2-A



# LITE RESEARCH LABORATORIES

P.O. Box 119

Fort Duchesne, Utah 84026

(801) 722-2254

LABORATORY NUMBER W-2123  
SAMPLE TAKEN 4-17-75  
SAMPLE RECEIVED 4-17-75  
RESULTS REPORTED 4-17-75

## SAMPLE DESCRIPTION

COMPANY Husky Oil LEASE Russell FIELD NO. 2-32B4  
FIELD Altamont COUNTY Duchesne STATE Utah  
SAMPLE TAKEN FROM Duchesne River - Uinta TOP 2464 - 2470  
PRODUCING FORMATION 2464 - 2470  
REMARKS

SAMPLE TAKEN BY


## CHEMICAL AND PHYSICAL PROPERTIES

SPECIFIC GRAVITY @60/60° F. 1.0138 pH 8.91 RES. 0.50 OHM METERS @ 77°F

TOTAL HARDNESS 254.35 mg/L as CaCO<sub>3</sub> TOTAL ALKALINITY 352.0 mg/L as CaCO<sub>3</sub>

CONSTITUENT	MILLIGRAMS PER LITER mg/L	MILLEQUIVALENTS PER LITER MEQ/L		REMARKS
CALCIUM - Ca ++	51.15	2.56		
MAGNESIUM - Mg ++	30.30	2.48		
SODIUM - Na +	4890.0	212.61		
BARIUM (INCL. STRONTIUM) - Ba ++	2.9	0.04		
TOTAL IRON - Fe ++ AND Fe +++	1.07	0.04	217.73	
BICARBONATE - HCO <sub>3</sub> --	260.0	4.26		
CARBONATE - CO <sub>3</sub> --	92.0	3.07		
SULFATE - SO <sub>4</sub> --	2600.0	54.17		
CHLORIDE - CL -	9596.2	270.32	331.82	
TOTAL DISSOLVED SOLIDS	17440.			

MILLEQUIVALENTS PER LITER



Al

Cl

Exhibit G2-B

# UNICHEM

A Division of BJ Services

P.O. Box 217  
Roosevelt, Utah 84066

Office (435) 722-5084  
Fax (435) 722-5727

Exhibit G-3

## WATER ANALYSIS REPORT

Company EL PASO Address \_\_\_\_\_ Date 5/24/01  
Source 1-36B5 Date Sampled \_\_\_\_\_ Analysis No. \_\_\_\_\_

Swab Sample	Analysis	5/24/01 8:00 mg/l(ppm)	*Meq/l
1. PH	<u>11.6</u>		
2. H <sub>2</sub> S (Qualitative)	<u>1.0</u>		
3. Specific Gravity	<u>1.060</u>		
4. Dissolved Solids	<u>66,564</u>		
5. Alkalinity (CaCO <sub>3</sub> )	CO <sub>3</sub> <u>5,400</u>	+ 30 <u>180</u>	CO <sub>3</sub>
6. Bicarbonate (HCO <sub>3</sub> )	HCO <sub>3</sub> _____	+ 61 _____	HCO <sub>3</sub>
7. Hydroxyl (OH)	OH <u>3,230</u>	+ 17 <u>190</u>	OH
8. Chlorides (Cl)	Cl <u>30,100</u>	+ 35.5 <u>848</u>	Cl
9. Sulfates (SO <sub>4</sub> )	SO <sub>4</sub> <u>60</u>	+ 48 <u>0</u>	SO <sub>4</sub>
10. Calcium (Ca)	Ca <u>1,600</u>	+ 20 <u>80</u>	Ca
11. Magnesium (Mg)	Mg <u>0</u>	+ 12.2 <u>0</u>	Mg
12. Total Hardness (CaCO <sub>3</sub> )	<u>4,000</u>		
13. Total Iron (Fe)	<u>15.0</u>		
14. Manganese	<u>0.9</u>		
15. Phosphate Residuals			

\*Milli equivalents per liter

### PROBABLE MINERAL COMPOSITION

80	Ca	←	HCO <sub>3</sub>	370
0	Mg	→	SO <sub>4</sub>	0
1,138	Na	→	Cl	848

Compound	Equlv. Wt.	X	Meq/l	=	Mg/l
Ca(HCO <sub>3</sub> ) <sub>2</sub>	81.04	<u>80</u>			<u>6,483</u>
CaSO <sub>4</sub>	88.07				
CaCl <sub>2</sub>	55.50				
Mg(HCO <sub>3</sub> ) <sub>2</sub>	73.17				
MgSO <sub>4</sub>	80.19				
MgCl <sub>2</sub>	47.82				
NaHCO <sub>3</sub>	84.00	<u>290</u>			<u>24,360</u>
Na <sub>2</sub> SO <sub>4</sub>	71.03				
NaCl	58.48	<u>848</u>			<u>49,574</u>

#### Saturation Values

CaCO <sub>3</sub>	13 Mg/l
CaSO <sub>4</sub> · 2H <sub>2</sub> O	2,090 Mg/l
MgCO <sub>3</sub>	103 Mg/l

#### Distilled Water 20°C

REMARKS Resistivity = 0.19 ohms/meter @ 76 degrees F 75 bbls recovered

Ammonia 380 ppm



A Procter & Gamble Co.

P.O. Box 217  
Roosevelt, Utah 84066

Office (801) 722-5066  
Fax (801) 722-5727

## WATER ANALYSIS REPORT

COMPANY Genesis Production Company ADDRESS 1600 Stout St. #720 DATE: 10-14  
Denver CO 80202  
SOURCE Sample #2 Blue Bench 1-13 CS DATE SAMPLED \_\_\_\_\_ ANALYSIS NO. \_\_\_\_\_

Analysis

7.9

1. PH

2. H<sub>2</sub>S (Qualitative)

3. Specific Gravity

4. Dissolved Solids

5. Suspended Solids

6. Anaerobic Bacterial Count CI C/MI

7. Methyl Orange Alkalinity (CaCO<sub>3</sub>)

8. Bicarbonate (HCO<sub>3</sub>)

9. Chlorides (Cl)

10. Sulfates (SO<sub>4</sub>)

11. Calcium (Ca)

12. Magnesium (Mg)

13. Total Hardness (CaCO<sub>3</sub>)

14. Total Iron (Fe)

15. Barium (Qualitative)

16. Phosphate Residuals

Mg/l (ppm)

\*Meq/l

- Exhibit G4 -

47,585

HCO <sub>3</sub>	3,540	÷61	58	HCO <sub>3</sub>
Cl	26,000	÷35.5	732	Cl
SO <sub>4</sub>	90	÷48	2	SO <sub>4</sub>
Ca	360	÷20	18	Ca
Mg	230	÷12.2	15	Mg
1,850				
4.0				

\*Milli equivalents per liter

### PROBABLE MINERAL COMPOSITION

18	Ca	←	HCO <sub>3</sub>	58
19	Mg	→	SO <sub>4</sub>	2
755	Na	→	Cl	732

Saturation Values

Distilled Water 20°C

Ca CO<sub>3</sub>

13 Mg/l

Ca SO<sub>4</sub> · 2H<sub>2</sub>O

2,090 Mg/l

Mg CO<sub>3</sub>

103 Mg/l

Compound	Eqv. Wt.	X	Meq/l	=	Mg/l
Ca (HCO <sub>3</sub> ) <sub>2</sub>	81.04		18		1458
Ca SO <sub>4</sub>	68.07				
Ca Cl <sub>2</sub>	55.50				
Mg (HCO <sub>3</sub> ) <sub>2</sub>	73.17		19		1390
Mg SO <sub>4</sub>	60.19				
Mg Cl <sub>2</sub>	47.62				
Na HCO <sub>3</sub>	84.00		21		1764
Na <sub>2</sub> SO <sub>4</sub>	71.03		2		142
Na Cl	58.46		732		42,793

REMARKS Swab sample from injection zone.

Landowner List- IWM SWD 2-6 C4

— Exhibit H

El Paso E&P Co. LP  
PO Box 154  
Houston, TX 77001

Pure Water Properties LLC  
PO Box 982993  
Park City, UT 84098

Graves, Ceclia E.  
7824 Woodhall Ave.  
Conoga Park, CA 91304

Kozar, Julian  
Amber Financial Group (MPO)  
11415 W. Bernardo Ct.  
San Diego, CA 92127

Young, Harrison L.  
PO Box 3560  
Running Springs, CA 92382

West, John R. Trustee  
1518 Homecoming Ave  
South Jordan, UT 84095

Barraza, Yesenia E. (J/T)  
900 W. Bitner Rd #B-32  
Park City, UT 84098

Preciado, Alvaro III  
Amber Financial Group (MPO)  
11415 W. Bernardo Ct.  
San Diego, CA 92127

Berry, Lee B/Jan A Trustees  
3410 Palm Grove Dr.  
Lake Havasu City, AZ 86404

Hewett, Chester A.  
PO Box 313  
Sunland, CA 91041

Miya, Hisa/Nancy Trustee  
11916 Aneta St.  
Culver City, CA 90230

Miya, Kazu  
12112 Havelock Ave  
Culver City CA 90230

Miller, Tressa M  
1590 Cumbre Rd.  
Paso Robles, CA 93446

Duchesne County  
PO Box 910  
Duchesne, UT 84021

— Exhibit I —


BEFORE THE DOGM in and for the STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF IWM SEEKING  
FOR ADMINISTRATIVE APPROVAL,  
PURSUANT TO RULE C-11, AUTHORIZING THE CONVERSION OF A PREVIOUSLY  
PLUGGED AND ABANDONED WELL (THE GERITZ-MURPHY 1-6 C4) TO AN INJECTION  
WELL AND THE UNDERGROUND DISPOSAL OF  
WATER PRODUCED AS A BY PRODUCT OF OIL AND GAS  
PRODUCTION

CERTIFICATE of MAILING

State of Utah  
County of Duchesne

Robert L. Ballou, Agent for applicant, Integrated Water Management, deposes and affirms that on January 19, 2012 he caused to be deposited in the US mail, copies of the application as directed by the DOGM for the above entitled matter to the list referred to as Exhibit "H", and that the addresses given in that exhibit are correct to the best of the affiant's information and belief; such exhibit includes all lease holders, offset operators and surface owners within a 1/2 mile radius of the proposed SWD described in the application.




Robert L. Ballou PG -Consultant

Subscribed and sworn to before me this 19 day of January 2012.



My commission expires: 09/13/15







GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director


## ONE YEAR UNDERGROUND INJECTION CONTROL PERMIT Cause No. UIC-378.1

**Operator:** Integrated Water Management, LLC  
**Well:** IWM SWD 3-30 B4  
**Location:** Section 30, Township 2 South, Range 4 West, USM  
**County:** Duchesne  
**API No.:** 43-013-50753  
**Well Type:** Saltwater Disposal

### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on **October 26, 2011**
2. Maximum Allowable Injection Pressure: 736 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Lower Uinta Formation (4,063' – 5,130')
5. A Radioactive Tracer Survey is to be run one year after date of this injection approval, in order to demonstrate which perforated zones are accommodating water.
6. Maximum Cumulative Injection Volume:  $6.7 \times 10^6$  barrels; to be re-evaluated after the results of the RAT survey.
7. The off-setting well (Christman-Bland 1-31B4, 43-013-30198) shall be monitored on a weekly basis and reported to the Division monthly. In the event that pressure changes are noted, **Injection Shall Cease Immediately** and the Division shall be notified.

Approved by:

  
John Rogers  
Associate Director

03-15-2012

Date

JR/AM/js

cc: Bruce Suchomel, Environmental Protection Agency  
Duchesne County  
El Paso E&P Company  
Well File

N:\O&G Permits\Injection Permits\Integrated Water Mng

1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114 -5801

telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • [www.ogm.utah.gov](http://www.ogm.utah.gov)



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

N/a

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

N/a

7. UNIT or CA AGREEMENT NAME:

N/a

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER SWD

8. WELL NAME and NUMBER:

IWM 3-30-B4

2. NAME OF OPERATOR:

Integrated Water Management

9. API NUMBER:

4301350753

3. ADDRESS OF OPERATOR:

20250west 2000 South

CITY

Duchesne

STATE

Ut

ZIP

84021

PHONE NUMBER:

(435) 454-4646

10. FIELD AND POOL, OR WILDCAT:

Alliement

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 6130'

COUNTY: Duchesne

QTR/QR, SECTION, TOWNSHIP, RANGE, MERIDIAN: S41 30 2s 4W U

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/22/2012</u>	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: <u>6/22/2012</u>	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On June 22nd we pumped 500 Gallons of Acid followed by 90 bbls of fresh water down the 3-30 B4SWD well. We shut the well in for 11 hrs after the acid was pumped. The acid was injected into the wells perms from 4063'-5130'.

NAME (PLEASE PRINT) Nate Robinson

TITLE Operations Manager

SIGNATURE 

DATE 6/28/2012

(This space for State use only)

RECEIVED

JUN 28 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>SWD</u>	5. LEASE DESIGNATION AND SERIAL NUMBER: N/A
2. NAME OF OPERATOR: Integrated Water Management	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: Po box 430 CITY <u>Altamont</u> STATE <u>Ut</u> ZIP <u>84007</u>	7. UNIT or CA AGREEMENT NAME: PRIVATE FEE
PHONE NUMBER: (435) 454-4646	8. WELL NAME and NUMBER: IWM SWD 3-30B4
9. API NUMBER: 4301350753	10. FIELD AND POOL, OR WILDCAT: ALTAMONT

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 300' southline 800' east line

COUNTY: DUCHESNE

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESE 30 2s 4W U

STATE:


UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: <u>3/13/2013</u>	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>rat test</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Shut well in on 3-10-13 till morning of the 11th then pumped 1650 gallons of 15% acid down swd well. Left well shut in for 24 hrs then pumped approx 4000 bbls through out the night in to displace acid. morning of the 13th brought in PLS to complete the RAT survey. RAT survey has been completed, and digital results have been emailed to Ammon McDonald

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Operations Manager</u>
SIGNATURE 	DATE <u>3/13/2013</u>

(This space for State use only)

RECEIVED  
MAR 13 2013  
DIV. OF OIL, GAS & MINING

**Final - Report Number:** 820718  
**INTEGRATED WATER MANAGEMENT**  
20250 W 2000 S  
DUCHESNE UT 84021 USA  
**Sold To:** 0500068849 **Ship To:** 0500068849  
**Representative:** Joe E Meeks

**Sample Number** ACW009089  
**Date Sampled** 20-Feb-2013  
**Date Received** 21-Feb-2013  
**Date Completed** 21-Feb-2013  
**Date Authorized** 21-Feb-2013

**Analytical Report**

This sample was analyzed as received, the results being as follows:

**Sampling point:** INJECTION 3-30 B4

**Water**

43-013-50753  
2S 4W 30

Cations - Metals	Test Method	Total
Aluminum (Al)		<1.5 mg/L
Antimony (Sb)		<5 mg/L
Barium (Ba)		2.4 mg/L
Boron (B)		19 mg/L
Calcium (Ca)		150 mg/L
Calcium (CaCO <sub>3</sub> )		370 mg/L
Chromium (Cr)		<0.8 mg/L
Cobalt (Co)		0.7 mg/L
Copper (Cu)		<1.5 mg/L
Iron (Fe)		8.1 mg/L
Lead (Pb)		<5.0 mg/L
Lithium (Li)		3.1 mg/L
Magnesium (Mg)		38 mg/L
Magnesium (CaCO <sub>3</sub> )		160 mg/L
Manganese (Mn)		0.4 mg/L
Molybdenum (Mo)		<2.0 mg/L
Nickel (Ni)		<0.5 mg/L
Phosphorus (P)		7.0 mg/L
Potassium (K)		1100 mg/L
Silicon (Si)		25 mg/L
Silica (SiO <sub>2</sub> )		53 mg/L
Sodium (Na)		5400 mg/L
Sodium (CaCO <sub>3</sub> )		12000 mg/L
Strontium (Sr)		8.4 mg/L
Titanium (Ti)		<0.5 mg/L
Vanadium (V)		<0.5 mg/L
Zinc (Zn)		<0.5 mg/L
Total Hardness (CaCO <sub>3</sub> )		530 mg/L

Alkalinity	Test Method	Total
Bicarbonate (CaCO <sub>3</sub> )		2700 mg/L
Bicarbonate (HCO <sub>3</sub> )		3300 mg/L

**RECEIVED**

**MAR 13 2013**

**DIV. OF OIL, GAS & MINING**



Authorized by Tasia D Hamann

**Final - Report Number:** 820718

**INTEGRATED WATER MANAGEMENT**

20250 W 2000 S

DUCHESNE UT 84021 USA

**Sold To:** 0500068849 **Ship To:** 0500068849

**Representative:** Joe E Meeks

<b>Sample Number</b>	ACW009089
<b>Date Sampled</b>	20-Feb-2013
<b>Date Received</b>	21-Feb-2013
<b>Date Completed</b>	21-Feb-2013
<b>Date Authorized</b>	21-Feb-2013

**Analytical Report**

This sample was analyzed as received, the results being as follows:

**Sampling point:** INJECTION 3-30 B4

43-013-50753

Physical	Test Method	Total
Conductivity at 25°C		28000 µS/cm
Resistivity		0.356 Ohms-M
Total Cations		6687 mg/L
Total Anions		12077.2 mg/L
pH @ 25°C		7.9 pH

Field Analysis	Test Method	Total
WELLHEAD		

Inorganic Constituents	Test Method	Total
Chloride (Cl)		8900 mg/L
Sulfate (SO4)		480 mg/L

Product Residuals	Test Method	Total
04VD008		640 mg/L

**RECEIVED**

**MAR 13 2013**

**DIV. OF OIL, GAS & MINING**



Authorized by Tasia D Hamann



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

## ONE YEAR UNDERGROUND INJECTION CONTROL PERMIT Cause No. UIC-378.1

**Operator:** Integrated Water Management, LLC

**Well:** IWM SWD 3-30 B4

**Location:** Section 30, Township 2 South, Range 4 West, USM

**County:** Duchesne


**API No.:** 43-013-50753

**Well Type:** Saltwater Disposal

### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on **October 26, 2011.**
2. Maximum Allowable Injection Pressure: 736 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Lower Uinta Formation (4,063' – 5,130')
5. A Radioactive Tracer Survey is to be run one year after date of this injection approval, in order to demonstrate which perforated zones are accommodating water.
6. Maximum Cumulative Injection Volume:  $6.7 \times 10^6$  barrels; to be re-evaluated after the results of the RAT survey.
7. The off-setting well (Christman-Bland 1-31B4, 43-013-30198) shall be monitored on a weekly basis and reported to the Division monthly. In the event that pressure changes are noted, **Injection Shall Cease Immediately** and the Division shall be notified.

Approved by:

  
John Rogers  
Associate Director

03-15-2013

Date

JR/AM/js

cc: Bruce Suchomel, Environmental Protection Agency  
Duchesne County  
EP Energy E&P Company  
Well File

N:\O&G Permits\Injection Permits\Integrated Water Mng  
1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114 -5801  
telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • [www.ogm.utah.gov](http://www.ogm.utah.gov)





GARY R. HERBERT  
Governor

SPENCER J. COX  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

## ONE YEAR UNDERGROUND INJECTION CONTROL PERMIT Cause No. UIC-378.1

**Operator:** Integrated Water Management, LLC

**Well:** IWM SWD 3-30 B4

**Location:** Section 30, Township 2 South, Range 4 West, USM

**County:** Duchesne

**API No.:** 43-013-50753

**Well Type:** Saltwater Disposal

### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on **October 26, 2011**.
2. Maximum Allowable Injection Pressure: 736 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Lower Uinta Formation (4,063' – 5,130')
5. A Radioactive Tracer Survey is to be run one year after date of this injection approval, in order to demonstrate which perforated zones are accommodating water.
6. Maximum Cumulative Injection Volume:  $6.7 \times 10^6$  barrels; to be re-evaluated after the results of the RAT survey.
7. The off-setting well (Christman Bland 1-31B4, 43-013-30198) shall be monitored on a weekly basis and reported to the Division monthly. In the event that pressure changes are noted, **INJECTION SHALL CEASE IMMEDIATELY** and the Division shall be notified.

Approved by: \_\_\_\_\_

  
John Rogers  
Associate Director

03-15-2014  
Date

JR/AM/js

cc: Bruce Suchomel, Environmental Protection Agency  
Duchesne County  
EP Energy E&P Company  
Well File

N:\O&G Permits\Injection Permits\Integrated Water Mng  
1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114-5801  
telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • [www.ogm.utah.gov](http://www.ogm.utah.gov)



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> 3691
<b>1. TYPE OF WELL</b> Water Disposal Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> INTEGRATED WATER MANAGEMENT LLC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> PO Box 430, Altamont, UT, 84001		<b>8. WELL NAME and NUMBER:</b> IWM SWD 3-30 B4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0300 FSL 0800 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U		<b>9. API NUMBER:</b> 43013507530000
<b>PHONE NUMBER:</b> 435-454-4646 Ext		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/3/2016  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIT passed with Success witnessed by Ammon McDonald 11-30-2016 leaving 500 mPSI on Backside of tubing. Will monitor daily		
<b>Accepted by the          Utah Division of          Oil, Gas and Mining          FOR RECORD ONLY          December 01, 2016</b>		
<b>NAME (PLEASE PRINT)</b> Nathan Robinson	<b>PHONE NUMBER</b> 435 454-4646	<b>TITLE</b> Director
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/30/2016	



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>SWD 3-30B4</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: IWM		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY Altamont STATE UT ZIP 84001		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (435) 454-4646		8. WELL NAME and NUMBER: IWM SWD 3-30 B4
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		9. API NUMBER: 4301350753
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SESE 0 02s 04W U</u>		10. FIELD AND POOL, OR WILDCAT: Altamont
		COUNTY: <u>Duchesne</u>
		STATE: <u>UTAH</u>

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>11/30/2016</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>5 year MIT</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIT passed with success witnessed by Ammon McDonald 11-30-2016

Leaving 500 PSI on Backside of tubing. Will monitor and record Daily.

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Managing Director</u>
SIGNATURE 	DATE <u>11/30/2016</u>

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> 3691
		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>1. TYPE OF WELL</b> Water Disposal Well	<b>8. WELL NAME and NUMBER:</b> IWM SWD 3-30 B4	
<b>2. NAME OF OPERATOR:</b> INTEGRATED WATER MANAGEMENT LLC	<b>9. API NUMBER:</b> 43013507530000	
<b>3. ADDRESS OF OPERATOR:</b> PO Box 430, Altamont, UT, 84001	<b>PHONE NUMBER:</b> 435-454-4646 Ext	<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0300 FSL 0800 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U		<b>COUNTY:</b> DUCHESNE
		<b>STATE:</b> UTAH

11.


CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>11/3/2016</b>	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input checked="" type="checkbox"/> <b>NEW CONSTRUCTION</b>  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input type="text"/>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Construction of 8 new tanks on the secondary containment berm in line west of the existing triplex feed tank to add additional storage capacity.

Approved by the  
 December 06, 2016  
 Oil, Gas and Mining

Date: \_\_\_\_\_  
 By: 

<b>NAME (PLEASE PRINT)</b> Nathan Robinson	<b>PHONE NUMBER</b> 435 454-4646	<b>TITLE</b> Director
<b>SIGNATURE</b> N/A		<b>DATE</b> 11/29/2016



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Disposal</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: IWM		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY Altamont STATE UT ZIP 84001		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (435) 454-4646		8. WELL NAME and NUMBER: IWM SWD 3-30 B4
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0300 FSL 0800 FEL		9. API NUMBER: 4301350753
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESE 30 02S 04W U		10. FIELD AND POOL, OR WILDCAT: Altamont
COUNTY: Duchesne		STATE: UTAH

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>11/3/2016</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input checked="" type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

## 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Construction of 8 new tanks on the secondary containment berm in line west of the existing triplex feed tank to add additional storage capacity.

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Facility Manager</u>
SIGNATURE 	DATE <u>11/6/2016</u>

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperfing the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> 3691
<b>1. TYPE OF WELL</b> Water Disposal Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> INTEGRATED WATER MANAGEMENT LLC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> PO Box 430, Altamont, UT, 84001		<b>8. WELL NAME and NUMBER:</b> IWM SWD 3-30 B4
<b>PHONE NUMBER:</b> 435-454-4646 Ext		<b>9. API NUMBER:</b> 43013507530000
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0300 FSL 0800 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U		<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
		<b>COUNTY:</b> DUCHESNE
		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 12/12/2016  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input checked="" type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION         </div> </div> <div style="margin-top: 10px;">           OTHER: <input style="width: 100px;" type="text"/> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. 2 tots of acid will be put down hole on 12/26/2016 it will sit for 12 hours and then flowback. 4 totes of acid will be put down hole on Tuesday 12/27/2016 and will sit for 12 hours and then flowback. Then the hole will be flushed with brine water		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> January 04, 2017		
<b>NAME (PLEASE PRINT)</b> Nathan Robinson	<b>PHONE NUMBER</b> 435 454-4646	<b>TITLE</b> Director
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/23/2016	



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Disposal</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: <b>Integrated Water Managment LLC</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		8. WELL NAME and NUMBER: <b>IWM SWD 3-30 B-4</b>
5. PHONE NUMBER:		9. API NUMBER: <b>4301350753</b>
6. FIELD AND POOL, OR WILDCAT: <b>Altamont</b>		10. FIELD AND POOL, OR WILDCAT: <b>Altamont</b>

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: **SESE 30 02S 04W U**COUNTY: **Duchesne**STATE: **UTAH**

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>12/26/2016</u>	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2 tots of acid will be put down hole on 12/26/2016 it will sit for 12 hours and then flowback.

4 totes of acid will be put down hole on Tuesday 12/27/2016 and will sit for 12 hours and then flowback.

Then the hole will be flushed with brine water

NAME (PLEASE PRINT) Nate Robinson TITLE Managing Director

SIGNATURE  DATE 12/22/2016

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL		5. LEASE DESIGNATION AND SERIAL NUMBER:
OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Disposal</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR:		7. UNIT or CA AGREEMENT NAME:
<u>Integrated Water Managment LLC</u>		8. WELL NAME and NUMBER:
3. ADDRESS OF OPERATOR:		9. API NUMBER:
PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>		4301350753
4. LOCATION OF WELL		10. FIELD AND POOL, OR WILDCAT:
FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		<u>Altamont</u>

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESE 30 02S 04W UCOUNTY: DuchesneSTATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
Approximate date work will start:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<u>12/28/2016</u>	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
Date of work completion:	<input checked="" type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change out tubing from 3.5 inches to 4.5 inch tubing. Tubing will be a11.6 #P110 LTC.

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Managing Director</u>
SIGNATURE _____	DATE <u>12/22/2016</u>

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:


- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 3691
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Water Disposal Well	8. WELL NAME and NUMBER: IWM SWD 3-30 B4	
2. NAME OF OPERATOR: INTEGRATED WATER MANAGEMENT LLC	9. API NUMBER: 43013507530000	
3. ADDRESS OF OPERATOR: PO Box 430, Altamont, UT, 84001	PHONE NUMBER: 435-454-4646 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0300 FSL 0800 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U	COUNTY: DUCHESNE	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>12/28/2016</b>	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input checked="" type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change out tubing from 3.5 inches to 4.5 inch tubing. Tubing will be a 11.6 #P110 LTC.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: January 04, 2017

By: 

Please Review Attached Conditions of Approval

NAME (PLEASE PRINT) Nathan Robinson	PHONE NUMBER 435 454-4646	TITLE Director
SIGNATURE N/A		DATE 12/23/2016



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43013507530000**

**MIT will need to be conducted once work is completed. NOTE: Per discussion 1/3/2017, this change of plan will more than likely not take place and another request will be made to isolate the casing issues below 3600'.**



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Disposal</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: <b>Integrated Water Managment LLC</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		8. WELL NAME and NUMBER: <b>IWM SWD 3-30 B-4</b>
5. PHONE NUMBER:		9. API NUMBER: <b>4301350753</b>
6. FIELD AND POOL, OR WILDCAT: <b>Altamont</b>		10. FIELD AND POOL, OR WILDCAT: <b>Altamont</b>

COUNTY: **Duchesne**STATE: **UTAH**

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>12/26/2016</u>	<input checked="" type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2 tots of acid will be put down hole on 12/26/2016 it will sit for 12 hours and then flowback.

4 totes of acid will be put down hole on Tuesday 12/27/2016 and will sit for 12 hours and then flowback.

Then the hole will be flushed with brine water

NAME (PLEASE PRINT) Nate Robinson TITLE Managing Director

SIGNATURE  DATE 12/22/2016

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Water Disposal</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: <u>Integrated Water Managment LLC</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>UT</u> ZIP <u>84001</u>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		8. WELL NAME and NUMBER: <u>IWM SWD 3-30 B-4</u>
PHONE NUMBER:		9. API NUMBER: <u>4301350753</u>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SESE 30 02S 04W U</u>		10. FIELD AND POOL, OR WILDCAT: <u>Altamont</u>
COUNTY: <u>Duchesne</u>		STATE: <u>UTAH</u>

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: <u>12/28/2016</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input checked="" type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change out tubing from 3.5 inches to 4.5 inch tubing. Tubing will be a11.6 #P110 LTC.

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Managing Director</u>
SIGNATURE _____	DATE <u>12/22/2016</u>

(This space for State use only)



## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:


- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 3691
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Water Disposal Well	8. WELL NAME and NUMBER: IWM SWD 3-30 B4	
2. NAME OF OPERATOR: INTEGRATED WATER MANAGEMENT LLC	9. API NUMBER: 43013507530000	
3. ADDRESS OF OPERATOR: PO Box 430, Altamont, UT, 84001	PHONE NUMBER: 435-454-4646 Ext	9. FIELD and POOL or WILDCAT: ALTAMONT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0300 FSL 0800 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U	COUNTY: DUCHESNE	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>1/9/2017</b>  <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input checked="" type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input checked="" type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

1. Attempt to push fish to bottom was unsuccessful. The fish is an arrow set packer and 2 jts of 3 1/2" tbg. We was not able to get the fish top past 4171'. IWM will have to leave the fish in the hole - other options is. 2. Fish moved to only 4171' 3. Recommendation moving forward for IWM 4. POOH W/ TBG & BHA. 5. PU and RIH W 550' of 9.3# 3 1/2" 8rd tubing X-OVER RIH W/ Packer & 3500' 4 1/2" P-110 11.6# tubing set packer @ 3500' land tubing EOT with 3 1/2" stinger will be 4050'. 6. ND BOP NU WH 7. RD workover rig install flow lines start injecting. 8. Note the stinger will help keep the bad 7" casing from collapsing in. IWM should be able to run the injection well until a new well is drilled .Then possible side track this well and have two injection wells in good shape. 9. NOTE The collapse of 9.3# P-110 is 13530 PSI the J-55 9.3# that was in the well is 7400 PSI

NAME (PLEASE PRINT) Nathan Robinson	PHONE NUMBER 435 454-4646	TITLE Director
SIGNATURE N/A		DATE 1/10/2017



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>WDW</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: <u>Integrated Water Managment LLC</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: PO Box 430 CITY <u>Altamont</u> STATE <u>Ut</u> ZIP <u>84001</u>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>0300 FSL 0800FEL</u>		8. WELL NAME and NUMBER: <u>IWM SWD 3-30 B-4</u>
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <u>SESE 30 02S 04W U</u>		9. API NUMBER: <u>4301350753</u>
COUNTY: <u>Duchesne</u>		10. FIELD AND POOL, OR WILDCAT: <u>Altamont</u>
STATE: <u>UTAH</u>		

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>1/9/2016</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input checked="" type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Revised #2

Procedure Moving Ahead On the Stella 3-30 B4 SWD

1. Attempt to push fish to bottom was unsuccessful. The fish is an arrow set packer and 2 jts of 3 ½" tbg. We was not able to get the fish top past 4171'. IWM will have to leave the fish in the hole - other options is.

2. Fish moved to only 4171'

3. Recommendation moving forward for IWM

4. POOH W/ TBG & BHA.

5. PU and RIH W 550' of 9.3# 3 ½" 8rd tubing X-OVER RIH W/ Packer & 3500' 4 ½" P-110 11.6# tubing set packer @ 3500' land tubing EOT with 3 ½" stinger will be 4050'.

6. ND BOP NU WH

7. RD workover rig install flow lines start injecting.

8. Note the stinger will help keep the bad 7" casing from collapsing in. IWM should be able to run the injection well until a new well is drilled. Then possible side track this well and have two injection wells in good shape.

9. NOTE The collapse of 9.3# P-110 is 13530 PSI the J-55 9.3# that was in the well is 7400 PSI

NAME (PLEASE PRINT) <u>Nate Robinson</u>	TITLE <u>Managing Director</u>
SIGNATURE 	DATE <u>1/9/2016</u>

(This space for State use only)

## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperforating the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> 3691
<b>1. TYPE OF WELL</b> Water Disposal Well	<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> INTEGRATED WATER MANAGEMENT LLC	<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> PO Box 430, Altamont, UT, 84001	<b>8. WELL NAME and NUMBER:</b> IWM SWD 3-30 B4
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0300 FSL 0800 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESE Section: 30 Township: 02.0S Range: 04.0W Meridian: U	<b>9. API NUMBER:</b> 43013507530000
<b>PHONE NUMBER:</b> 435-454-4646 Ext	<b>9. FIELD and POOL or WILDCAT:</b> ALTAMONT
<b>COUNTY:</b> DUCHESNE	<b>STATE:</b> UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"><input type="checkbox"/> ACIDIZE</div> <div style="width: 33%;"><input type="checkbox"/> ALTER CASING</div> <div style="width: 33%;"><input type="checkbox"/> CASING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TUBING</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL NAME</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL STATUS</div> <div style="width: 33%;"><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div style="width: 33%;"><input type="checkbox"/> CONVERT WELL TYPE</div> <div style="width: 33%;"><input type="checkbox"/> DEEPEN</div> <div style="width: 33%;"><input type="checkbox"/> FRACTURE TREAT</div> <div style="width: 33%;"><input type="checkbox"/> NEW CONSTRUCTION</div> <div style="width: 33%;"><input type="checkbox"/> OPERATOR CHANGE</div> <div style="width: 33%;"><input type="checkbox"/> PLUG AND ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> PLUG BACK</div> <div style="width: 33%;"><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div style="width: 33%;"><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div style="width: 33%;"><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div style="width: 33%;"><input type="checkbox"/> TEMPORARY ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> TUBING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> VENT OR FLARE</div> <div style="width: 33%;"><input type="checkbox"/> WATER DISPOSAL</div> <div style="width: 33%;"><input type="checkbox"/> WATER SHUTOFF</div> <div style="width: 33%;"><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div style="width: 33%;"><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div style="width: 33%;"><input type="checkbox"/> OTHER</div> </div>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	
OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

**Approved by the  
 Utah Division of  
 Oil, Gas and Mining**

**Date:** January 25, 2017

**By:**

**Please Review Attached Conditions of Approval**

<b>NAME (PLEASE PRINT)</b> Nathan Robinson	<b>PHONE NUMBER</b> 435 454-4646	<b>TITLE</b> Director
<b>SIGNATURE</b> N/A	<b>DATE</b> 1/24/2017	



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43013507530000**

**A copy of the log shall be submitted to the Division for review prior to commencing injection.**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

## SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR:		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: CITY STATE ZIP		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER:		8. WELL NAME and NUMBER:
4. LOCATION OF WELL FOOTAGES AT SURFACE:		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:
		STATE: <b>UTAH</b>

## 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	_____	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

NAME (PLEASE PRINT) \_\_\_\_\_ TITLE \_\_\_\_\_

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

(This space for State use only)



## INSTRUCTIONS

**This form shall be submitted by the operator to show the intention and/or completion of the following:**

- miscellaneous work projects and actions for which other specific report forms do not exist;
- all other work and events as identified in section 11, Type of Action, or as required by the Utah Oil and Gas Conservation General Rules, including:
  - minor deepening of an existing well bore,
  - plugging back a well,
  - recompleting to a different producing formation within an existing well bore (intent only),
  - reperfing the current producing formation,
  - drilling a sidetrack to repair a well,
  - reporting monthly the status of each drilling well.

**This form is not to be used for proposals to**

- drill new wells,
- reenter previously plugged and abandoned wells,
- significantly deepen existing wells below their current bottom-hole depth,
- drill horizontal laterals from an existing well bore,
- drill hydrocarbon exploratory holes such as core samples and stratigraphic tests.

**Use Form 3, Application for Permit to Drill (APD) for such proposals.**

**NOTICE OF INTENT** - A notice of intention to do work on a well or to change plans previously approved shall be submitted in duplicate and must be received and approved by the division before the work is commenced. The operator is responsible for receipt of the notice by the division in ample time for proper consideration and action. In cases of emergency, the operator may obtain verbal approval to commence work. Within five days after receiving verbal approval, the operator shall submit a Sundry Notice describing the work and acknowledging the verbal approval.

**SUBSEQUENT REPORT** - A subsequent report shall be submitted to the division within 30 days of the completion of the outlined work. Specific details of the work performed should be provided, including dates, well depths, placement of plugs, etc.

**WELL ABANDONMENT** - Proposals to abandon a well and subsequent reports of abandonment should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, and method of parting of any casing, liner, or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

In addition to any Sundry Notice forms submitted, **Form 8, Well Completion or Recompletion Report and Log** must be submitted to the division to report the results of the following operations:

- completing or plugging a new well,
- reentering a previously plugged and abandoned well,
- significantly deepening an existing well bore below the current bottom-hole depth,
- drilling horizontal laterals from an existing well bore,
- drilling hydrocarbon exploratory holes such as core samples and stratigraphic tests,
- recompleting to a different producing formation.

Send to:

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940